

# LOAN DOCUMENT

PHOTOGRAPH THIS SHEET

DTIC ACCESSION NUMBER

LEVEL

INVENTORY

SITE-SPECIFIC TECHNICAL...

DOCUMENT IDENTIFICATION

28 NOV 95

**DISTRIBUTION STATEMENT A**  
Approved for Public Release  
Distribution Unlimited

DISTRIBUTION STATEMENT

ACCESSION FOR	
NTIS	GRAM <input checked="" type="checkbox"/>
DTIC	TRAC <input type="checkbox"/>
UNANNOUNCED	
JUSTIFICATION	
BY	
DISTRIBUTION/	
AVAILABILITY CODES	
DISTRIBUTION	AVAILABILITY AND/OR SPECIAL
A-1	

DISTRIBUTION STAMP

DATE ACCESSIONED

DATE RETURNED

20001215 115

DATE RECEIVED IN DTIC

REGISTERED OR CERTIFIED NUMBER

PHOTOGRAPH THIS SHEET AND RETURN TO DTIC-FDAC

H  
A  
N  
D  
L  
E  
  
W  
I  
T  
H  
  
C  
A  
R  
E

DEFENSE TECHNICAL INFORMATION CENTER  
REQUEST FOR SCIENTIFIC AND TECHNICAL REPORTS

Title

AFCEE Collection

## 1. Report Availability (Please check one box)

- ☒ This report is available. Complete sections 2a - 2f.  
☐ This report is not available. Complete section 3.

2a. Number of  
Copies Forwarded

1 each

## 2b. Forwarding Date

July/2000

## 2c. Distribution Statement (Please check ONE box)

DoD Directive 5230.24, "Distribution Statements on Technical Documents," 18 Mar 87, contains seven distribution statements, as described briefly below. Technical documents MUST be assigned a distribution statement.

- ☒ DISTRIBUTION STATEMENT A: Approved for public release. Distribution is unlimited.
- ☐ DISTRIBUTION STATEMENT B: Distribution authorized to U.S. Government Agencies only.
- ☐ DISTRIBUTION STATEMENT C: Distribution authorized to U.S. Government Agencies and their contractors.
- ☐ DISTRIBUTION STATEMENT D: Distribution authorized to U.S. Department of Defense (DoD) and U.S. DoD contractors only.
- ☐ DISTRIBUTION STATEMENT E: Distribution authorized to U.S. Department of Defense (DoD) components only.
- ☐ DISTRIBUTION STATEMENT F: Further dissemination only as directed by the controlling DoD office indicated below or by higher authority.
- ☐ DISTRIBUTION STATEMENT X: Distribution authorized to U.S. Government agencies and private individuals or enterprises eligible to obtain export-controlled technical data in accordance with DoD Directive 5230.25, Withholding of Unclassified Technical Data from Public Disclosure, 6 Nov 84.

## 2d. Reason For the Above Distribution Statement (in accordance with DoD Directive 5230.24)

## 2e. Controlling Office

HQ AFCEE

2f. Date of Distribution Statement  
Determination

15 Nov 2000

## 3. This report is NOT forwarded for the following reasons. (Please check appropriate box)

- ☐ It was previously forwarded to DTIC on \_\_\_\_\_ (date) and the AD number is \_\_\_\_\_
- ☐ It will be published at a later date. Enter approximate date if known. \_\_\_\_\_
- ☐ In accordance with the provisions of DoD Directive 3200.12, the requested document is not supplied because: \_\_\_\_\_

Print or Type Name

Laura Peña

Signature

Laura Peña

Telephone

210-536-1431

(For DTIC Use Only)

AQ Number

01-03-0561

**SITE-SPECIFIC TECHNICAL REPORT  
FOR BIOSLURPER TESTING AT  
SITES UST 70/72 AND SS010,  
ROBINS AFB, GEORGIA**

**DRAFT**



**PREPARED FOR:**

**AIR FORCE CENTER FOR ENVIRONMENTAL EXCELLENCE  
TECHNOLOGY TRANSFER DIVISION  
(AFCEE/ERT)  
8001 ARNOLD DRIVE  
BROOKS AFB, TEXAS 78235-5357**

**AND**

**CEOUW  
ROBINS AFB, GEORGIA**

**28 NOVEMBER 1995**

*AQM01-03-0561*

**RECEIVED**  
DEC 01 1995

**DRAFT**

**SITE-SPECIFIC TECHNICAL REPORT (A003)**

**for**

**BIOSLURPER TESTING AT  
SITES UST 70/72 AND SS010, ROBINS AFB, GEORGIA**

**by**

**A. Leeson, J.A. Kittel, E. Drescher, and M. Wheeler**

**for**

**Mr. Patrick Haas  
U. S. Air Force Center for Environmental Excellence  
Technology Transfer Division  
(AFCEE/ERT)  
Brooks AFB, Texas 78235-5357**

**November 28, 1995**

**Battelle  
505 King Avenue  
Columbus, Ohio 43201-2693**

**Contract No. F41624-94-C-8012**

*This report is a work prepared for the United States Government by Battelle. In no event shall either the United States Government or Battelle have any responsibility or liability for any consequences of any use, misuse, inability to use, or reliance upon the information contained herein, nor does either warrant or otherwise represent in any way the accuracy, adequacy, efficacy, or applicability of the contents hereof.*

## TABLE OF CONTENTS

LIST OF TABLES .....	ii
LIST OF FIGURES .....	iii
EXECUTIVE SUMMARY .....	v
1.0 INTRODUCTION .....	1
1.1 Objectives .....	1
1.2 Testing Approach .....	2
2.0 SITE UST 70/72 .....	2
2.1 Site Description .....	2
2.2 Bioslurper Short-Term Pilot Test Methods .....	3
2.2.1 Initial LNAPL/Groundwater Measurements and Baildown Testing .....	3
2.2.2 Well Construction Details .....	3
2.2.3 Soil Gas Monitoring Point and Thermocouple Installation .....	6
2.2.4 Soil Sampling and Analysis .....	7
2.2.5 LNAPL Recovery Testing .....	7
2.2.5.1 System Setup .....	7
2.2.5.2 Initial Skimmer Pump Test .....	9
2.2.5.3 Bioslurper Pump Test .....	9
2.2.5.4 Second Skimmer Pump Test .....	9
2.2.5.5 Drawdown Pump Test .....	12
2.2.5.6 Off-Gas Sampling and Analysis .....	12
2.2.5.7 Groundwater Sampling and Analysis .....	14
2.2.6 Soil Gas Permeability Testing .....	14
2.2.7 In Situ Respiration Testing .....	14
2.3 Results .....	15
2.3.1 Baildown Test Results .....	15
2.3.2 Soil Sample Analyses .....	15
2.3.3 LNAPL Pump Test Results .....	17
2.3.3.1 Initial Skimmer Pump Test Results .....	17
2.3.3.2 Bioslurper Pump Test Results .....	17
2.3.3.3 Second Skimmer Pump Test .....	17
2.3.3.4 Drawdown Pump Test .....	21
2.3.4 Emulsion Control and Extracted Groundwater, LNAPL, and Off-Gas Analyses .....	21
2.3.5 Bioventing Analyses .....	22
2.3.5.1 Soil Gas Permeability and Radius of Influence .....	22
2.3.5.2 In Situ Respiration Test Results .....	24
2.4 Discussion .....	24
3.0 SITE SS010 .....	28
3.1 Site Description .....	28
3.2 Bioslurper Short-Term Pilot Test Methods .....	28

3.2.1	Initial LNAPL/Groundwater Measurements and Baildown Testing . . . . .	28
3.2.2	Well Construction Details . . . . .	28
3.2.3	Soil Gas Monitoring Point and Thermocouple Installation . . . . .	31
3.2.4	Soil Sampling and Analysis . . . . .	31
3.2.5	LNAPL Recovery Testing . . . . .	32
3.2.5.1	System Setup . . . . .	32
3.2.5.2	Initial Skimmer Pump Test . . . . .	33
3.2.5.3	Bioslurper Pump Test . . . . .	33
3.2.5.4	Drawdown Pump Test . . . . .	34
3.2.5.5	Off-Gas Sampling and Analysis . . . . .	34
3.2.5.6	Groundwater Sampling and Analysis . . . . .	34
3.2.6	Soil Gas Permeability Testing . . . . .	35
3.2.7	In Situ Respiration Testing . . . . .	35
3.3	Results . . . . .	36
3.3.1	Baildown Test Results . . . . .	36
3.3.2	Soil Sample Analyses . . . . .	36
3.3.3	LNAPL Pump Test Results . . . . .	36
3.3.3.1	Initial Skimmer Pump Test Results . . . . .	36
3.3.3.2	Bioslurper Pump Test Results . . . . .	39
3.3.3.3	Drawdown Pump Test . . . . .	42
3.3.4	Emulsion Control and Extracted Groundwater, LNAPL, and Off-Gas Analyses . . . . .	43
3.3.5	Bioventing Analyses . . . . .	47
3.3.5.1	Soil Gas Permeability and Radius of Influence . . . . .	47
3.3.5.2	In Situ Respiration Test Results . . . . .	47
3.4	Discussion . . . . .	47
4.0	REFERENCES . . . . .	49
APPENDIX A:	SITE-SPECIFIC TEST PLAN FOR BIOSLURPER FIELD ACTIVITIES AT ROBINS AFB, GEORGIA . . . . .	A-1
APPENDIX B:	LABORATORY ANALYTICAL REPORTS . . . . .	B-1
APPENDIX C:	SYSTEM CHECKLISTS . . . . .	C-1
APPENDIX D:	DATA SHEETS FROM THE SHORT-TERM PILOT TEST . . . . .	D-1
APPENDIX E:	SOIL GAS PERMEABILITY TEST RESULTS . . . . .	E-1
APPENDIX F:	IN SITU RESPIRATION TEST RESULTS . . . . .	F-1

#### LIST OF TABLES

Table 1.	Initial Soil Gas Compositions at Site UST 70/72, Robins AFB, GA . . . . .	6
Table 2.	Results of Baildown Testing in Monitoring Well EA-2, Site UST 70/72, Robins AFB, GA . . . . .	16

Table 3.	BTEX and TPH Concentrations in Soil Samples from Site UST 70/72, Robins AFB, GA . . . . .	16
Table 4.	Depths to Groundwater and LNAPL Prior to Each Pump Test . . . . .	18
Table 5.	Pump Test Results at Site UST 70/72, Robins AFB, GA . . . . .	18
Table 6.	Oxygen Concentrations During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA . . . . .	21
Table 7.	BTEX and TPH Concentrations in Extracted Groundwater During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA . . . . .	22
Table 8.	BTEX and TPH Concentrations in Off-Gas During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA . . . . .	23
Table 9.	BTEX Concentrations in LNAPL from Site UST 70/72, Robins AFB, GA . . . . .	23
Table 10.	C-Range Compounds in LNAPL from Site UST 70/72, Robins AFB, GA . . . . .	24
Table 11.	In Situ Respiration Test Results at Site UST 70/72, Robins AFB, GA . . . . .	27
Table 12.	Initial Soil Gas Compositions at Site SS010, Robins AFB, GA . . . . .	32
Table 13.	Results of Baildown Testing in Monitoring Wells PZ-1 and LF-1-3, Site SS010, Robins AFB, GA . . . . .	37
Table 14.	BTEX and TPH Concentrations in Soil Samples from Site SS010, Robins AFB, GA . . . . .	38
Table 15.	Depths to Groundwater and LNAPL Prior to Each Pump Test . . . . .	38
Table 16.	Pump Test Results at Site SS010, Robins AFB, GA . . . . .	39
Table 17.	Oxygen Concentrations During the Bioslurper Pump Test at Site SS010, Robins AFB, GA . . . . .	42
Table 18.	BTEX and TPH Concentrations in Extracted Groundwater During the Bioslurper Pump Test at Site SS010, Robins AFB, GA . . . . .	43
Table 19.	BTEX and TPH Concentrations in Off-Gas During the Bioslurper Pump Test at Site SS010, Robins AFB, GA . . . . .	44
Table 20.	BTEX Concentrations in LNAPL from Site SS010, Robins AFB, GA . . . . .	44
Table 21.	C-Range Compounds in LNAPL from Site SS010, Robins AFB, GA . . . . .	45
Table 22.	In Situ Respiration Test Results at Site SS010, Robins AFB, GA . . . . .	47

## LIST OF FIGURES

Figure 1.	Locations of Groundwater Monitoring Wells and Soil Gas Monitoring Points at Site UST 70/72, Robins AFB, GA . . . . .	4
Figure 2.	Schematic Diagram Illustrating Site Lithology and Construction Details of the Bioslurper Well and Soil Gas Monitoring Points at Site UST 70/72, Robins AFB, GA . . . . .	5
Figure 3.	Components of the Emulsion Control and Groundwater Treatment System Used at Site UST 70/72, Robins AFB, GA . . . . .	8
Figure 4.	Slurper Tube Placement and Valve Position for the Skimmer Pump Test . . . . .	10
Figure 5.	Slurper Tube Placement and Valve Position for the Bioslurper Pump Test . . . . .	11
Figure 6.	Slurper Tube Placement and Valve Position for the Drawdown Pump Test . . . . .	13
Figure 7.	LNAPL Recovery Versus Time During Each Pump Test at Site UST 70/72 . . . . .	19
Figure 8.	LNAPL Recovery Rate Versus Time During the Bioslurper Pump Test at Site UST 70/72 . . . . .	20
Figure 9.	Distribution of C-Range Compounds in Extracted LNAPL at Site UST 70/72, Robins AFB, GA . . . . .	25



Figure 10.	Soil Gas Pressure Change as a Function of Distance During the Soil Gas Permeability Test at Site UST 70/72 .....	26
Figure 11.	Locations of Groundwater Monitoring Wells and Soil Gas Monitoring Points at Site SS010, Robins AFB, GA .....	29
Figure 12.	Schematic Diagram Illustrating Site Lithology and Construction Details of the Bioslurper Well and Soil Gas Monitoring Points at Site SS010, Robins AFB, GA .....	30
Figure 13.	LNAPL Recovery Versus Time During Each Pump Test at Site SS010 .....	40
Figure 14.	LNAPL Recovery Rate Versus Time During the Bioslurper Pump Test at Site SS010 .....	41
Figure 15.	Distribution of C-Range Compounds in Extracted LNAPL at Site SS010, Robins AFB, GA .....	46
Figure 16.	Soil Gas Pressure Change as a Function of Distance During the Soil Gas Permeability Test at Site SS010 .....	48

## EXECUTIVE SUMMARY

This report summarizes the field activities conducted at two sites at Robins AFB, Georgia, for a short-term field pilot test to compare vacuum-enhanced free-product recovery (bioslurping) to traditional free-product recovery techniques to remove light, nonaqueous-phase liquid (LNAPL) from subsurface soils and aquifers. The field testing at Robins AFB is part of the Bioslurper Initiative, which is funded and managed by the U.S. Air Force Center for Environmental Excellence (AFCEE) Technology Transfer Division. The AFCEE Bioslurper Initiative is a multisite program designed to evaluate the efficacy of the bioslurping technology for (1) recovery of LNAPL from groundwater and the capillary fringe, and (2) enhancing natural in situ degradation of petroleum contaminants in the vadose zone via bioventing.

The main objective of the Bioslurper Initiative is to develop procedures for evaluating the potential for recovering free-phase LNAPL present at petroleum-contaminated sites. The overall study is designed to evaluate bioslurping and identify site parameters that are reliable predictors of bioslurping performance. To measure LNAPL recovery in a wide variety of in situ conditions, tests are being performed at many sites. The tests at Robins AFB are two of at least 35 similar field tests to be conducted at various locations throughout the United States and its possessions.

The intent of field testing is to collect data to support determination of the predictability of LNAPL recovery and to evaluate the applicability, cost, and performance of the bioslurping technology for removal of free product and remediation of the contaminated area. The on-site testing is structured to allow direct comparison of the LNAPL recovery achieved by bioslurping with the performance of more conventional LNAPL recovery technologies. The test method included an initial site characterization followed by LNAPL recovery testing. The three LNAPL recovery technologies tested at Robins AFB were skimmer pumping, bioslurping, and drawdown pumping.

Site characterization activities were conducted to evaluate site variables that could affect LNAPL recovery efficiency and to determine the bioventing potential of the site. Testing included baildown testing, soil sampling, soil gas permeability testing, and in situ respiration testing.

After the site characterization activities, the pilot tests for the skimmer pumping, bioslurping, and drawdown pumping were conducted. The bioslurper system was installed in existing monitoring wells at both sites, Site Underground Storage Tank (UST) 70/72 and Site SS010. The pilot test sequence was as follows: 1 to 2 days in the skimmer configuration, 3 to 4 days in the bioslurper configuration, an additional day in the skimmer configuration (not conducted at Site SS010 due to

poor free product recovery), and 1 day in the drawdown configuration. Measurements of extracted soil gas composition, LNAPL thickness, and groundwater level were taken throughout the testing. The volumes of LNAPL recovered and groundwater extracted were quantified over time.

### Site UST 70/72 Results

Skimmer pumping was not as effective as bioslurping at recovering LNAPL from at Site UST 70/72. Free-product recovery rates remained relatively low during skimmer pumping, at an average recovery rate of 11 gallons/day during the initial skimmer pump test and decreasing to 5.0 gallons/day by the end of the second skimmer pump test. In contrast, free-product recovery rates during the bioslurper pump test remained relatively stable after the first day of operation at approximately 40 gallons/day. Drawdown pumping resulted in only slightly higher recovery than skimmer pumping and much less than bioslurping, with an average recovery rate of 12 gallons/day.

Groundwater recovery rates during the bioslurper pump test were high in comparison to rates during the skimmer or drawdown pump tests. On average, groundwater was extracted at rates of <sup>1400</sup>~~5,400~~ gallons/day during bioslurping, compared to <sup>850</sup>~~1,400~~ and <sup>2100</sup>~~1,900~~ gallons/day during skimming and drawdown pumping, respectively.

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Monitoring points at depths of 3.0 and 5.0 ft were not oxygen-limited. Oxygen concentrations increased slightly at monitoring points R1-MPA-7.0' and R1-MPB-7.0', but not at all at R1-MPC-7.0'. These results correlate with radius of influence results from the soil gas permeability test, where a radius of influence of approximately 57 ft was calculated. Given the low permeability of the soil, it is unlikely that soils would be oxygenated fully during the short time period of the soil gas permeability test. However, over time, it is likely that soils within the radius of influence of the bioslurper well will become oxygenated.

Implementation of bioslurping at the Robins AFB test site probably would facilitate enhanced recovery of LNAPL from the water table and simultaneous in situ biodegradation of hydrocarbons in the vadose zone via bioventing. An extended bioslurper test is planned for this site. The bioslurper system will be configured to tie into the bioslurper test well and into existing wells on site.

## Site SS010 Results

Free-product recovery was poor at Site SS010 during all pump tests. The maximum recovery rate was achieved during the bioslurper pump test; however, the average recovery rate was 3.2 gallons/day compared to an average groundwater extraction rate of 1,500 gallons/day. Free-product recovery may be limited due to the site hydrogeology or the condition that only small quantities of free product may be present.

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Oxygen concentrations increased slightly at all monitoring points where a soil gas sample could be collected. As at Site UST 70/72, given the low permeability of the soil, a time period longer than the length of this test may be necessary to fully oxygenate the soils. However, based on these results, it is likely that the soils will become oxygenated over time.

Implementation of bioslurping at Site SS010 does not appear to be a feasible option for free-product recovery due to the low recovery rate versus the high groundwater extraction rate. Given that free-product recovery was poor during all pump tests, the quantity of free product present may be low. Therefore, intrinsic bioremediation may be a more appropriate option for this site.

# **DRAFT SITE-SPECIFIC TECHNICAL REPORT (A003)**

**for**

## **BIOSLURPER TESTING AT SITES UST 70/72 AND SS010, ROBINS AFB, GEORGIA**

**November 28, 1995**

### **1.0 INTRODUCTION**

This report describes activities performed and data collected during two field tests at Robins Air Force Base (AFB), Georgia, to compare vacuum-enhanced free-product recovery (bioslurping) to traditional free-product recovery technologies for removal of light, nonaqueous-phase liquid (LNAPL) from subsurface soils and aquifers. The field testing at Robins AFB is part of the Bioslurper Initiative, which is funded and managed by the U.S. Air Force Center for Environmental Excellence (AFCEE) Technology Transfer Division. The AFCEE Bioslurper Initiative is a multisite program designed to evaluate the efficacy of the bioslurping technology for (1) recovery of LNAPL from groundwater and the capillary fringe and (2) enhancing natural in situ degradation of petroleum contaminants in the vadose zone via bioventing.

#### **1.1 Objectives**

The main objective of the Bioslurper Initiative is to develop procedures for evaluating the potential for recovering free-phase LNAPL present at petroleum-contaminated sites. The overall study is designed to evaluate bioslurping and identify site parameters that are reliable predictors of bioslurping performance. To measure LNAPL recovery in a wide variety of in situ conditions, tests are being performed at many sites. The tests at Robins AFB are two of at least 35 similar field tests to be conducted at various locations throughout the United States and its possessions. Aspects of the testing program that apply to all sites are described in the *Test Plan and Technical Protocol for Bioslurping* (Battelle, 1995). Test provisions specific to activities at Robins AFB are described in the Site-Specific Test Plan provided in Appendix A of this report.

The intent of field testing is to collect data to support determination of the predictability of LNAPL recovery and to evaluate the applicability, cost, and performance of the bioslurping

technology for removal of free product and remediation of the contaminated area. The on-site testing is structured to allow direct comparison of the LNAPL recovery achieved by bioslurping with the performance of more conventional LNAPL recovery technologies. The test method included an initial site characterization followed by LNAPL recovery testing. The three LNAPL recovery technologies tested at Robins AFB were skimmer pumping, bioslurping, and drawdown pumping. The specific test objectives, methods, and results for the Robins AFB test program are discussed in the following sections.

## **1.2 Testing Approach**

Site characterization activities were conducted to evaluate site variables that could affect LNAPL recovery efficiency and to determine the bioventing potential of the site. Testing included baildown testing to evaluate the mobility of LNAPL, soil sampling to determine physical/chemical site characteristics, soil gas permeability testing to determine the radius of influence, and in situ respiration testing to evaluate site microbial activity.

Following the site characterization activities, the pilot tests for skimmer pumping, bioslurping, and drawdown pumping were conducted. The LNAPL recovery testing was conducted in the following sequence at both sites: 1 to 2 days in the skimmer configuration, 3 to 4 days in the bioslurper configuration, 1 additional day in the skimmer configuration (not conducted at Site SS010 due to poor free-product recovery), and 1 day in the drawdown configuration. Measurements of extracted soil gas composition, LNAPL thickness, and groundwater level were taken throughout the testing. The volume of LNAPL recovered and groundwater extracted were quantified over time.

## **2.0 SITE UST 70/72**

### **2.1 Site Description**

Site Underground Storage Tank (UST) 70/72 is located in the 19th and 912th Air Refueling Wing located in the northeastern quadrant of Robins AFB. USTs 70 and 72 were installed in 1958 and have been used continuously since that time. The two tanks originally were used for JP-4 jet fuel storage, but were converted over to JP-8 jet fuel storage in June 1994. According to the Fuels

Maintenance Branch Staff at Robins AFB, large nondocumented releases of JP-4 jet fuel have occurred at UST 70 several times. Site characterization activities have shown soil and groundwater contamination.

Figure 1 illustrates the locations of monitoring wells at Site UST 70/72. Free product has been detected regularly in monitoring wells EA-1 and EA-2.

## **2.2 Bioslurper Short-Term Pilot Test Methods**

This section documents the initial conditions at the test site and describes the test equipment and methods used for the short-term pilot test at Robins AFB.

### **2.2.1 Initial LNAPL/Groundwater Measurements and Baildown Testing**

Monitoring well EA-2 was evaluated for use in the bioslurper pilot testing. Initial depths to LNAPL and to groundwater were measured using an oil/water interface probe (ORS Model #1068013). LNAPL was removed from the well with a Teflon™ bailer until the LNAPL thickness could no longer be reduced. The rate of increase in the thickness of the floating LNAPL layer was monitored for approximately 22 hours using the oil/water interface probe.

An LNAPL sample was collected after completing the baildown test and was labeled R1-Fuel-1. The sample was sent to Alpha Analytical, Inc., Sparks, Nevada for analysis of benzene, toluene, ethylbenzene, and xylenes (BTEX) and for boiling point fractionation.

### **2.2.2 Well Construction Details**

Existing monitoring well EA-2 was selected for use in the bioslurper pilot testing. The well is constructed of 4-inch-diameter, schedule 40 polyvinyl chloride (PVC) with a total depth of 14 ft and 10 ft of screen. A schematic diagram illustrating well construction details is provided in Figure 2.




Figure 1. Locations of Groundwater Monitoring Wells and Soil Gas Monitoring Points at Site UST 70/72, Robins AFB, GA






Figure 2. Schematic Diagram Illustrating Site Lithology and Construction Details of the Bioslurper Well and Soil Gas Monitoring Points at Site UST 70/72, Robins AFB, GA

### 2.2.3 Soil Gas Monitoring Point and Thermocouple Installation

On July 22, 1995, three monitoring points were installed in the area of monitoring well EA-2 and were labeled R1-MPA, R1-MPB, and R1-MPC. The locations and construction details of the monitoring points are illustrated in Figures 1 and 2, respectively.

The monitoring points consisted of sets of ¼-inch tubing, with 1-inch-diameter, 6-inch-long screened areas. The screened lengths were positioned at the appropriate depths, and the annular space corresponding to each screened length was filled with silica sand. The interval between the screened lengths was filled with bentonite clay chips, as was the space from the top of the shallowest screened length to the ground surface. After placement, the bentonite clay was hydrated with water to expand the chips and provide a seal.

All monitoring points were installed in a 6-inch-diameter borehole to a depth of 8.0 ft. Screened lengths were placed at three depths: 2.5 to 3.0 ft, 4.5 to 5.0 ft, and 6.5 to 7.0 ft.

After installation of the monitoring points, initial soil gas measurements were taken with a GasTector portable O<sub>2</sub>/CO<sub>2</sub> meter and a GasTech Trace-Tector portable hydrocarbon meter. Oxygen limitation was observed only at the deeper depths, with oxygen concentrations ranging from 1.5% to 2.0% and total petroleum hydrocarbons (TPH) >20,000 ppmv at a depth of 7.0 ft (Table 1).

**Table 1. Initial Soil Gas Compositions at Site UST 70/72, Robins AFB, GA**

Monitoring Point	Depth (ft)	Oxygen (%)	Carbon Dioxide (%)	TPH (ppmv)
R1-MPA	3.0	20.9	0.5	20
	5.0	19.5	2.1	360
	7.0	2.0	12.5	>20,000
R1-MPB	3.0	20.9	0.3	10
	5.0	17.8	2.1	370
	7.0	1.7	12.5	>20,000
R1-MPC	3.0	20.9	0.1	0
	5.0	17.5	2.8	290
	7.0	1.5	15.1	>20,000

#### **2.2.4 Soil Sampling and Analysis**

Two soil samples were collected during the installation of monitoring point R1-MPA. The soil samples were collected in brass sleeves driven down the center of the hollow-stem auger used to drill the soil gas monitoring point. The samples were labeled R1-MPA-7.0'-7.5' and R1-MPA-7.5'-8.0'. The samples were placed in insulated coolers, chain-of-custody records and shipping papers were completed, and the samples were sent to Alpha Analytical, Inc., Sparks, Nevada by overnight express. Both samples were analyzed for BTEX and TPH, while sample R1-MPA-7.0'-7.5' was analyzed for bulk density, moisture content, and porosity. Laboratory analytical reports are provided in Appendix B.

#### **2.2.5 LNAPL Recovery Testing**

##### **2.2.5.1 System Setup**

The bioslurping pilot test system is a trailer-mounted mobile unit. The vacuum pump (Atlantic Fluidics Model A100, 7.5-hp liquid ring pump), oil/water separator, and required support equipment are carried to the test location on a trailer. The trailer was located near monitoring well EA-2, the well cap was removed, a coupling and tee were attached to the top of the well, and the slurper tube was lowered into the well. The slurper tube was attached to the vacuum pump. Different configurations of the tee and the placement depth of the slurper tube allow for simulation of skimmer pumping, operation in the bioslurping configuration, or simulation of drawdown pumping as described in Sections 2.2.5.2, 2.2.5.3, and 2.2.5.5, respectively. Extracted groundwater was treated to control emulsion formation by passing the effluent through a knockout tank, a bag filter, an oil/water separator, and hydrophobic clay drums (Figure 3). Activated carbon drums were added at the end of the treatment train to reduce contaminant concentrations.

A brief system startup test was performed prior to LNAPL recovery testing to ensure that all system components were working properly. The system checklist is provided in Appendix C. All site data and field testing information were recorded in a field notebook and then transcribed onto pilot test data sheets provided in Appendix D.




Figure 3. Components of the Emulsion Control and Groundwater Treatment System Used at Site UST 70/72, Robins AFB, GA

#### **2.2.5.2 Initial Skimmer Pump Test**


Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set at the LNAPL/groundwater interface with the wellhead open to the atmosphere via a PVC connecting tee (Figure 4). The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 1, 1995, to begin the skimmer pump test. The test was operated continuously for approximately 40 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the skimmer pump test. Test data sheets are provided in Appendix D.

#### **2.2.5.3 Bioslurper Pump Test**

Upon completion of the skimmer pump test, preparations were made to begin the bioslurper pump test. Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set at the LNAPL/groundwater interface, as in the skimmer pump test. However, in contrast to the skimmer pump test, the PVC connecting tee was removed, sealing the wellhead and allowing the pump to establish a vacuum in the well (Figure 5). A pressure gauge was installed at the wellhead to measure the vacuum inside the extraction well. The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 3, 1995, to begin the bioslurper pump test. The test was initiated approximately 2.5 hours after the skimmer pump test and was operated continuously for approximately 94 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the bioslurper pump test. Test data sheets are provided in Appendix D.


#### **2.2.5.4 Second Skimmer Pump Test**

Upon completion of the bioslurper pump test, preparations were made to begin the second skimmer pump test. Prior to test initiation, depths to LNAPL and groundwater were measured. The



NGA/Kittel/10-01c

Figure 4. Slurper Tube Placement and Valve Position for the Skimmer Pump Test



NKA/GW/10-01b

Figure 5. Slurper Tube Placement and Valve Position for the Bioslurper Pump Test

valve and slurper tube configuration were identical to that used for the initial skimmer pump test. The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 8, 1995, to begin the second skimmer pump test. The test was initiated approximately 1.5 hours after the bioslurper pump test and was operated continuously for 22 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the bioslurper pump test. Test data sheets are provided in Appendix D.


#### **2.2.5.5 Drawdown Pump Test**

Upon completion of the second skimmer pump test, preparations were made to begin the drawdown pump test. Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set so that the tip was 24 inches below the oil/water interface with the PVC connecting tee open to the atmosphere (Figure 6). The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 9, 1995, to begin the drawdown pump test. The test was initiated approximately 2 hours after the second skimmer pump test and was operated continuously for 22 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the drawdown pump test. Test data sheets are provided in Appendix D.

#### **2.2.5.6 Off-Gas Sampling and Analysis**

Soil gas samples were collected from the bioslurper off-gas during the bioslurper pump test. Samples were collected in Summa™ canisters during the first and third day after test initiation and were labeled R1-Stack-1 and R1-Stack-2, respectively. The samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analyses of BTEX and TPH.





NKA/Q26a/10-01d

Figure 6. Slurper Tube Placement and Valve Position for the Drawdown Pump Test

### **2.2.5.7 Groundwater Sampling and Analysis**

Seven groundwater samples were collected during the bioslurper pump test. One sample was collected from the oil/water separator (R1-H2O-1), one sample was collected from the 1,500-gallon tank (R1-H2O-2), one sample was collected after the second clay unit (R1-H2O-3), and four samples were collected after the second carbon treatment unit (R1-H2O-4, R1-OutH2O-1, R1-OutH2O-2, and R1-OutH2O-3). Samples were collected in 40-mL septa vials containing HCl preservative. Samples were checked to ensure no headspace was present and were then shipped on ice and sent under chain of custody to Lubrication Analysts, Inc., in Albany, Georgia for analyses of BTEX and TPH.

### **2.2.6 Soil Gas Permeability Testing**

The soil gas permeability test data were collected during the bioslurper pump test. Before a vacuum was established in the extraction well, the initial soil gas pressures at the three installed monitoring points were recorded. The start of the bioslurper pump test created a steep pressure drop in the extraction well which was the starting point for the soil gas permeability testing. Soil gas pressures were measured at each of the three monitoring points at all depths to track the rate of outward propagation of the pressure drop in the extraction well. Soil gas pressure data were collected frequently during the first 20 minutes of the test. The soil gas pressures were recorded throughout the bioslurper pump test to determine the bioventing radius of influence. Test data are provided in Appendix E.

### **2.2.7 In Situ Respiration Testing**

Air containing approximately 1% helium was injected into three monitoring points for approximately 24 hours beginning on August 9, 1995. The setup for the in situ respiration test is described in the *Test Plan and Technical Protocol a Field Treatability Test for Bioventing* (Hinchee et al., 1992). A ½-hp diaphragm pump was used for air and helium injection. Air and helium were injected through the following monitoring points at the depths indicated: R1-MPA-7.0', R1-MPB-7.0', and R1-MPC-7.0'. After the air/helium injection was terminated, soil gas concentrations of oxygen, carbon dioxide, TPH, and helium were monitored periodically. The respiration test was

terminated on August 13, 1995. Oxygen utilization and biodegradation rates were calculated as described in Hinchey et al. (1992). Raw data for these tests are presented in Appendix F.

Helium concentrations were measured during the in situ respiration test to quantify helium leakage to or from the surface around the monitoring points. Helium loss over time is attributable to either diffusion through the soil or leakage. A rapid drop in helium concentration usually indicates leakage. A gradual loss of helium along with a first-order curve generally indicates diffusion. As a rough estimate, the diffusion of gas molecules is inversely proportional to the square root of the molecular weight of the gas. Based on molecular weights of 4 for helium and 32 for oxygen, helium diffuses approximately 2.8 times faster than oxygen, or the diffusion of oxygen is 0.35 times the rate of helium diffusion. As a general rule, we have found that if helium concentrations at test completion are at least 50 to 60% of the initial levels, measured oxygen uptake rates are representative. Greater helium loss indicates a problem, and oxygen utilization rates are not considered representative.

## **2.3 Results**

This section documents the results of the site characterization, the comparative LNAPL recovery pump test, and other supporting tests conducted at Robins AFB.

### **2.3.1 Baildown Test Results**

Results from the baildown test in monitoring well EA-2 are presented in Table 2. A total volume of 5.8 L (1.5 gallons) was removed by hand bailing from monitoring well EA-2. The LNAPL thickness recovered rapidly to approximately initial levels by the end of the 22-hour test period. These results indicated that monitoring well EA-2 was suitable for bioslurper field testing.

### **2.3.2 Soil Sample Analyses**

Table 3 shows the BTEX and TPH concentrations measured in soil samples collected from Site UST 70/72. BTEX and TPH concentrations were high, with an average total BTEX concentration of 220 mg/kg and an average TPH concentration of 25,000 mg/kg. Results of the physical characterization of the soils showed a moisture content of 9.6%, a bulk density of 1.21 g/cm<sup>3</sup>, a porosity of 54.3%, and particle size of 91% sand, 4.0% silt, and 5.0% clay.

**Table 2. Results of Baildown Testing in Monitoring Well EA-2, Site UST 70/72, Robins AFB, GA**

<b>Date-Time</b>	<b>Depth to LNAPL (ft)</b>	<b>Depth to Groundwater (ft)</b>	<b>LNAPL Thickness (ft)</b>
Initial Reading 7/20/95-0830	6.67	8.50	1.83
Test Initiation 7/20/95-0850	6.78	8.09	1.31
7/20/95-0900	6.67	8.35	1.68
7/20/95-0910	6.67	8.38	1.71
7/20/95-0920	6.67	8.40	1.73
7/20/95-1154	6.67	8.45	1.78
7/20/95-1616	6.67	8.47	1.80
7/21/95-0656	6.67	8.50	1.83

**Table 3. BTEX and TPH Concentrations in Soil Samples from Site UST 70/72, Robins AFB, GA**

<b>Parameter</b>	<b>Concentration (mg/kg)</b>	
	<b>R1-MPA-7.0'-7.5'</b>	<b>R1-MPA-7.5'-8.0'</b>
TPH	31,000	19,000
Benzene	13	14
Toluene	19	15
Ethylbenzene	31	24
Xylenes	190	140

### **2.3.3 LNAPL Pump Test Results**

#### **2.3.3.1 Initial Skimmer Pump Test Results**

The LNAPL thickness prior to the initial skimmer pump test was 1.82 ft (Table 4). A total of 18.2 gallons of LNAPL was recovered during this test, with an average recovery rate of 11 gallons/day (Table 5). A total of 1,420 gallons of groundwater was extracted with an average extraction rate of 850 gallons/day (Table 5). Results of LNAPL recovery versus time are shown in Figure 7.

#### **2.3.3.2 Bioslurper Pump Test Results**

LNAPL recovery rates increased significantly during the bioslurper pump test (Figure 7). The increase in recovery rate indicates that LNAPL was mobilized to the extraction well under vacuum-enhanced conditions. A total of 186 gallons of LNAPL and 5,425 gallons of groundwater was extracted during the bioslurper pump test, with an average recovery rate of 48 gallons/day for LNAPL and 1,400 gallons/day for groundwater (Table 5). The LNAPL recovery rate versus time is shown in Figure 8. The vacuum-exerted wellhead pressure on monitoring well EA-2 was kept relatively constant throughout the bioslurper pump test at approximately 25 inches of mercury.

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Oxygen concentrations increased slightly at monitoring points R1-MPA-7.0' and R1-MPB-7.0', but not at all at R1-MPC-7.0' (Table 6). These results correlate with radius of influence results from the soil gas permeability test.

#### **2.3.3.3 Second Skimmer Pump Test**

Totals of 4.6 gallons of LNAPL and 697 gallons of groundwater were recovered during the second skimmer pump test, with average recovery rates of 5.0 gallons/day for LNAPL and 750 gallons/day for groundwater (Table 5). These results demonstrate that operation of the bioslurper system in the skimmer mode was not as effective a means of free-product recovery as the bioslurper system at this site.

**Table 4. Depths to Groundwater and LNAPL Prior to Each Pump Test**

Test	Test Start Date	Depth to LNAPL (ft)	Depth to Groundwater (ft) <sup>1</sup>	LNAPL Thickness (ft)
Initial Skimmer Pump Test	8/1/95	6.67	8.49	1.82
Bioslurper Pump Test	8/3/95	6.80	7.35	0.55
Second Skimmer Pump Test	8/7/95	6.95	7.26	0.31
Drawdown Pump Test	8/8/95	6.90	7.15	0.25

**Table 5. Pump Test Results at Site UST 70/72, Robins AFB, GA**

Recovery Rate (gal/day)	Initial Skimmer Pump Test		Bioslurper Pump Test		Second Skimmer Pump Test		Drawdown Pump Test	
	LNAPL	Groundwater	LNAPL	Groundwater	LNAPL	Groundwater	LNAPL	Groundwater
Day 1	16	750	64	1,440	8.6	750	12	2,100
Day 2	6.3	930	45	1,520	NA	NA	NA	NA
Day 3	NA	NA	40	1,490	NA	NA	NA	NA
Day 4	NA	NA	40	1,060	NA	NA	NA	NA
Average	11	850	48	1,400	5.0	750	12	2,100
Total Recovered (gal)	18.2	1,420	186.1	5,425	4.6	697	10.5	1,910

NA = Not applicable.




Figure 7. LNAPL Recovery Versus Time During Each Pump Test at Site UST 70/72




Figure 8. LNAPL Recovery Rate Versus Time During the Biosurper Pump Test at Site UST 70/72



**Table 6. Oxygen Concentrations During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA**

Monitoring Point	Oxygen Concentrations (%) Versus Time (minutes)				
	0	3.5	26	49	90
R1-MPA-3.0'	20.9	20.9	20.9	20.9	20.9
R1-MPA-5.0'	19.5	19.2	19.0	18.5	18.9
R1-MPA-7.0'	2.0	2.5	2.9	4.8	5.1
R1-MPB-3.0'	20.9	20.9	20.9	21.0	21.0
R1-MPB-5.0'	17.8	17.9	18.5	20.9	20.9
R1-MPB-7.0'	1.7	2.0	2.1	2.2	2.5
R1-MPC-3.0'	20.9	20.9	20.9	20.9	20.9
R1-MPC-5.0'	17.5	17.9	17.1	18.9	18.9
R1-MPC-7.0'	1.5	1.7	1.6	1.4	1.6

#### **2.3.3.4 Drawdown Pump Test**

Results from the drawdown pump test were similar to those from the skimmer pump tests (Figure 7). A high ratio of LNAPL to groundwater was extracted, with totals of 10.5 gallons of LNAPL and 1,910 gallons of groundwater extracted (Table 5). These results demonstrate that operation of the bioslurper system in the drawdown mode was not as effective a means of free-product recovery as the bioslurper system at this site.

#### **2.3.4 Emulsion Control and Extracted Groundwater, LNAPL, and Off-Gas Analyses**

During the skimmer, bioslurper, and drawdown pump tests, the emulsion control system did minimize the formation of the solid fuel/water emulsion; however, the liquid fuel/water emulsion was not affected. Consequently, contaminant concentrations were not significantly reduced by the emulsion control system. Treatment through activated carbon resulted in BTEX and TPH concentrations reduced to below detection limits (Table 7).

**Table 7. BTEX and TPH Concentrations in Extracted Groundwater During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA**

Parameter	Concentration (mg/L)				
	TPH	Benzene	Toluene	Ethylbenzene	Total Xylenes
R1-H2O-1	22	0.13	0.092	0.092	0.22
R1-H2O-2	29	0.30	0.33	0.13	0.18
R1-H2O-3	20	0.22	0.18	0.043	0.27
R1-H2O-4	<0.50	<0.00050	<0.00050	<0.00050	<0.00050
R1-OutH2O-1	<0.50	<0.0010	<0.0010	<0.0010	<0.0010
R1-OutH2O-2	<0.50	<0.0010	<0.0010	<0.0010	<0.0010
R1-OutH2O-3	<0.50	<0.0010	<0.0010	<0.0010	<0.0010

Off-gas samples from the bioslurper system also were collected during the bioslurper pump test. The results from the off-gas analyses are presented in Table 8. Given a vapor discharge rate of 5 scfm and using an average concentration of 37,000 ppmv TPH, approximately 110 lb/day of TPH was emitted to the air during the bioslurper pump test. Benzene emissions were approximately 0.74 lb/day.

The composition of LNAPL is shown in Tables 9 and 10 in terms of BTEX concentrations and distribution of C-range compounds, respectively. The distribution of C-range compounds is shown graphically in Figure 9.

### 2.3.5 Bioventing Analyses

#### 2.3.5.1 Soil Gas Permeability and Radius of Influence

The radius of influence is calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the extraction well. The radius of influence is then defined as the distance from the extraction well where 0.1 inch of H<sub>2</sub>O can be measured. Based on this definition, the radius of influence at this site is approximately 57 ft (Figure 10).

**Table 8. BTEX and TPH Concentrations in Off-Gas During the Bioslurper Pump Test at Site UST 70/72, Robins AFB, GA**

Parameter	Concentration (ppmv)	
	R1-Stack-1	R1-Stack-2
TPH as jet fuel	27,000	47,000
Benzene	370	660
Toluene	140	260
Ethylbenzene	20	43
Xylenes	65	130

**Table 9. BTEX Concentrations in LNAPL from Site UST 70/72, Robins AFB, GA**

Compound	Concentration (mg/kg)
Benzene	460
Toluene	1,600
Ethylbenzene	7,200
Total Xylenes	1,100

**Table 10. C-Range Compounds in LNAPL from Site UST 70/72, Robins AFB, GA**


<b>C-Range Compound</b>	<b>Percentage of Total</b>
< C9	17.33
C10	28.09
C11	19.14
C12	12.48
C13	10.31
C14	6.60
C15	3.53
C16	1.59
> C17	0.93

#### **2.3.5.2 In Situ Respiration Test Results**

Results from the in situ respiration test are presented in Table 11. Oxygen depletion was relatively rapid, with oxygen utilization rates ranging from 0.11 to 0.20% O<sub>2</sub>/hr. Biodegradation rates ranged from 1.8 to 3.2 mg/kg-day. The helium concentration was steady, indicating that leakage and diffusion were insignificant.


#### **2.4 Discussion**

Skimmer pumping was not as effective as bioslurping at recovering LNAPL from this site. Free-product recovery rates remained relatively low during skimmer pumping, at an average recovery rate of 11 gallons/day during the initial skimmer pump test and decreasing to 5.0 gallons/day by the end of the second skimmer pump test. In contrast, free-product recovery rates during the bioslurper pump test remained relatively stable after the first day of operation at approximately 40 gallons/day. Drawdown pumping resulted in only slightly higher recovery than skimmer pumping and much less than bioslurping, with an average recovery rate of 12 gallons/day.



c:\plot50\biolurp\robins\crange1.sp5

**Figure 9. Distribution of C-Range Compounds in Extracted LNAPL at Site UST 70/72, Robins AFB, GA**



**Figure 10. Soil Gas Pressure Change as a Function of Distance During the Soil Gas Permeability Test at Site UST 70/72**

**Table 11. In Situ Respiration Test Results at Site UST 70/72, Robins AFB, GA**

Monitoring Point	Oxygen Utilization Rate (%/hr)	Biodegradation Rate (mg/kg-day)
R1-MPA-7.0'	0.18	2.9
R1-MPB-7.0'	0.20	3.2
R1-MPC-7.0'	0.11	1.8

Groundwater recovery rates during the bioslurper pump test were high in comparison to rates during the skimmer or drawdown pump tests. On average, groundwater was extracted at rates of \$,400 gallons/day during bioslurping, compared to <sup>950</sup>~~1,400~~ and <sup>2100</sup>~~1,900~~ gallons/day during skimming and drawdown pumping, respectively.

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Monitoring points at depths of 3.0 and 5.0 ft were not oxygen-limited. Oxygen concentrations increased slightly at monitoring points R1-MPA-7.0' and R1-MPB-7.0', but not at all at R1-MPC-7.0'. These results correlate with radius of influence results from the soil gas permeability test, where a radius of influence of approximately 57 ft was calculated. Given the low permeability of the soil, it is unlikely that soils would be oxygenated fully during the short time period of the soil gas permeability test. However, over time, it is likely that soils within the radius of influence of the bioslurper well will become oxygenated.

Implementation of bioslurping at the Robins AFB test site probably would facilitate enhanced recovery of LNAPL from the water table and simultaneous in situ biodegradation of hydrocarbons in the vadose zone via bioventing. An extended bioslurper test is planned for this site. The bioslurper system will be configured to tie into the bioslurper test well and into existing wells on-site.

### **3.0 SITE SS010**

#### **3.1 Site Description**

Site SS010, located in Zone 4 at Robins AFB, consists of JP-4 fuel storage tanks that are supplied by a pipeline running from the Standard Transmission Corporation Tank Farm located to the north of Robins AFB. Two major spills have occurred since the mid-1960s and recent site characterization studies have shown that a large LNAPL plume is present at Site SS010.

Figure 11 illustrates the locations of monitoring wells at Site SS010. Several monitoring wells have routinely contained significant thicknesses of free product.

#### **3.2 Bioslurper Short-Term Pilot Test Methods**

This section documents the initial conditions at the test site and describes the test equipment and methods used for the short-term pilot test at Robins AFB.

##### **3.2.1 Initial LNAPL/Groundwater Measurements and Baildown Testing**

Monitoring wells LF-1-3 and PZ-1 were evaluated for use in the bioslurper pilot testing. Initial depths to LNAPL and to groundwater were measured using an oil/water interface probe (ORS Model #1068013). LNAPL was removed from the wells with a Teflon™ bailer until the LNAPL thickness could no longer be reduced. The rate of increase in the thickness of the floating LNAPL layer was monitored for approximately 66 hours using the oil/water interface probe.

An LNAPL sample was collected from monitoring well LF-1-3 after completing the baildown test and was labeled R2-Fuel-1. The sample was sent to Alpha Analytical, Inc., Sparks, Nevada for analyses of BTEX and boiling point fractionation.

##### **3.2.2 Well Construction Details**

Existing monitoring well LF-1-3 was selected for use in the bioslurper pilot testing. The well is constructed of 2-inch-diameter, schedule 40 PVC with a total depth of 25 ft and 20 ft of screen. A schematic diagram illustrating the well construction details is provided in Figure 12.






Figure 11. Locations of Groundwater Monitoring Wells and Soil Gas Monitoring Points at Site SS010, Robins AFB, GA




Figure 12. Schematic Diagram Illustrating Site Lithology and Construction Details of the Bioslurper Well and Soil Gas Monitoring Points at Site SS010, Robins AFB, GA

### 3.2.3 Soil Gas Monitoring Point and Thermocouple Installation

On July 22, 1995, three monitoring points were installed in the area of monitoring well LF-1-3 and were labeled R2-MPA, R2-MPB, and R2-MPC. The locations and construction details of the monitoring points are illustrated in Figures 11 and 12, respectively.

The monitoring points consisted of sets of ¼-inch tubing, with 1-inch-diameter, 6-inch-long screened areas. The screened lengths were positioned at the appropriate depths, and the annular space corresponding to the screened length was filled with silica sand. The interval between the screened lengths was filled with bentonite clay chips, as was the space from the top of the shallowest screened length to the ground surface. After placement, the bentonite clay was hydrated with water to expand the chips and provide a seal.

All monitoring points were installed in a 6-inch-diameter borehole to a depth of 7.0 ft. Screened lengths were placed at three depths: 1.5 to 2.0 ft, 3.5 to 4.0 ft, and 5.5 to 6.0 ft.

After installation of the monitoring points, initial soil gas measurements were taken with a GasTechtor portable O<sub>2</sub>/CO<sub>2</sub> meter and a GasTech Trace-Techtor portable hydrocarbon meter. In general, oxygen limitation was observed at the deeper depths, with oxygen concentrations ranging from 5.2% to 9.8% at a depth of 4.0 ft (Table 12). Soil gas concentrations could not be measured at deeper depths due to excess soil moisture.

### 3.2.4 Soil Sampling and Analysis

Two soil samples were collected during the installation of monitoring point R2-MPA. The soil samples were collected in brass sleeves driven down the center of the hollow-stem auger used to drill the monitoring well. The samples were labeled as follows: R2-MPA-6.0'-6.5' and R2-MPA-6.5'-7.0'. The samples were placed in insulated coolers, chain-of-custody records and shipping papers were completed, and the samples were sent to Alpha Analytical, Inc., in Sparks, Nevada by overnight express. Both samples were analyzed for BTEX and TPH. Sample R2-MPA-6.0'-6.5' also was analyzed for bulk density, moisture content, and porosity. Laboratory analytical reports for all samples are provided in Appendix B.

**Table 12. Initial Soil Gas Compositions at Site SS010, Robins AFB, GA**

Monitoring Point	Depth (ft)	Oxygen (%)	Carbon Dioxide (%)	TPH (ppmv)
R2-MPA	2.0	19.8	1.7	400
	4.0	5.2	8.9	> 10,000
	6.0	ND	ND	ND
R2-MPB	2.0	19.5	2.1	460
	4.0	9.5	7.8	5,800
	6.0	ND	ND	ND
R2-MPC	2.0	15.7	4.6	580
	4.0	9.8	9.5	7,000
	6.0	ND	ND	ND

ND Not determined. Excess soil moisture prohibited soil gas collection at this depth.

### 3.2.5 LNAPL Recovery Testing

#### 3.2.5.1 System Setup

The bioslurping pilot test system is a trailer-mounted mobile unit. The vacuum pump (Atlantic Fluidics Model A100, 7.5-hp liquid ring pump), oil/water separator, and required support equipment are carried to the test location on a trailer. The trailer was located near monitoring well LF-1-3, the well cap was removed, a coupling and tee were attached to the top of the well, and the slurper tube was lowered into the well. The slurper tube was attached to the vacuum pump. Different configurations of the tee and the placement depth of the slurper tube allow for simulation of skimmer pumping, operation in the bioslurping configuration, or simulation of drawdown pumping as described in Sections 3.2.5.2, 3.2.5.3, and 3.2.5.5, respectively. Extracted groundwater was treated to control emulsion formation by passing the effluent through a knockout tank, a bag filter, an oil/water separator, and hydrophobic clay drums (Figure 3). Activated carbon drums were added at the end of the treatment train to reduce contaminant concentrations.

A brief system startup test was performed prior to LNAPL recovery testing to ensure that all system components were working properly. The system checklist is provided in Appendix C. All site data and field testing information were recorded in a field notebook and then transcribed onto pilot test data sheets provided in Appendix D.

#### **3.2.5.2 Initial Skimmer Pump Test**

Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set at the LNAPL/groundwater interface with the wellhead open to the atmosphere via a PVC connecting tee (Figure 4). The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 10, 1995, to begin the skimmer pump test. The test was operated continuously for approximately 43 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the skimmer pump test. Test data sheets are provided in Appendix D.

#### **3.2.5.3 Bioslurper Pump Test**

Upon completion of the skimmer pump test, preparations were made to begin the bioslurper pump test. Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set at the LNAPL/groundwater interface, as in the skimmer pump test. However, in contrast to the skimmer pump test, the PVC connecting tee was removed, sealing the wellhead and allowing the pump to establish a vacuum in the well (Figure 5). A pressure gauge was installed at the wellhead to measure the vacuum inside the extraction well. The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 12, 1995, to begin the bioslurper pump test. The test was initiated approximately 2.5 hours after the skimmer pump test and was operated continuously for approximately 86 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the bioslurper pump test. Test data sheets are provided in Appendix D.

#### **3.2.5.4 Drawdown Pump Test**

Upon completion of the bioslurper pump test, preparations were made to begin the drawdown pump test. Prior to test initiation, depths to LNAPL and groundwater were measured. The slurper tube was then set so that the tip was 24 inches below the oil/water interface with the PVC connecting tee open to the atmosphere (Figure 6). The liquid ring pump and oil/water separator were primed with known amounts of groundwater to ensure that any LNAPL or groundwater entering the system could be quantified. The flow totalizers for the LNAPL and aqueous effluent were zeroed, and the liquid ring pump was started on August 16, 1995, to begin the drawdown pump test. The test was initiated approximately 2 hours after the bioslurper pump test and was operated continuously for 33 hours. The LNAPL and groundwater extraction rates were monitored throughout the test, as were all other relevant data for the drawdown pump test. Test data sheets are provided in Appendix D.

#### **3.2.5.5 Off-Gas Sampling and Analysis**

Soil gas samples were collected from the bioslurper off-gas during the bioslurper pump test. Samples were collected in Summa™ canisters during the first and third day after test initiation and were labeled R2-Stack-1 and R2-Stack-2, respectively. The samples were sent under chain of custody to Air Toxics, Ltd., in Rancho Cordova, California, for analyses of BTEX and TPH.

#### **3.2.5.6 Groundwater Sampling and Analysis**

Six groundwater samples were collected during the bioslurper pump test. One sample was collected from the oil/water separator (R2-H2O-1), one sample was collected from the 1,500-gallon tank (R2-H2O-2), one sample was collected after the second clay unit (R2-H2O-3), and three samples were collected after the second carbon treatment unit (R2-H2O-4, R2-OutH2O-1, and R2-OutH2O-2). Samples were collected in 40-mL septa vials containing HCl preservative. Samples were checked to ensure no headspace was present and were then shipped on ice and sent under chain of custody to Lubrication Analysts, Inc., in Albany, Georgia for analyses of BTEX and TPH.

### 3.2.6 Soil Gas Permeability Testing

The soil gas permeability test data were collected during the bioslurper pump test. Before a vacuum was established in the extraction well, the initial soil gas pressures at the three installed monitoring points were recorded. The start of the bioslurper pump test created a steep pressure drop in the extraction well which was the starting point for the soil gas permeability testing. Soil gas pressures were measured at each of the three monitoring points at all depths to track the rate of outward propagation of the pressure drop in the extraction well. Soil gas pressure data were collected frequently during the first 20 minutes of the test. The soil gas pressures were recorded throughout the bioslurper pump test to determine the bioventing radius of influence. Test data are provided in Appendix E.

### 3.2.7 In Situ Respiration Testing

Air containing approximately 1% helium was injected into three monitoring points for approximately 24 hours beginning on August 16, 1995. The setup for the in situ respiration test is described in the *Test Plan and Technical Protocol a Field Treatability Test for Bioventing* (Hinchee et al., 1992). A ½-hp diaphragm pump was used for air and helium injection. Air and helium were injected through the following monitoring points at the depths indicated: R2-MPA-4.0', R2-MPB-4.0', and R2-MPC-4.0'. After the air/helium injection was terminated, soil gas concentrations of oxygen, carbon dioxide, TPH, and helium were monitored periodically. The respiration test was terminated on August 20, 1995. Oxygen utilization and biodegradation rates were calculated as described in Hinchee et al. (1992). Raw data for these tests are presented in Appendix F.

Helium concentrations were measured during the in situ respiration test to quantify helium leakage to or from the surface around the monitoring points. Helium loss over time is attributable to either diffusion through the soil or leakage. A rapid drop in helium concentration usually indicates leakage. A gradual loss of helium along with a first-order curve generally indicates diffusion. As a rough estimate, the diffusion of gas molecules is inversely proportional to the square root of the molecular weight of the gas. Based on molecular weights of 4 for helium and 32 for oxygen, helium diffuses approximately 2.8 times faster than oxygen, or the diffusion of oxygen is 0.35 times the rate of helium diffusion. As a general rule, we have found that if helium concentrations at test completion

are at least 50 to 60% of the initial levels, measured oxygen uptake rates are representative. Greater helium loss indicates a problem, and oxygen utilization rates are not considered representative.

### **3.3 Results**

This section documents the results of the site characterization, the comparative LNAPL recovery pump test, and other supporting tests conducted at Site SS010, Robins AFB.

#### **3.3.1 Baildown Test Results**

Results from the baildown test in monitoring wells LF-1-3 and PZ-1 are presented in Table 13. A total volume of 1.6 and 0.9 L (0.42 and 0.24 gallons) was removed by hand bailing from monitoring wells LF-1-3 and PZ-1, respectively. The LNAPL thickness recovered relatively slowly to approximately initial levels by the end of the 66-hour test period. Monitoring well LF-1-3 was selected for testing primarily due to the deeper groundwater depth.

#### **3.3.2 Soil Sample Analyses**

Table 14 shows the BTEX and TPH concentrations measured in soil samples collected from Site SS010. BTEX and TPH concentrations were relatively high, with an average total BTEX concentration of 11 mg/kg and an average TPH concentration of 420 mg/kg. Results of the physical characterization of the soils showed a moisture content of 17.2%, a bulk density of 1.83 g/cm<sup>3</sup>, a porosity of 30.9%, and particle size of 86% sand, 4.0% silt, and 10.0% clay.

#### **3.3.3 LNAPL Pump Test Results**

##### **3.3.3.1 Initial Skimmer Pump Test Results**

The LNAPL thickness prior to the initial skimmer pump test was 0.48 ft (Table 15). A total of 2.5 gallons of LNAPL was recovered during this test, with an average recovery rate of 1.4 gallons/day (Table 16). A total of 1,550 gallons of groundwater was extracted with an average



**Table 13. Results of Baildown Testing in Monitoring Wells PZ-1 and LF-1-3, Site SS010, Robins AFB, GA**

Monitoring Well	Date-Time	Depth to LNAPL (ft)	Depth to Groundwater (ft)	LNAPL Thickness (ft)
LF-1-3	Initial Reading 7/22/95-1400	6.78	7.30	0.52
	Test Initiation 7/22/95-1500	6.89	6.91	0.02
	7/22/95-1510	6.87	6.92	0.05
	7/22/95-1520	6.85	6.93	0.08
	7/22/95-1530	6.84	6.93	0.09
	7/22/95-1630	6.83	6.95	0.12
	7/23/95-0445	6.82	6.97	0.15
	7/23/95-0920	6.82	6.97	0.15
	7/23/95-1440	6.81	6.97	0.16
	7/24/95-1415	6.79	7.07	0.28
	7/25/95-0930	6.77	7.22	0.45
PZ-1	Initial Reading 7/22/95-0900	3.90	4.60	0.70
	Test Initiation 7/22/95-1500	4.05	4.06	0.01
	7/22/95-1510	4.05	4.09	0.04
	7/22/95-1520	4.04	4.11	0.07
	7/22/95-1530	4.03	4.11	0.08
	7/22/95-1630	4.03	4.20	0.17
	7/23/95-0500	4.02	4.22	0.20
	7/23/95-0940	4.02	4.24	0.22
	7/23/95-1505	4.00	4.27	0.27
	7/24/95-1420	3.95	4.39	0.44
	7/25/95-0940	3.95	4.20	0.25

**Table 14. BTEX and TPH Concentrations in Soil Samples from Site SS010, Robins AFB, GA**

Parameter	Concentration (mg/kg)	
	R2-MPA-6.0'-6.5'	R2-MPA-6.5'-7.0'
TPH	430	410
Benzene	<0.20	<0.20
Toluene	1.3	1.5
Ethylbenzene	1.3	1.4
Xylenes	8.2	8.9

**Table 15. Depths to Groundwater and LNAPL Prior to Each Pump Test**

Test	Test Start Date	Depth to LNAPL (ft)	Depth to Groundwater (ft)	LNAPL Thickness (ft)
Initial Skimmer Pump Test	8/10/95	6.77	7.25	0.48
Bioslurper Pump Test	8/12/95	6.89	6.97	0.08
Drawdown Pump Test	8/16/95	6.92	6.94	0.02

**Table 16. Pump Test Results at Site SS010, Robins AFB, GA**

Recovery Rate (gal/day)	Initial Skimmer Pump Test		Bioslurper Pump Test		Drawdown Pump Test	
	LNAPL	Groundwater	LNAPL	Groundwater	LNAPL	Groundwater
Day 1	1.6	870	5.0	1,510	0.27	1,790
Day 2	1.1	890	2.3	1,500	0.55	1,820
Day 3	NA	NA	3.5	1,390	NA	NA
Day 4	NA	NA	1.1	1,380	NA	NA
Average	1.4	880	3.2	1,460	0.36	1,800
Total Recovered (gal)	2.5	1,550	11.5	5,220	0.50	2,480

NA = Not applicable.

extraction rate of 880 gallons/day (Table 16). Results of LNAPL recovery versus time are shown in Figure 13.

### 3.3.3.2 Bioslurper Pump Test Results

LNAPL recovery rates increased during the bioslurper pump test (Figure 13). The increase in recovery rate indicates that LNAPL was mobilized to the extraction well under vacuum-enhanced conditions. A total of 11.5 gallons of LNAPL and 5,220 gallons of groundwater were extracted during the bioslurper pump test, with average recovery rates of 3.2 gallons/day for LNAPL and 1,460 gallons/day for groundwater (Table 16). The LNAPL recovery rate versus time is shown in Figure 14. The vacuum-exerted wellhead pressure on monitoring well LF-1-3 was kept relatively constant throughout the bioslurper pump test at approximately 16 inches of mercury.

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Oxygen concentrations increased slightly at all monitoring points where a soil gas sample could be collected (Table 17). Given the low permeability of the soil, a longer time period than the length of this test may be necessary to fully




Figure 13. LNAPL Recovery Versus Time During Each Pump Test at Site SS010




Figure 14. LNAPL Recovery Rate Versus Time During the Bioslurper Pump Test at Site SS010

**Table 17. Oxygen Concentrations During the Bioslurper Pump Test at Site SS010, Robins AFB, GA**

Monitoring Point	Oxygen Concentrations (%) Versus Time (minutes)				
	0	4.5	26	48	80
R2-MPA-2.0'	19.5	19.6	19.5	19.8	19.8
R2-MPA-4.0'	5.0	5.2	5.5	5.7	5.7
R2-MPA-6.0'	NM	NM	NM	NM	NM
R2-MPB-2.0'	19.2	19.5	19.5	19.7	19.8
R2-MPB-4.0'	9.2	9.3	9.5	9.8	9.9
R2-MPB-6.0'	NM	NM	NM	NM	NM
R2-MPC-2.0'	15.2	15.4	15.7	15.9	16.0
R2-MPC-4.0'	9.3	9.6	9.6	9.9	9.9
R2-MPC-6.0'	NM	NM	NM	NM	NM

NM Not measured. Excess soil moisture prohibited collection of soil gas samples.

oxygenate the soils. However, based on these results, it is likely that soils will become oxygenated over time. These results correlate with radius of influence results from the soil gas permeability test.

### 3.3.3.3 Drawdown Pump Test

Totals of 0.50 gallon of LNAPL and 2,480 gallons of groundwater were recovered during the drawdown pump test, with average recovery rates of 0.36 gallon/day for LNAPL and 1,800 gallons/day for groundwater (Table 16). These results demonstrate that operation of the bioslurper system in the drawdown mode was not as effective a means of free-product recovery as the bioslurper system at this site.

### 3.3.4 Emulsion Control and Extracted Groundwater, LNAPL, and Off-Gas Analyses

During the skimmer, bioslurper, and drawdown pump tests, the emulsion control system minimized the formation of the solid fuel/water emulsion; however, the liquid fuel/water emulsion was not affected. Consequently, contaminant concentrations were not significantly reduced by the emulsion control system. Treatment through activated carbon resulted in BTEX and TPH concentrations reduced to below detection limits (Table 18).

**Table 18. BTEX and TPH Concentrations in Extracted Groundwater During the Bioslurper Pump Test at Site SS010, Robins AFB, GA**

Parameter	Concentration (mg/L)				
	TPH	Benzene	Toluene	Ethylbenzene	Total Xylenes
R2-H2O-1	46	0.19	0.052	0.39	0.58
R2-H2O-2	36	0.099	0.047	<0.00050	0.14
R2-H2O-3	22	0.36	0.30	0.092	0.57
R2-H2O-4	<0.50	<0.00050	<0.00050	<0.00050	<0.00050
R2-OutH2O-1	<0.50	<0.0010	<0.0010	<0.0010	<0.0010
R2-OutH2O-2	<0.50	<0.0010	<0.0010	<0.0010	<0.0010

Off-gas samples from the bioslurper system also were collected during the bioslurper pump test. The results from the off-gas analyses are presented in Table 19. Given a vapor discharge rate of 5.5 scfm and using an average concentration of 680 ppmv TPH<sup>1</sup>, approximately 2.2 lb/day of TPH was emitted to the air during the bioslurper pump test. Benzene emissions were approximately 0.021 lb/day.

The composition of LNAPL is shown in Tables 20 and 21 in terms of BTEX concentrations and distribution of C-range compounds, respectively. The distribution of C-range compounds is shown graphically in Figure 15.

---

<sup>1</sup> This concentration was considered to be more representative of actual long-term operating conditions.

**Table 19. BTEX and TPH Concentrations in Off-Gas During the Bioslurper Pump Test at Site SS010, Robins AFB, GA**

Parameter	Concentration (ppmv)	
	R2-Stack-1	R2-Stack-2
TPH	60,000	680
Benzene	830	13
Toluene	890	21
Ethylbenzene	200	6.7
Total Xylenes	750	29


**Table 20. BTEX Concentrations in LNAPL from Site SS010, Robins AFB, GA**

Compound	Concentration (mg/kg)
Benzene	< 720
Toluene	1,400
Ethylbenzene	2,200
Total Xylenes	18,000



**Table 21. C-Range Compounds in LNAPL from Site SS010, Robins AFB, GA**

<b>C-Range Compound</b>	<b>Percentage of Total</b>
<C9	38.7
C10	19.3
C11	15.6
C12	11.1
C13	8.3
C14	3.9
C15	1.9
C16	0.63
>C17	0.45



c:\plot\501\bioc\urp\robins\crange2.sp5

**Figure 15. Distribution of C-Range Compounds in Extracted LNAPL at Site SS010, Robins AFB, GA**

### 3.3.5 Bioventing Analyses

#### 3.3.5.1 Soil Gas Permeability and Radius of Influence

The radius of influence is calculated by plotting the log of the pressure change at a specific monitoring point versus the distance from the extraction well. The radius of influence is then defined as the distance from the extraction well where 0.1 inch of H<sub>2</sub>O can be measured. Based on this definition, the radius of influence at this site is approximately 76 ft (Figure 16).

#### 3.3.5.2 In Situ Respiration Test Results


Results from the in situ respiration test are presented in Table 22. Oxygen depletion was relatively rapid, with oxygen utilization rates ranging from 0.20 to 0.27% O<sub>2</sub>/hr. Biodegradation rates ranged from 3.3 to 4.5 mg/kg-day. The helium concentration was steady, indicating that leakage and diffusion were insignificant.

Table 22. In Situ Respiration Test Results at Site SS010, Robins AFB, GA

Monitoring Point	Oxygen Utilization Rate (%/hr)	Biodegradation Rate (mg/kg-day)
R2-MPA-4.0'	0.27	4.3
R2-MPB-4.0'	0.20	3.2
R2-MPC-4.0'	0.27	4.3

### 3.4 Discussion

Free-product recovery was poor at this site during all pump tests. The maximum recovery rate was achieved during the bioslurper pump test; however, the average recovery rate was 3.2 gallons/day compared to an average groundwater extraction rate of 1,500 gallons/day. Free-product recovery may be limited due to the site hydrogeology, to the condition that only small quantities of free product may be present.



**Figure 16. Soil Gas Pressure Change as a Function of Distance During the Soil Gas Permeability Test at Site SS010**

Soil gas concentrations were measured at monitoring points during the bioslurper pump test to determine whether the vadose zone was being oxygenated. Oxygen concentrations increased slightly at all monitoring points where a soil gas sample could be collected. As at Site UST 70/72, given the low permeability of the soil, a longer time period than the length of this test may be necessary to fully oxygenate the soils. However, based on these results, it is likely that soils will become oxygenated over time.

Implementation of bioslurping at Site SS010 does not appear to be a feasible option for free-product recovery due to the low recovery rate versus the high groundwater extraction rate. Given that free-product recovery was poor during all pump tests, the quantity of free product present may be low. Therefore, intrinsic bioremediation may be a more appropriate option for this site.

#### 4.0 REFERENCES

Battelle. 1995. *Test Plan and Technical Protocol for Bioslurping*, Report prepared by Battelle Columbus Operations for the U.S. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

Hinchee, R.E., S.K. Ong, R.N. Miller, D.C. Downey, and R. Frandt. 1992. *Test Plan and Technical Protocol for a Field Treatability Test for Bioventing* (Rev. 2), Report prepared by Battelle Columbus Operations, U.S. Air Force Center for Environmental Excellence, and Engineering Sciences, Inc. for the U.S. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

**APPENDIX A**

**SITE-SPECIFIC TEST PLAN FOR BIOSLURPER FIELD ACTIVITIES  
AT ROBINS AFB, GEORGIA**

**SITE-SPECIFIC TEST PLAN FOR BIOSLURPER TESTING AT  
ROBINS AIR FORCE BASE, GEORGIA (A002)  
CONTRACT NO. F41624-94-C-8012**

**FINAL**

**to**

**U.S. Air Force Center for Environmental Excellence  
Technology Transfer Division  
(AFCEE/ERT)  
8001 Arnold Drive  
Building 642  
Brooks AFB, TX 78235**

**June 5, 1995**

**by**

**Battelle  
505 King Avenue  
Columbus, OH 43201**

*This report is a work prepared for the United States Government by Battelle. In no event shall either the United States Government or Battelle have any responsibility or liability for any consequences of any use, misuse, inability to use, or reliance upon the information contained herein, nor does either warrant or otherwise represent in any way the accuracy, adequacy, efficacy, or applicability of the contents hereof.*



## TABLE OF CONTENTS

LIST OF TABLES .....	ii
LIST OF FIGURES .....	ii
1.0 INTRODUCTION .....	1
2.0 SITE DESCRIPTION .....	2
2.1 Site SS010 .....	2
2.2 UST #70 and #72 Site .....	4
3.0 PROJECT ACTIVITIES .....	6
3.1 Mobilization to the Site .....	6
3.2 Site Characterization Tests .....	7
3.2.1 Baildown Tests .....	7
3.2.2 Soil-Gas Survey (Limited) .....	7
3.2.3 Slug Tests .....	7
3.2.4 Monitoring Point Installations .....	9
3.2.5 Soil Sampling .....	9
3.3 Bioslurper System Installation and Operation .....	9
3.3.1 System Setup .....	13
3.3.2 System Shakedown .....	13
3.3.3 System Startup and Test Operations .....	13
3.3.4 Soil-Gas Permeability Tests .....	13
3.3.5 LNAPL and Water Level Monitoring .....	13
3.3.6 In Situ Respiration Tests .....	14
3.3.7 Extended Testing .....	14
3.4 Demobilization .....	14
4.0 BIOSLURPER SYSTEM DISCHARGE .....	14
4.1 Vapor Discharge Disposition .....	14
4.2 Aqueous Influent/Effluent Disposition .....	15
4.3 Free-Product Recovery Disposition .....	16
5.0 SCHEDULE .....	16
6.0 PROJECT SUPPORT ROLES .....	16
6.1 Battelle Activities .....	17
6.2 Robins AFB Support Activities .....	17
6.3 AFCEE Activities .....	19
7.0 REFERENCES .....	19
APPENDIX A: CONE PENETROMETER-LASER INDUCED FLUORESCENCE SENSOR DATA FOR ROBINS AFB, GA .....	A-1

APPENDIX B:	SITE CHARACTERIZATION DATA FOR SITE SS010 . . . . .	B-1
APPENDIX C:	SITE CHARACTERIZATION DATA FOR THE UST #70 AND #72 SITE . . . . .	C-1
APPENDIX D:	LETTER DETAILING WATER DISCHARGE FLOWRATE AND CONCENTRATIONS . . . . .	D-1

## LIST OF TABLES

Table 1.	Free Product Thickness Measurements for Site SS010 . . . . .	4
Table 2.	Schedule of Bioslurper Test Activities . . . . .	6
Table 3.	Benzene and TPH Discharge Levels at Previous Bioslurper Test Sites . . . . .	15
Table 4.	Air Release Summary Information . . . . .	16
Table 5.	Health and Safety Information Checklist . . . . .	18

## LIST OF FIGURES

Figure 1.	Schematic Diagram Showing Areas of interest for Bioslurper Testing at Site SS010, Robins AFB, GA . . . . .	3
Figure 2.	Schematic Diagram Showing Location of Monitoring Wells at UST #70 and #72 Site, Robins AFB, GA . . . . .	5
Figure 3.	General Bioslurper Well and Monitoring Point Arrangement . . . . .	8
Figure 4.	Schematic Diagram of a Typical Soil-Gas Monitoring Point . . . . .	10
Figure 5.	Bioslurper Process Flow . . . . .	11
Figure 6.	Schematic Diagram of a Typical Bioslurper Well . . . . .	12

# **FINAL SITE-SPECIFIC TEST PLAN FOR BIOSLURPER FIELD ACTIVITIES AT ROBINS AIR FORCE BASE, GEORGIA**

**June 5, 1995**

**to**

**U.S. Air Force Center for Environmental Excellence  
Technology Transfer Division  
AFCEE/ERT  
Brooks AFB, TX**

## **1.0 INTRODUCTION**

The Air Force Center for Environmental Excellence (AFCEE) Technology Transfer Division is conducting a nationwide application of an innovative technology for free-product recovery and soil bioremediation. The technology being tested is vacuum-enhanced free-product recovery with bioremediation (bioslurping). The field test and evaluation are intended to demonstrate the initial feasibility of bioslurping by measuring system performance in the field. The Bioslurper Initiative has been designed to evaluate the effectiveness of bioslurping as a light, non-aqueous phase liquid (LNAPL) recovery technology relative to conventional gravity-driven recovery technologies. System performance parameters, mainly free-product recovery, will be determined at numerous sites. Field testing will be performed at many sites to determine the effects of different organic contaminant types and concentrations and different geological conditions on bioslurping effectiveness.

Plans for the field test activities are presented in two documents. The first is the overall Test Plan and Technical Protocol for the entire program, titled *Test Plan and Technical Protocol for Bioslurping* (Battelle, 1995). The overall plan is supplemented by plans specific to each test site. The concise site-specific plans communicate vapor and aqueous discharge rates to ensure compliance with regulatory requirements specific to the base.

The overall Test Plan and Technical Protocol was developed as a generic plan for the Bioslurper Initiative to improve the accuracy and efficiency of Test Plan preparation. The field program requires installation and operation of the bioslurping system supported by a wide variety of site characterization, performance monitoring, and chemical analysis activities. The basic methods to be applied from site to site do not change. Preparation and review of the overall plan allows efficient documentation and review of the basic approach to the test program. Peer and regulatory review were performed for the overall plan to ensure the credibility of the overall program.

This letter report is the site-specific plan for application of bioslurping at Robins Air Force Base (AFB), Georgia. It was prepared based on site-specific information received by Battelle from Robins AFB and other pertinent site-specific information to support the generic test plan.

Site-specific information for Robins AFB included data for the two pilot test locations: the JP-4 Spill Site (Zone 4-JP-4 Fuel Spill Site SS010, referred to as Site SS010 in text) and the Underground Storage Tank (UST) #70 and #72 Site. An initial review of the data for Site SS010 indicates that Well #LF1-3 appears to be the best candidate for the bioslurper field test. If Well #LF1-3 is found unsuitable for testing, Well #RI-4-JP-6 is a viable alternative. At the UST #70 and #72 Site, the well

that appears to be the best candidate for bioslurper testing is Well #EA-2. If Well #EA-2 is found to be unsuitable for testing or site logistics prevent its use, then Well #EA-1 could be used as an alternative extraction well for the bioslurper pilot test. Also, in order to supplement existing site characterization data and the bioslurper testing, AFCEE/ERT has mobilized a cone penetrometer equipped with an innovative laser induced fluorescence sensor (CPT-LIF). The laser induced fluorescence sensor provides useful information on fuel contamination distribution for both Robins AFB sites based on the fluorescence response to polycyclic aromatic fuel constituents (i.e. naphthalene). CPT-LIF data is presented in Appendix A for locations near both sites at Robins AFB.

## 2.0 SITE DESCRIPTION

### 2.1 Site SS010

The site description of Site SS010 has been adapted from the *Installation Restoration Program RCRA Facility Investigation Report for Robins AFB* prepared by CH2M Hill Southeast, Inc. (August 1989). This document is referred to as IRP 1989 in the text. The JP-4 fuel storage tanks in Zone 4 are supplied by a 4-inch-diameter steel pipe running from the Standard Transmission Corporation Tank Farm located to the north of Robins AFB. Two major fuel spills have occurred in Zone 4 during the past 30 years. The first fuel spill occurred in the mid-1960s when a leak in the 4-inch supply line was discovered. An undetermined amount of JP-4 jet fuel was released in the area north of the petroleum, oil, and lubricants (POL) bulk storage area in the vicinity of Landfill No.1. The pipeline was repaired; however, none of the JP-4 jet fuel was recovered. The second spill occurred in the early 1970s. An estimated 60,000 gallons of JP-4 jet fuel was released to the surface when a POL storage tank overflowed. During the overflow, the containment dike valve had been left open and the fuel was able to flow into drainage ditches that lead to Horse Creek. A small, undetermined volume of the JP-4 jet fuel was recovered during cleanup operations. However, recent site characterization studies have shown that a large LNAPL plume is still present at Site SS010.

Figure 1 is a site map that depicts Site SS010, Robins AFB. This figure appeared in the IRP 1989 report. Table 1 provides data for the free-product thickness measurements made on February 5 and 6 and April 4 and 8, 1991, by base personnel. A generalized cross section extending north-south across Site SS010 is also presented in Appendix B. From these data, the wells that are most likely to yield significant amounts of free product have been identified. Well #LF1-3 had the largest fuel thickness during the February 5, 1991, measurement and has shown the greatest amount of free-product recovery throughout the measurement period. Soil-gas concentrations of total petroleum hydrocarbon (TPH) and benzene in 1992 were approximately 55,000 ppm and 270 ppm, respectively. Groundwater near the site ranges from 6.75 to 8.25 ft. Site characterization will start with Site SS010 and will focus on Well #LF1-3. If preliminary site characterization indicates that Site SS010 is unsuitable, or if site logistics prevent the use of wells in that area, the AFCEE/ERT and Base Point of Contact (POC) will be notified immediately to discuss alternative sites where the bioslurper pilot demonstration could be conducted.




Figure 1. Schematic Diagram Showing Areas of Interest for Bioslurper Testing at Site SS010, Robins AFB, GA

Table 1. Free Product Thickness Measurements for Site SS010

Well ID	Date	LNAPL Thickness (ft)
LF1-3	February 5, 1991	1.9
	April 4, 1991	1.2
RI-4-JP-6	February 6, 1991	0.9
	April 8, 1991	0.5

## 2.2 UST #70 and #72 Site

The site description of the UST #70 and #72 Site has been adapted from the *Contamination Assessment Report for the Underground Storage Tank Systems at UST Sites #70 and #72 for Robins AFB* prepared by EA Engineering, Science, and Technology (November 1994). This document is referred to as CAR 1994 in the text. The UST #70 and #72 Site is in the 19th and 912th Air Refueling Wing area located in the northeastern quadrant of Robins AFB. The UST #70 and #72 Site serves as large aircraft refueling/defueling hydrant system, which provides ground support to the Air Refueling Wings operating at Robins AFB.

Figure 2 shows the location of monitoring wells and the estimated extent of free product within the UST #70 and #72 Site. Free-product recovery data, geologic cross sections, and boring logs for the wells within the UST #70 and #72 Site are located in Appendix C. The aircraft refueling/defueling hydrant system at UST #70 consists of a small storage building, a pumphouse/control room, six 50,000-gal steel USTs currently containing JP-8, a 2,000-gal steel UST containing waste JP-8, a 400-gal UST containing water, and approximately 5,200 ft of 4- to 6-inch-diameter steel fueling/defueling lines that supply six hydrants located on the adjacent parking apron. UST #72 is identical to UST #70, in that it has the same tankage and piping configuration. It is located directly north of UST #70.

The #70 and #72 USTs were installed in 1958 and have been used continuously since that time. The two systems originally stored JP-4 jet fuel and were not converted over to JP-8 jet fuel until June 1994. According to the Fuels Maintenance Branch staff at Robins AFB, large nondocumented releases of JP-4 jet fuel have occurred at UST#70 several times. The releases were controlled by the Base Fire Department, which hosed the spilled JP-4 jet fuel with water. The resultant contamination of the clean up occurred off the parking lot aprons and into the soils and storm drains adjacent to the site.

Analytical data taken during the CAR 1994 report listed groundwater concentration of benzene ranged from approximately <0.0010 to 4.2 mg/L, and the TPH concentration in soils ranged from approximately <270 to 5,700 mg/kg. Groundwater at the site is found at 7 ft bgs. From the initial review of data presented in the CAR 1994 report it appears that Wells #EA-2 and #EA-1 are the best candidates for the short-term bioslurper test. These wells had persistent measurements of LNAPL thickness during the CAR 1994 report.




Figure 2. Schematic Diagram Showing Location of Monitoring Wells at UST #70 and #72 Site, Robins AFB, GA

### 3.0 PROJECT ACTIVITIES

The following field activities are planned for the bioslurper pilot test at Robins AFB. Additional details about the activities are presented in the *Test Plan and Technical Protocol for Bioslurping* (Battelle, 1995). As appropriate, specific sections in the generic Test Plan and Technical Protocol are referenced. Table 2 shows the schedule of activities for the Bioslurper Initiative at Robins AFB.

#### 3.1 Mobilization to the Site

After the site-specific Test Plan is approved, Battelle staff will mobilize equipment. Some of the equipment will be shipped via air express to Robins AFB prior to staff arrival. The Base POC will have been asked in advance to find a suitable holding facility to receive the bioslurper pilot test equipment so that it will be easily accessible to the Battelle staff when they arrive with the remainder of the equipment. The exact mobilization date will be confirmed with the Base POC as far in advance of fieldwork as is possible. The Battelle POC will provide the Base POC with information on each Battelle employee who will be on site. Battelle personnel will be mobilized to the site after it has been confirmed that the shipped equipment has been received by Robins AFB.

Table 2. Schedule of Bioslurper Test Activities

Pilot Test Activity	Schedule
Mobilization	day 1-2
Site Characterization	day 2-3
Baildown Tests and Product/Groundwater Interface Monitoring	
Soil-Gas Survey (limited)	
Slug Tests	
Monitoring Point Installation (3 MPs)	
Soil Sampling (TPH, BTEX, physical characteristics)	
System Installation	day 2-3
Test Startup	day 3
Skimmer Test (2 days)	day 3-4
Bioslurper Vacuum Extraction (4 days)	day 6-9
Soil-Gas Permeability Testing	day 6
Skimmer Test (continued)	day 10
In Situ Respiration Test — air/helium injection	day 10
In Situ Respiration Test — monitoring	day 11-16
Drawdown Pump Test (2 days)	day 11-12
Demobilization/Mobilization	day 13-14



## **3.2 Site Characterization Tests**

### **3.2.1 Baildown Tests**

The baildown test is the primary test for selection of the bioslurper test well. Baildown tests will be performed at wells that contain measurable free product to estimate the recovery potential at those particular wells. At the Site SS010, baildown tests will be performed on Wells #LF1-3 and #RI-4-JP-6. For the UST #70 and #72 Site, baildown tests will be performed on Wells #EA-1 and #EA-2. Detailed procedures for the baildown tests are provided in Section 5.6 of the Test Plan and Technical Protocol.

### **3.2.2 Soil-Gas Survey (Limited)**

If existing monitoring points are suitably located, no new monitoring will be installed. If installation of monitoring points is required, a small-scale soil-gas survey will be conducted to identify the best location for installation of the bioslurping system soil gas monitoring points. The soil-gas survey will be conducted in areas where historical site data indicate the highest contamination levels of floating LNAPL. These areas will be surveyed to select the locations for installation of soil-gas monitoring points. Soil-gas monitoring points will be located in areas that exhibit the following soil-gas characteristics:

1. Relatively high TPH concentrations (10,000 ppm or greater).
2. Relatively low oxygen concentrations (between 0% and 5%).
3. Relatively high carbon dioxide concentrations (depending on soil type, between 2% and 10% or greater).

To obtain further information about the soil-gas survey, consult Section 5.2 of the Test Plan and Technical Protocol.

### **3.2.3 Slug Tests**

Slug tests will be performed to determine the characteristics of the aquifer where the candidate bioslurper test well is located. Slug tests will be performed using one or more in situ pressure transducers and data loggers to track pressure (water-level) changes and a polyvinyl chloride (PVC) capsule (slug) to introduce a rapid level change. Slug tests will be performed on wells that do not have any measurable free product. Using the data collected during the slug test, the aquifer characteristics at Site SS010 and the UST #70 and #72 Site will be compared with those at other bioslurper test sites. Additional information about the slug test methods can be found in Section 5.7 of the Test Plan and Technical Protocol.

### **3.2.4 Monitoring Point Installations**

Monitoring points will be installed to determine the radius of influence of the bioslurper system in the vadose zone. A general arrangement of the bioslurping well and monitoring points is shown in Figure 3.




Figure 3. General Bioslurper Well and Monitoring Point Arrangement

Upon conclusion of the initial soil-gas survey and baildown tests, at least three soil-gas monitoring points will be installed at each site to measure soil-gas changes that occur during bioslurper operation. A digging clearance or permit will be obtained by the Base POC before Battelle staff arrive at the base. These monitoring points will be located in highly contaminated soils within the free-phase plumes and will be positioned to allow detailed monitoring of the in situ changes in soil-gas composition caused by the bioslurper system. A schematic diagram of a typical soil-gas monitoring point is shown in Figure 4. Additional information on monitoring point installation can be found in Section 4.2.1 of the Test Plan and Technical Protocol.

### **3.2.5 Soil Sampling**

Soil samples will be collected to determine the physical and chemical composition of the soil. Soil samples will be collected from the boreholes advanced for monitoring point installation at two or three locations. Generally, samples will be collected from the capillary fringe over the free product.

Soil samples from each boring will be analyzed for benzene, toluene, ethylbenzene, and xylenes (BTEX); bulk density; moisture content; particle-size distribution; porosity; and TPH. Section 5.5.1 of the Test Plan and Technical Protocol will be consulted for information on the field measurements and sample collection procedures for soil sampling.

## **3.3 Bioslurper System Installation and Operation**

As stated previously, Wells #LFI-3 and #EA-2 most likely will be used for the bioslurper test demonstrations at Site SS010 and the UST #70 and #72 Site, respectively. Once the wells to be used have been selected, the bioslurper and support equipment will be installed.

### **3.3.1 System Setup**

Upon completion of the site characterization activities and the bioslurper system assembly, the LNAPL recovery tests will be initiated. Figure 5 is a flow diagram of the bioslurper process. Figure 6 is a schematic diagram of a typical bioslurper extraction wellhead and extraction tube that will be installed on existing extraction wells at the two Robins AFB test sites.

Before the LNAPL recovery tests are initiated, all relevant baseline field data will be collected and recorded. These data will include soil-gas concentrations, initial soil-gas pressures, depth to groundwater, and LNAPL thickness. All the atmospheric conditions (e.g., temperature, humidity, barometric pressure) also will be recorded. All emergency equipment (i.e., emergency shutoff switches and fire extinguishers) will be installed and checked for proper operation at this time.

A clear, level area near the well selected for the bioslurper test installation will be identified for the 20' X 10' flatbed trailer that holds the equipment required for the bioslurper system operation. For more information on bioslurper system installation, consult Section 6.0 of the Test Plan and Technical Protocol.




Figure 4. Schematic Diagram of a Typical Soil-Gas Monitoring Point




Figure 5. Bioslurper Process Flow




Figure 6. Schematic Diagram of a Typical Bioslurper Well

### **3.3.2 System Shakedown**

A brief startup test will be conducted to ensure that the system is constructed properly and operates safely. All system components will be checked for problems and/or malfunctions. A checklist will be provided to document the system shakedown.

### **3.3.3 System Startup and Test Operations**

After installation is complete and the bioslurper system is confirmed to be operating properly, the LNAPL recovery tests will be started. The Bioslurper Initiative has been designed to evaluate the effectiveness of bioslurping as an LNAPL recovery technology relative to conventional gravity-driven LNAPL recovery technologies. The Bioslurper Test Plan and Technical Protocol includes three separate LNAPL recovery tests: (1) a skimmer simulation test, (2) a vacuum-assisted bioslurper test, and (3) a groundwater drawdown LNAPL recovery test. The three recovery tests are described in detail in Section 7.3 of the Test Plan and Technical Protocol.

The bioslurper operating parameters that will be measured during operation are vapor discharge, aqueous effluent, LNAPL recovery volume rates, vapor discharge volume rates, and groundwater discharge volume rates. Vapor monitoring will consist of intermittent monitoring of TPH using hand-held instruments supplemented by two samples collected for detailed laboratory analysis. A total of two samples of aqueous effluent will be collected for analysis of BTEX and TPH. Recovered LNAPL volume will be recorded using an in-line flow-totalizing meter. The off-gas discharge volume will be measured using a calibrated pitot tube, and groundwater discharge volume will be recorded using an in-line flow-totalizing meter. Section 8.0 of the Test Plan and Technical Protocol describes process monitoring of the bioslurper system.

### **3.3.4 Soil-Gas Permeability Tests**

A soil-gas permeability test will be conducted concurrently with startup of the bioslurper operation. Soil-gas permeability data will provide data for estimating the vadose zone radius of influence of the bioslurper system. Soil-gas permeability results also will aid in determining the number of wells required if it is decided to treat the site with a large-scale bioslurper system. The soil-gas permeability test method is described in Section 5.7 of the Test Plan and Technical Protocol.

### **3.3.5 LNAPL and Water Level Monitoring**

During the bioslurper test, the LNAPL and water levels will be monitored in a well adjacent to the extraction well. The top of the monitoring well will be sealed from the atmosphere to contain the subsurface vacuum. Additional information for monitoring of fluid levels during the bioslurper pilot test can be found in Section 4.3.4 of the Test Plan and Technical Protocol.

### **3.3.6 In Situ Respiration Tests**

An in situ respiration test will be conducted after completion of the bioslurper tests. The in situ respiration testing will involve injection of air and helium injection into selected soil-gas monitoring points followed by monitoring changes in concentration of oxygen, carbon dioxide, petroleum hydrocarbons, and helium in soil-gas near the injection point. Measurement of the soil-gas composition typically will be conducted at 2, 4, 6, and 8 hours and then every 4 to 12 hours for about 2 days.

Timing of the tests will be adjusted based on oxygen-use rate. If oxygen depletion occurs rapidly, more frequent monitoring will be conducted. If oxygen depletion is slow, less frequent readings will be acceptable. In situ respiration rates measured during the bioslurper pilot testing will be compared to the respiration rates estimated from Site SS010 bioventing testing. The oxygen utilization rate will be used to estimate the biodegradation rate at the site. Further information on the procedures and data collection for in situ respiration testing is given in Section 5.8 of the Test Plan and Technical Protocol.

### **3.3.7 Extended Testing**

The AFCEE/ERT has the option of extending the operation of the bioslurper system for up to 6 months, if LNAPL recovery rates are promising and viable long-term vapor and aqueous discharge requirements have been identified. If extended testing is to be performed, Robins AFB will need to provide electrical power for long-term operation of the bioslurper pump. Disposition of all generated wastes and routine operation and maintenance of the system will be the Air Force's responsibility. Battelle will provide technical support during the extended testing operation.

## **3.4 Demobilization**

Once all necessary tests have been completed at the Robins AFB sites, the equipment will be disassembled by Battelle staff and moved back to the holding facility, where it will remain until its next destination is determined. Battelle staff will receive this information and will be responsible for shipment of the equipment to the next site before they leave Robins AFB.

## **4.0 BIOSLURPER SYSTEM DISCHARGE**

### **4.1 Vapor Discharge Disposition**

Battelle expects that the operation of the bioslurper test system at the Robins AFB sites may require a waiver or a point source air release registration. At Site SS010, it can be assumed that the concentration of hydrocarbons released to the atmosphere will be approximately 65 lb TPH/day and < 1.0 lb benzene/day. This value is based on the average TPH discharge level at two bioslurper test sites (Wright-Patterson AFB and Travis AFB) that are contaminated with jet fuel. The value may vary depending on the TPH concentration of the soil-gas and the permeability of the soils found at Site SS010. The concentration of aromatic hydrocarbons released to the atmosphere at the UST #70 and #72 Site should be less than 65 lb TPH/day. The data for the TPH and benzene vapor discharge levels for five previous bioslurper test sites are presented in Table 3. The relatively large TPH discharge level at Travis AFB is partially due to the extraction rate of the soil-gas vapors. The extraction rate at Travis AFB is the maximum rate a 3-hp pump will achieve and likely will be much less at Robins AFB due to the nature of the site soils. The vapor stream generated by the bioslurper system may be discharged directly to the atmosphere because of the short duration of the test and the low concentration levels of TPH and benzene in the stream. However, a short-term pumping waiver (9 to 10 days per site) is requested.



**Table 3. Benzene and TPH Discharge Levels at Previous Bioslurper Test Sites**

Site Location	Fuel Type	Extraction Rate (scfm)	Benzene (ppmv)	TPH (ppmv)	Benzene Discharge (lb/day)	TPH Discharge (lb/day)
Wright-Patterson AFB	Jet Fuel	3	ND	595	0.0	1.0
Bolling AFB (Site #1)	No. 2 Fuel Oil	4	0.2	153	0.0003	0.009
Bolling AFB (Site #2)	Gasoline	21	370	70,000	2.3	470.1
Andrews AFB	No. 2 Fuel Oil	8	16	2,000	0.01	0.2
Travis AFB	Jet Fuel	20	100	10,800	0.58	126.4

ND = Not detected

Based on site visits, site layouts, and locations it has been determined that no unacceptable health risks will result from the bioslurper pilot tests at Robins AFB. However, to ensure the safety and regulatory compliance of the bioslurper system, vapor discharge samples (TPH, O<sub>2</sub>, and CO<sub>2</sub>) will be collected periodically throughout the bioslurper pilot test, and field soil-gas screening instruments will be used to monitor vapor discharge concentration variability. The volume of vapor discharge will be monitored daily using airflow instruments. If state regulatory requirements will not permit the expected amount of organic vapor discharge to the atmosphere, the Base POC should inform AFCEE and Battelle so that alternative plans can be made prior to mobilization to the site. Table 4 provides information typically required to complete an air release registration form. Highly stringent discharge allowances may compromise AFCEE's ability to conduct site testing. Therefore, a short-term discharge allowance is requested.

#### **4.2 Aqueous Influent/Effluent Disposition**

The flowrate of groundwater pumped by the bioslurper will be less than 5 gpm (estimated at 1.25 gpm). However, it may be necessary to obtain a groundwater pumping waiver or registration permit in Georgia. If one is required, the Base POC will inform Battelle of the necessary steps in obtaining the waiver or permit.

Operation of the bioslurper system will generate an aqueous waste discharge that will be passed through an oil/water separator. The intention of Battelle staff will be to dispose of the wastewater by discharge directly to the Base industrial wastewater treatment plant (IWTP). If existing Base wastewater channels can be used, no water discharge permits will be required. A copy of the letter that details the estimated concentrations of TPH and benzene expected in the system wastewater discharge is included in Appendix D. The expected levels of organic discharge in the wastewater

stream will be within the operational parameters of the IWTP and the downstream sewage treatment plant.

**Table 4. Air Release Summary Information**

<b>Data Item</b>	<b>Air Release Information</b>
Contractor Point of Contact	Jeff Kittel, (614) 424-6122
Contractor address	Battelle, 505 King Avenue, Columbus, OH 43201
Estimated total quantity of petroleum product to be recovered	TBD
Description of petroleum product to be recovered	Site SS010: JP-4 Jet Fuel
	UST #70 and #72 Site: JP-4 Jet Fuel
Planned date of test start	Tentatively scheduled as July 10, 1995
Test duration	9 days (active pumping)
Maximum expected VOC concentration in air	~65 lb/day (65 lb TPH/day, ~0.25 lb benzene/day)
Expected contaminants in air release	TPH, benzene
Stack height above ground level	10 ft

#### **4.3 Free-Product Recovery Disposition**

The bioslurper system will recover free-phase product from the pilot tests performed at Robins AFB. Free product recovered by the bioslurping tests will be turned over to the Base for disposal and/or recycling. The volume of free product recovered from the Base will not be known until the tests have been performed. The maximum recovery rate for this system is 5 gpm, but the actual rate of LNAPL recovery likely will be much lower.

#### **5.0 SCHEDULE**

The schedule for the bioslurper fieldwork at Robins AFB will depend on approval of the project Test Plan. Battelle will determine a definitive schedule as soon as possible after approval is received. Battelle will have two to three staff members on site for approximately 2 weeks to conduct all necessary pilot testing. At the conclusion of the field testing at Robins AFB, Battelle staff will return their Base passes and will remove all bioslurper field testing equipment from the Base before they leave the site.

#### **6.0 PROJECT SUPPORT ROLES**

This section outlines some of the major functions of personnel from Battelle, Robins AFB, and AFCEE during the bioslurper field test.

**Table 5. Health and Safety Information Checklist**

<u>Emergency Contacts</u>	<u>Name</u>	<u>Telephone Number</u>
Hospital Emergency Room:	_____	_____
Point of Contact:	_____	_____
Fire Department:	_____	_____
Emergency Unit (Ambulance):	_____	_____
Security:	_____	_____
Explosives Unit:	_____	_____
Community Emergency Response Coordinator:	_____	_____
Other:	_____	_____
 <u>Program Contacts</u>	 Patrick Haas	 210-536-4314
Air Force:	Mike Stevens	912-926-0983
Battelle:	Jeff Kittel	614-424-6122
Other:	Eric Drescher	614-424-3088
 <u>Emergency Routes</u>	_____	_____
Hospital (maps attached)		
Other: _____		

### 6.3 AFCEE Activities

The AFCEE POC will act as a liaison between Battelle and Base staff. The AFCEE POC will ensure that all necessary permits are obtained and the space required to house the bioslurper field equipment is found.

The following is a listing of Battelle, AFCEE, and Robins Base staff who can be contacted in cases of emergency and/or for required technical support during the bioslurper field initiative tests at Robins AFB.

Battelle POCs	Jeff Kittel	614-424-6122
	Eric Drescher	614-424-3088
AFCEE POC	Patrick Haas	210-536-4314
Robins AFB POC	Mike Stevens	912-926-0983
Regulator POCs		
Air:	_____	_____
Water:	Tom Kirby	_____

### 7.0 REFERENCES


Battelle. 1995. *Test Plan and Technical Protocol for Bioslurping*, Report prepared by Battelle Columbus Operations for the U.S. Air Force Center for Environmental Excellence, Brooks Air Force Base, Texas.

**APPENDIX A**

**CONE PENETROMETER-LASER INDUCED FLUORESCENCE SENSOR DATA  
FOR ROBINS AFB, GA**

Legend

- LIF Push
- 2" Sample Point
- ▽ Monitoring Well



Robins AFB Ga  
Survey Data

Fuel Area - Site 1

SCAPS

U.S. Army Corps of Engineers - Kansas City  
Geotechnical Branch


Date 13 February 1995

Scale 1" = 50' ±

Sheet 1 of 1

1RBND1  
LEFT BLANK  
DUMMY PUSH

CPT based SOIL  
CLASSIFICATION



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB <NEW>  
Probe Depth: 20.17

**CPT; 2RBNL1**



# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

**CPT; 3RBNL1**

Project; Robins AFB  
Probe Depth; 29.62

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 15.05

**CPT; 4RBNL1**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 15.00

**CPT; 5RBNL1**

6RBNL1  
LEFT BLANK

*1.5' concrete*

7RBNL1  
LEFT BLANK

*1.5' concrete*

CPT based SOIL  
CLASSIFICATION

0 Sands & Gravels  
1 Sand Mixtures  
2 Clay Mixtures  
3 Clays  
4 Silts  
5 Sands & Gravels

Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Wavelength  
at Peak (nm)

Depth (feet)

Depth (feet)

Laser induced  
fluorescence  
of POL via  
fiber optics

U. S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB

Probe Depth: 15.11

CPT: 8RBNL1

CPT based SOIL  
CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth: 16.45

**CPT; 9RBNL1**

Probing date: 02-09-1995

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 15.04

**CPT; 10RBNL1**



# CPT based SOIL CLASSIFICATION

Soils & Gravels  
Sand Mixtures  
Clays


Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

Fluorescence Intensity  
Norm. Counts - No BGND SUB

Fluorescence Intensity  
Norm. Counts - No BGND SUB

Wavelength  
at Peak (nm)



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-09-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 15.00

CPT; 11RBNL1

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-10-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 15.17

**CPT; 12RBNL1**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-10-1995

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth: 15.09

**CPT; 13RBNL1**

CPT based SOIL  
CLASSIFICATION

0 Gravel  
1 Sand & Gravel  
2 Sand  
3 Sand  
4 Sand  
5 Sand & Gravel

Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

0 Clays  
1 Silts  
2 Sand  
3 Sand  
4 Sand  
5 Sand & Gravel

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Wavelength  
at Peak (nm)

350 400 450 500 550 600

Depth (feet)

Depth (feet)

Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 15.09

**CPT; 14RBNL1**

Probing date: 02-10-1995

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**

Project; Robins AFB  
Probe Depth; 15.05

Site  
Characterization  
and Analysis  
Penetrometer System


**CPT; 15RBNL1**

Probing date: 02-10-1995

16RBNW1  
2" PVC  
SAMPLE POINT  
DEPTH 8 FT  
NEAR PUSH  
10RBNL1

17 RBNW1  
2" PVC  
SAMPLE POINT  
DEPTH 8 FT  
NEAR PUSH  
12RBNL1

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.62

**CPT; 18RBNL1**



# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 13.48

**CPT; 19RBNL1**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 13.13

**CPT; 20RBNL1**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.53

**CPT; 21RBNLP**

Probing date: 02-13-1995

# CPT based SOIL CLASSIFICATION

Sands & Gravels  
Sands  
Sand  
Mixture  
Clays  
Peats

Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

0 1 2 3 4 5

0 2 4 6 8 10

Fluorescence Intensity  
Norm. Counts - No Background

0 500 1000 1500 2000 2500 3000

Fluorescence Intensity  
Norm. Counts - No Background

0 100 1000 10000

Wavelength  
at Peak (nm)

350 400 450 500 550 600

Depth (feet)

Depth (feet)

Laser Induced  
Fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995


SCAPS

Project: Robins AFB  
Probe Depth: 13.49

Site  
Characterization  
and Analysis  
Penetrometer System

CPT; 22RBNLP

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of POL via fiber optics

U.S. Army Engineer District Kansas City Geotechnical Branch

Probing date: 02-13-1995


SCAPS

Site Characterization and Analysis Penetrometer System

Project: Robins AFB  
Probe Depth: 16.52

CPT; 23RBNLP

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.38

**CPT: 24RBNLP**

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of PDL via fiber optics

U.S. Army Engineer District Kansas City Geotechnical Branch

Probing date: 02-13-1995


SCAPS

Site Characterization and Analysis Penetrometer System

Project: Robins AFB  
Probe Depth: 16.51

CPT; 25RBNLP

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 19.85

**CPT; 26RBNLP**



# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 13.18

**CPT; 27RBNLP**

Probing date; 02-13-1995

CPT based SOIL  
CLASSIFICATION

Gravels  
Sands  
Silt  
Mixtures  
Clays

Cone Resistance  
 $Q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

0 1 2 3 4 5  
Gravels  
Sands  
Silt  
Mixtures  
Clays

Fluorescence Intensity  
Norm. Counts - No BGND Sub  
0 250 500 1000 1500 2000 2500

Fluorescence Intensity  
Norm. Counts - No BGND Sub  
1 10 100 1000 10000

Wavelength  
at Peak (nm)  
350 400 450 500 550 600

Depth (feet)

Depth (feet)

Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 16.56

**CPT; 28RBNLP**

# CPT based SOIL CLASSIFICATION



Laser Induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-13-1995

*SCAPS*


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB

Probe Depth: 16.41

CPT: 29RBNLP

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.51

**CPT; 30RBNLP**

Probing date: 02-13-1995

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Project: Robins AFB  
Probe Depth: 16.93


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

**CPT; 32RBNL1**

Probing date: 02-13-1995

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of PDL via fiber optics

U.S. Army Engineer District Kansas City Geotechnical Branch

Probing date: 02-13-1995


SCAPS

Site Characterization and Analysis Penetrometer System

CPT; 33RBNL1

Project; Robins AFB  
Probe Depth; 13.20

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of PDL via fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch


**SCAPS**

Project; Robins AFB  
Probe Depth; 24.81

Site Characterization and Analysis Penetrometer System  
**CPT; 37RBNL2**

Probing date: 02-14-1995

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 23.42

**CPT; 38RBNL2**



CPT based SOIL  
CLASSIFICATION

0 1 2 3 4 5  
Clays  
Silt  
Sand  
Mixture  
Sands  
& Gravels


Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Fluorescence Intensity  
Norm. Counts - No BKGD Sub

Wavelength  
at Peak (nm)



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 16.58

**CPT; 39RBNL2**

Probing date; 02-14-1995

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995

Project: Robins AFB  
Probe Depth: 19.31

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

**CPT; 40RBNL2**

CPT based SOIL  
CLASSIFICATION

0 Sands & Gravels  
1 Sands  
2 Sands  
3 Sand Mixtures  
4 Silts  
5 Clays

Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Fluorescence Intensity  
Norm. Counts - No BKGD SUB

Wavelength  
at Peak (nm)

Depth (feet)

Depth (feet)

Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 19.79

Probing date: 02-14-1995

**CPT; 41RBNL2**

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of POL via fiber optics

U.S. Army Engineer District Kansas City Geotechnical Branch

Probing date: 02-14-1995


SCAPS

Site Characterization and Analysis Penetrometer System

Project: Robins AFB  
Probe Depth: 16.60

CPT; 42RBNL2

# CPT based SOIL CLASSIFICATION



Laser induced fluorescence of POL via fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995

**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.84

**CPT; 43RBNL2**

CPT based SOIL  
CLASSIFICATION

0  
1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
841  
842  
843  
844  
845  
846  
847  
848  
849  
850  
851  
852  
853  
854  
855  
856  
857  
858  
859  
860  
861  
862  
863  
864  
865  
866  
867  
868  
869  
870  
871  
872  
873  
874  
875  
876  
877  
878  
879  
880  
881  
882  
883  
884  
885  
886  
887  
888  
889  
890  
891  
892  
893  
894  
895  
896  
897  
898  
899  
900  
901  
902  
903  
904  
905  
906  
907  
908  
909  
910  
911  
912  
913  
914  
915  
916  
917  
918  
919  
920  
921  
922  
923  
924  
925  
926  
927  
928  
929  
930  
931  
932  
933  
934  
935  
936  
937  
938  
939  
940  
941  
942  
943  
944  
945  
946  
947  
948  
949  
950  
951  
952  
953  
954  
955  
956  
957  
958  
959  
960  
961  
962  
963  
964  
965  
966  
967  
968  
969  
970  
971  
972  
973  
974  
975  
976  
977  
978  
979  
980  
981  
982  
983  
984  
985  
986  
987  
988  
989  
990  
991  
992  
993  
994  
995  
996  
997  
998  
999  
1000

Cone Resistance  
 $q_c$  (tons/ft<sup>2</sup>)

Sleeve Friction  
 $f_s$  (tons/ft<sup>2</sup>)

0  
1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100  
101  
102  
103  
104  
105  
106  
107  
108  
109  
110  
111  
112  
113  
114  
115  
116  
117  
118  
119  
120  
121  
122  
123  
124  
125  
126  
127  
128  
129  
130  
131  
132  
133  
134  
135  
136  
137  
138  
139  
140  
141  
142  
143  
144  
145  
146  
147  
148  
149  
150  
151  
152  
153  
154  
155  
156  
157  
158  
159  
160  
161  
162  
163  
164  
165  
166  
167  
168  
169  
170  
171  
172  
173  
174  
175  
176  
177  
178  
179  
180  
181  
182  
183  
184  
185  
186  
187  
188  
189  
190  
191  
192  
193  
194  
195  
196  
197  
198  
199  
200  
201  
202  
203  
204  
205  
206  
207  
208  
209  
210  
211  
212  
213  
214  
215  
216  
217  
218  
219  
220  
221  
222  
223  
224  
225  
226  
227  
228  
229  
230  
231  
232  
233  
234  
235  
236  
237  
238  
239  
240  
241  
242  
243  
244  
245  
246  
247  
248  
249  
250  
251  
252  
253  
254  
255  
256  
257  
258  
259  
260  
261  
262  
263  
264  
265  
266  
267  
268  
269  
270  
271  
272  
273  
274  
275  
276  
277  
278  
279  
280  
281  
282  
283  
284  
285  
286  
287  
288  
289  
290  
291  
292  
293  
294  
295  
296  
297  
298  
299  
300  
301  
302  
303  
304  
305  
306  
307  
308  
309  
310  
311  
312  
313  
314  
315  
316  
317  
318  
319  
320  
321  
322  
323  
324  
325  
326  
327  
328  
329  
330  
331  
332  
333  
334  
335  
336  
337  
338  
339  
340  
341  
342  
343  
344  
345  
346  
347  
348  
349  
350  
351  
352  
353  
354  
355  
356  
357  
358  
359  
360  
361  
362  
363  
364  
365  
366  
367  
368  
369  
370  
371  
372  
373  
374  
375  
376  
377  
378  
379  
380  
381  
382  
383  
384  
385  
386  
387  
388  
389  
390  
391  
392  
393  
394  
395  
396  
397  
398  
399  
400  
401  
402  
403  
404  
405  
406  
407  
408  
409  
410  
411  
412  
413  
414  
415  
416  
417  
418  
419  
420  
421  
422  
423  
424  
425  
426  
427  
428  
429  
430  
431  
432  
433  
434  
435  
436  
437  
438  
439  
440  
441  
442  
443  
444  
445  
446  
447  
448  
449  
450  
451  
452  
453  
454  
455  
456  
457  
458  
459  
460  
461  
462  
463  
464  
465  
466  
467  
468  
469  
470  
471  
472  
473  
474  
475  
476  
477  
478  
479  
480  
481  
482  
483  
484  
485  
486  
487  
488  
489  
490  
491  
492  
493  
494  
495  
496  
497  
498  
499  
500  
501  
502  
503  
504  
505  
506  
507  
508  
509  
510  
511  
512  
513  
514  
515  
516  
517  
518  
519  
520  
521  
522  
523  
524  
525  
526  
527  
528  
529  
530  
531  
532  
533  
534  
535  
536  
537  
538  
539  
540  
541  
542  
543  
544  
545  
546  
547  
548  
549  
550  
551  
552  
553  
554  
555  
556  
557  
558  
559  
560  
561  
562  
563  
564  
565  
566  
567  
568  
569  
570  
571  
572  
573  
574  
575  
576  
577  
578  
579  
580  
581  
582  
583  
584  
585  
586  
587  
588  
589  
590  
591  
592  
593  
594  
595  
596  
597  
598  
599  
600  
601  
602  
603  
604  
605  
606  
607  
608  
609  
610  
611  
612  
613  
614  
615  
616  
617  
618  
619  
620  
621  
622  
623  
624  
625  
626  
627  
628  
629  
630  
631  
632  
633  
634  
635  
636  
637  
638  
639  
640  
641  
642  
643  
644  
645  
646  
647  
648  
649  
650  
651  
652  
653  
654  
655  
656  
657  
658  
659  
660  
661  
662  
663  
664  
665  
666  
667  
668  
669  
670  
671  
672  
673  
674  
675  
676  
677  
678  
679  
680  
681  
682  
683  
684  
685  
686  
687  
688  
689  
690  
691  
692  
693  
694  
695  
696  
697  
698  
699  
700  
701  
702  
703  
704  
705  
706  
707  
708  
709  
710  
711  
712  
713  
714  
715  
716  
717  
718  
719  
720  
721  
722  
723  
724  
725  
726  
727  
728  
729  
730  
731  
732  
733  
734  
735  
736  
737  
738  
739  
740  
741  
742  
743  
744  
745  
746  
747  
748  
749  
750  
751  
752  
753  
754  
755  
756  
757  
758  
759  
760  
761  
762  
763  
764  
765  
766  
767  
768  
769  
770  
771  
772  
773  
774  
775  
776  
777  
778  
779  
780  
781  
782  
783  
784  
785  
786  
787  
788  
789  
790  
791  
792  
793  
794  
795  
796  
797  
798  
799  
800  
801  
802  
803  
804  
805  
806  
807  
808  
809  
810  
811  
812  
813  
814  
815  
816  
817  
818  
819  
820  
821  
822  
823  
824  
825  
826  
827  
828  
829  
830  
831  
832  
833  
834  
835  
836  
837  
838  
839  
840  
841  
842  
843  
844  
845  
846  
847  
848  
849  
850  
851  
852  
853  
854  
855  
856  
857  
858  
859  
860  
861  
862  
863  
864  
865  
866  
867  
868  
869  
870  
871  
872  
873  
874  
875  
876  
877  
878  
879  
880  
881  
882  
883  
884  
885  
886  
887  
888  
889  
890  
891  
892  
893  
894  
895  
896  
897  
898  
899  
900  
901  
902  
903  
904  
905  
906  
907  
908  
909  
910  
911  
912  
913  
914  
915  
916  
917  
918  
919  
920  
921  
922  
923  
924  
925  
926  
927  
928  
929  
930  
931  
932  
933  
934  
935  
936  
937  
938  
939  
940  
941  
942  
943  
944  
945  
946  
947  
948  
949  
950  
951  
952  
953  
954  
955  
956  
957  
958  
959  
960  
961  
962  
963  
964  
965  
966  
967  
968  
969  
970  
971  
972  
973  
974  
975  
976  
977  
978  
979  
980  
981  
982  
983  
984  
985  
986  
987  
988  
989  
990  
991  
992  
993  
994  
995  
996  
997  
998  
999  
1000

Fluorescence Intensity  
Norm. Counts - No Background

Fluorescence Intensity  
Norm. Counts - No Background

Wavelength  
at Peak (nm)

Depth (feet)

Depth (feet)

Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.73

**CPT; 44RBNL2**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 16.62

Probing date: 02-14-1995

CPT; 45RBNL2

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.73

**CPT; 46RBNL2**



5  
5  
5



**Laser induced  
fluorescence  
of POL via  
fiber optics**

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Project: Robins AFB  
Probe Depth: 16.89


# SCAPS

Site  
Characterization  
and Analysis  
penetrometer Syst

**CPT: 47RBNL2**

**Probing date: 02-14-1995**

# CPT based SOIL CLASSIFICATION



Laser Induced  
Fluorescence  
of PCL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.93

**CPT; 48RBNL2**

CPT based SOIL  
CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995


*SCAPS*

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.75

CPT; 49RBNL2

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of POL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

Probing date: 02-14-1995


**SCAPS**

Site  
Characterization  
and Analysis  
Penetrometer System

Project: Robins AFB  
Probe Depth: 16.88

**CPT; 50RBNL2**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PDL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Project; Robins AFB  
Probe Depth; 16.77

CPT; 51RBNL2

Probing date: 02-14-1995

CPT based SOIL  
CLASSIFICATION



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**


Site  
Characterization  
and Analysis  
Penetrometer System

Probing date: 02-14-1995

Project: Robins AFB  
Probe Depth: 19.94

**CPT; 52RBNL2**

# CPT based SOIL CLASSIFICATION



Laser induced  
fluorescence  
of PQL via  
fiber optics

U.S. Army  
Engineer  
District  
Kansas City  
Geotechnical Branch

**SCAPS**

Project; Robins AFB  
Probe Depth; 20.09


Site  
Characterization  
and Analysis  
Penetrometer System  
**CPT; 53RBNL2**

Probing date: 02-14-1995

**APPENDIX B**

**SITE CHARACTERIZATION DATA FOR SITE SS010**





# LEGEND

Approximate Horizontal  
Scale in Feet





Vertical Exaggeration = 10X

▼ - Ground Water Elevation

**APPENDIX C**

**SITE CHARACTERIZATION DATA FOR THE UST #70 AND #72 SITE**





---




TABLE 6. SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
11-Jan-94	EA-1	260.57	N/A	N/A	7.59	252.98	N/A	0.00	N/A
19-Jan-94	EA-1	260.57	N/A	N/A	7.48	253.09	N/A	0.00	N/A
07-Mar-94	EA-1	260.57	6.65	253.92	7.15	253.42	253.83	0.50	-
08-Mar-94	EA-1	260.57	6.73	253.84	7.19	253.38	253.75	0.46	0.8
8-9 Mar 94	^EA-1						SKIMMER BELT RECOVERY =		0.4
09-Mar-94	EA-1	260.57	6.76	253.81	6.79	253.78	253.80	0.03	-
10-Mar-94	EA-1	260.57	6.90	253.67	6.93	253.64	253.66	0.03	-
29-Mar-94	EA-1	260.57	6.80	253.77	7.03	253.54	253.73	0.23	0.2
31-Mar-94	EA-1	260.57	6.73	253.84	6.93	253.64	253.80	0.20	-
01-Apr-94	EA-1	260.57	6.68	253.89	6.97	253.60	253.83	0.29	0.2
07-Apr-94	EA-1	260.57	7.26	253.31	7.49	253.08	253.27	0.23	0.1
14-Apr-94	EA-1	260.57	7.48	253.09	7.58	252.99	253.07	0.10	0.05
21-Apr-94	EA-1	260.57	7.40	253.17	7.47	253.10	253.16	0.07	0.02
28-Apr-94	EA-1	260.57	7.67	252.90	7.69	252.88	252.90	0.02	0.01
04-May-94	EA-1	260.57	7.71	252.86	7.73	252.84	252.86	0.02	0.02
10-May-94	EA-1	260.57	N/A	N/A	7.82	252.75	N/A	0.00	N/A
26-May-94	EA-1	260.57	SHEEN	N/A	8.11	252.46	N/A	SHEEN	N/A
03-Jun-94	EA-1	260.57	N/A	N/A	8.28	252.29	N/A	0.00	N/A
08-Jun-94	EA-1	260.57	8.25	252.32	8.29	252.28	252.31	0.04	0.05
17-Jun-94	EA-1	260.57	N/A	N/A	8.18	252.39	N/A	0.00	N/A
20-Jun-94	EA-1	260.57	8.10	252.47	8.19	252.38	252.45	0.09	0.05
20-Jul-94	EA-1	260.57	6.94	253.63	7.34	253.23	253.55	0.40	0.10
26-Jul-94	EA-1	260.57	6.94	253.63	7.34	253.23	253.55	0.40	0.30
02-Aug-94	EA-1	260.57	6.96	253.61	7.43	253.14	253.52	0.47	0.35
09-Aug-94	EA-1	260.57	7.15	253.42	7.53	253.04	253.35	0.38	0.00
15-Aug-94	EA-1	260.57	7.41	253.16	7.81	252.76	253.08	0.40	0.00
18-Aug-94	EA-1	260.57	7.27	253.30	7.40	253.17	253.28	0.13	0.20
30-Aug-94	EA-1	260.57	7.33	253.24	7.58	252.99	253.19	0.25	0.00
08-Sep-94	EA-1	260.57	7.49	253.08	7.62	252.95	253.06	0.13	0.15
22-Sep-94	EA-1	260.57	N/A	N/A	7.37	253.20	N/A	0.00	N/A
30-Sep-94	EA-1	260.57	7.61	252.96	7.63	252.94	252.96	0.02	0.02
14-Oct-94	EA-1	260.57	N/A	N/A	7.11	253.46	N/A	0.00	N/A
25-Oct-94	EA-1	260.57	7.03	253.54	7.04	253.53	253.54	0.01	0.00
11-Jan-94	EA-2	259.22	5.97	253.25	7.11	252.11	253.03	1.14	1.7
19-Jan-94	EA-2	259.22	5.87	253.35	6.94	252.28	253.15	1.07	2.6
07-Mar-94	^EA-2	259.22	5.17	254.05	6.54	252.68	253.79	1.37	15.6
8-22 Mar 94	^EA-2						SKIMMER BELT RECOVERY =		79.4
29-Mar-94	^EA-2	259.22	5.22	254.00	6.62	252.60	253.73	1.40	-
29-31 Mar 94	^EA-2						SKIMMER BELT RECOVERY =		16.4
31-Mar-94	^EA-2						GAUGED FROM SKIMMER: LPH THICKNESS =		8.0
1-3 Apr 94	^EA-2						SKIMMER BELT RECOVERY =		32.8
4-6 Apr 94	^EA-2						SKIMMER BELT RECOVERY =		24.8
7-14 Apr 94	^EA-2						SKIMMER BELT RECOVERY =		25.6
14-Apr-94	EA-2	259.22	6.17	253.05	6.87	252.35	252.92	0.70	-
14-21 Apr 94	SKIMMER BELT WAS MOVED TO VW-8 FOR THIS WEEK								
21-Apr-94	EA-2	259.22	5.91	253.31	7.54	251.68	253.00	1.63	-
21-28 Apr 94	^EA-2						SKIMMER BELT RECOVERY =		47.4
28-Apr-94	^EA-2	259.22	6.14	253.08	7.66	251.56	252.79	1.52	-

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
28 Apr-4 May	^EA-2						SKIMMER BELT RECOVERY =		37.6
04-May-94	^EA-2	259.22	6.14	253.08	7.73	251.49	252.78	1.59	-
4-10 May-94	^EA-2						SKIMMER BELT RECOVERY =		52.2
10-May-94	^EA-2	259.22	6.23	252.99	7.81	251.41	252.69	1.58	-
10-26 May-94	^EA-2						SKIMMER BELT RECOVERY =		52.0
26-May-94	^EA-2	259.22	6.46	252.76	8.19	251.03	252.43	1.73	-
26 May-3 Jun	^EA-2						SKIMMER BELT RECOVERY =		51.2
03-Jun-94	^EA-2	259.22	6.63	252.59	8.24	250.98	252.28	1.61	-
3-8 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		51.0
08-Jun-94	^EA-2	259.22	6.63	252.59	8.20	251.02	252.29	1.57	-
8-17 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		49.2
17-Jun-94	^EA-2	259.22	6.61	252.61	8.15	251.07	252.32	1.54	-
17-20 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		49.0
20-Jun-94	^EA-2	259.22	6.57	252.65	7.91	251.31	252.40	1.34	-
20-22 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		31.0
22-Jun-94	^EA-2	259.22	6.62	252.60	7.94	251.28	252.35	1.32	-
22-27 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		50.4
27-29 Jun 94	^EA-2						SKIMMER BELT RECOVERY =		0.0
29-Jun-94	^EA-2	259.22	6.54	252.68	7.99	251.23	252.40	1.45	-
29 Jun-1 Jul	^EA-2						SKIMMER BELT RECOVERY =		23.2
1-5 Jul 94	^EA-2						SKIMMER BELT RECOVERY =		44.8
5-12 Jul 94	^EA-2						SKIMMER BELT RECOVERY =		0.0
12-Jul-94	^EA-2	259.22	5.32	253.90	6.33	252.89	253.71	1.01	-
12-18 Jul 94	^EA-2						SKIMMER BELT RECOVERY =		3.6
18-Jul-94	^EA-2	259.22	N/A	N/A	5.96	253.26	N/A	0.00	-
18-20 Jul 94	^EA-2						SKIMMER BELT RECOVERY =		0.0
20-Jul-94	^EA-2	259.22	N/A	N/A	5.98	253.24	N/A	0.00	-
18-26 Jul 94	^EA-2	SKIMMER BELT OFF							
26-Jul-94	^EA-2	259.22	5.63	253.59	6.80	252.42	253.37	1.17	0.0
26 Jul- 2 Aug	^EA-2						SKIMMER BELT RECOVERY =		27.8
02-Aug-94	^EA-2	259.22	5.94	253.28	6.00	253.22	253.27	0.06	-
2-9 Aug 94	^EA-2						SKIMMER BELT RECOVERY =		4.2
09-Aug-94	^EA-2	259.22	6.13	253.09	6.15	253.07	253.09	0.02	-
9-16 Aug 94	^EA-2						SKIMMER BELT RECOVERY =		7.0
16-Aug-94	^EA-2	259.22	6.21	253.01	6.89	252.33	252.88	0.68	-
16-18 Aug 94	^EA-2						SKIMMER BELT RECOVERY =		6.6
18-Aug-94	^EA-2	259.22	6.02	253.20	6.45	252.77	253.12	0.43	-
18-30 Aug 94	^EA-2						SKIMMER BELT RECOVERY =		51.2
30-Aug-94	^EA-2	259.22	5.97	253.25	7.37	251.85	252.98	1.40	-
30 Aug-8 Sep	^EA-2						SKIMMER BELT RECOVERY =		52.2
08-Sep-94	^EA-2	259.22	6.11	253.11	7.46	251.76	252.85	1.35	-
8-22 Sep 94	^EA-2						SKIMMER BELT RECOVERY =		50.0
22-Sep-94	^EA-2	259.22	5.94	253.28	7.30	251.92	253.02	1.36	-
22-30 Sep 94	^EA-2						SKIMMER BELT RECOVERY =		53.0
30-Sep-94	^EA-2	259.22	6.11	253.11	7.66	251.56	252.82	1.55	-
9/30 - 10/14	^EA-2						SKIMMER BELT RECOVERY =		44.4
14-Oct-94	^EA-2	259.22	5.73	253.49	7.00	252.22	253.25	1.27	-
14-25 Oct 94	^EA-2						SKIMMER BELT RECOVERY =		51.4
25-Oct-94	^EA-2	259.22	5.66	253.56	7.09	252.13	253.29	1.43	-

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
11-Jan-94	EA-3	260.11	N/A	N/A	7.36	252.75	N/A	0.00	N/A
19-Jan-94	EA-3	260.11	N/A	N/A	7.26	252.85	N/A	0.00	N/A
07-Mar-94	EA-3	260.11	N/A	N/A	6.53	253.58	N/A	0.00	N/A
29-Mar-94	EA-3	260.11	N/A	N/A	6.65	253.46	N/A	0.00	N/A
14-Apr-94	EA-3	260.11	SHEEN	N/A	7.26	252.85	N/A	SHEEN	N/A
21-Apr-94	EA-3	260.11	N/A	N/A	7.14	252.97	N/A	0.00	N/A
28-Apr-94	EA-3	260.11	N/A	N/A	7.44	252.67	N/A	0.00	N/A
04-May-94	EA-3	260.11	N/A	N/A	7.49	252.62	N/A	0.00	N/A
26-May-94	EA-3	260.11	SHEEN	N/A	7.89	252.22	N/A	SHEEN	N/A
20-Jul-94	EA-3	260.11	N/A	N/A	6.75	253.36	N/A	0.00	N/A
18-Aug-94	EA-3	260.11	N/A	N/A	7.01	253.10	N/A	0.00	N/A
30-Aug-94	EA-3	260.11	N/A	N/A	7.12	252.99	N/A	0.00	N/A
22-Sep-94	EA-3	260.11	N/A	N/A	7.10	253.01	N/A	0.00	N/A
25-Oct-94	EA-3	260.11	N/A	N/A	6.74	253.37	N/A	0.00	N/A
11-Jan-94	EA-4	260.63	N/A	N/A	8.05	252.58	N/A	0.00	N/A
19-Jan-94	EA-4	260.63	N/A	N/A	7.95	252.68	N/A	0.00	N/A
07-Mar-94	EA-4	260.63	N/A	N/A	7.23	253.40	N/A	0.00	N/A
29-Mar-94	EA-4	260.63	N/A	N/A	7.36	253.27	N/A	0.00	N/A
14-Apr-94	EA-4	260.63	N/A	N/A	7.94	252.69	N/A	0.00	N/A
21-Apr-94	EA-4	260.63	N/A	N/A	7.80	252.83	N/A	0.00	N/A
28-Apr-94	EA-4	260.63	N/A	N/A	8.12	252.51	N/A	0.00	N/A
26-May-94	EA-4	260.63	N/A	N/A	8.59	252.04	N/A	0.00	N/A
20-Jul-94	EA-4	260.63	N/A	N/A	7.40	253.23	N/A	0.00	N/A
18-Aug-94	EA-4	260.63	N/A	N/A	7.66	252.97	N/A	0.00	N/A
30-Aug-94	EA-4	260.63	N/A	N/A	7.77	252.86	N/A	0.00	N/A
22-Sep-94	EA-4	260.63	N/A	N/A	7.79	252.84	N/A	0.00	N/A
25-Oct-94	EA-4	260.63	N/A	N/A	7.39	253.24	N/A	0.00	N/A
11-Jan-94	EA-5	260.20	N/A	N/A	7.48	252.72	N/A	0.00	N/A
19-Jan-94	EA-5	260.20	N/A	N/A	7.39	252.81	N/A	0.00	N/A
07-Mar-94	EA-5	260.20	N/A	N/A	6.68	253.52	N/A	0.00	N/A
29-Mar-94	EA-5	260.20	N/A	N/A	6.81	253.39	N/A	0.00	N/A
14-Apr-94	EA-5	260.20	N/A	N/A	7.30	252.90	N/A	0.00	N/A
21-Apr-94	EA-5	260.20	N/A	N/A	7.20	253.00	N/A	0.00	N/A
28-Apr-94	EA-5	260.20	N/A	N/A	7.48	252.72	N/A	0.00	N/A
26-May-94	EA-5	260.20	N/A	N/A	7.94	252.26	N/A	0.00	N/A
20-Jul-94	EA-5	260.20	N/A	N/A	6.77	253.43	N/A	0.00	N/A
18-Aug-94	EA-5	260.20	N/A	N/A	7.05	253.15	N/A	0.00	N/A
30-Aug-94	EA-5	260.20	N/A	N/A	7.13	253.07	N/A	0.00	N/A
22-Sep-94	EA-5	260.20	N/A	N/A	7.16	253.04	N/A	0.00	N/A
25-Oct-94	EA-5	260.20	N/A	N/A	6.77	253.43	N/A	0.00	N/A
11-Jan-94	EA-6	260.09	N/A	N/A	7.51	252.58	N/A	0.00	N/A
19-Jan-94	EA-6	260.09	N/A	N/A	7.44	252.65	N/A	0.00	N/A
07-Mar-94	EA-6	260.09	N/A	N/A	6.72	253.37	N/A	0.00	N/A
29-Mar-94	EA-6	260.09	N/A	N/A	6.87	253.22	N/A	0.00	N/A
14-Apr-94	EA-6	260.09	N/A	N/A	7.33	252.76	N/A	0.00	N/A



TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
21-Apr-94	EA-6	260.09	N/A	N/A	7.23	252.86	N/A	0.00	N/A
28-Apr-94	EA-6	260.09	N/A	N/A	7.51	252.58	N/A	0.00	N/A
26-May-94	EA-6	260.09	N/A	N/A	7.97	252.12	N/A	0.00	N/A
20-Jul-94	EA-6	260.09	N/A	N/A	6.78	253.31	N/A	0.00	N/A
18-Aug-94	EA-6	260.09	N/A	N/A	7.09	253.00	N/A	0.00	N/A
30-Aug-94	EA-6	260.09	N/A	N/A	7.16	252.93	N/A	0.00	N/A
22-Sep-94	EA-6	260.09	N/A	N/A	7.19	252.90	N/A	0.00	N/A
25-Oct-94	EA-6	260.09	N/A	N/A	6.81	253.28	N/A	0.00	N/A
11-Jan-94	EA-7	260.13	N/A	N/A	7.10	253.03	N/A	0.00	N/A
19-Jan-94	EA-7	260.13	N/A	N/A	6.97	253.16	N/A	0.00	N/A
07-Mar-94	EA-7	260.13	N/A	N/A	6.31	253.82	N/A	0.00	N/A
29-Mar-94	EA-7	260.13	N/A	N/A	6.36	253.77	N/A	0.00	N/A
14-Apr-94	EA-7	260.13	N/A	N/A	7.14	252.99	N/A	0.00	N/A
21-Apr-94	EA-7	260.13	N/A	N/A	7.06	253.07	N/A	0.00	N/A
28-Apr-94	EA-7	260.13	N/A	N/A	7.29	252.84	N/A	0.00	N/A
04-May-94	EA-7	260.13	N/A	N/A	7.31	252.82	N/A	0.00	N/A
26-May-94	EA-7	260.13	N/A	N/A	7.68	252.45	N/A	0.00	N/A
20-Jul-94	EA-7	260.13	N/A	N/A	6.75	253.38	N/A	0.00	N/A
18-Aug-94	EA-7	260.13	N/A	N/A	6.94	253.19	N/A	0.00	N/A
30-Aug-94	EA-7	260.13	N/A	N/A	7.11	253.02	N/A	0.00	N/A
22-Sep-94	EA-7	260.13	N/A	N/A	7.05	253.08	N/A	0.00	N/A
25-Oct-94	EA-7	260.13	N/A	N/A	6.77	253.36	N/A	0.00	N/A
11-Jan-94	EA-8	259.62	N/A	N/A	7.28	252.34	N/A	0.00	N/A
19-Jan-94	EA-8	259.62	N/A	N/A	7.19	252.43	N/A	0.00	N/A
07-Mar-94	EA-8	259.62	N/A	N/A	6.48	253.14	N/A	0.00	N/A
29-Mar-94	EA-8	259.62	N/A	N/A	6.60	253.02	N/A	0.00	N/A
14-Apr-94	EA-8	259.62	N/A	N/A	7.12	252.50	N/A	0.00	N/A
21-Apr-94	EA-8	259.62	N/A	N/A	6.99	252.63	N/A	0.00	N/A
28-Apr-94	EA-8	259.62	N/A	N/A	7.31	252.31	N/A	0.00	N/A
26-May-94	EA-8	259.62	N/A	N/A	7.76	251.86	N/A	0.00	N/A
20-Jul-94	EA-8	259.62	N/A	N/A	6.57	253.05	N/A	0.00	N/A
18-Aug-94	EA-8	259.62	N/A	N/A	6.84	252.78	N/A	0.00	N/A
30-Aug-94	EA-8	259.62	N/A	N/A	6.92	252.70	N/A	0.00	N/A
22-Sep-94	EA-8	259.62	N/A	N/A	6.91	252.71	N/A	0.00	N/A
25-Oct-94	EA-8	259.62	N/A	N/A	6.55	253.07	N/A	0.00	N/A
11-Jan-94	EA-9	260.63	N/A	N/A	7.91	252.72	N/A	0.00	N/A
19-Jan-94	EA-9	260.63	N/A	N/A	7.85	252.78	N/A	0.00	N/A
07-Mar-94	EA-9	260.63	N/A	N/A	7.11	253.52	N/A	0.00	N/A
29-Mar-94	EA-9	260.63	N/A	N/A	7.21	253.42	N/A	0.00	N/A
14-Apr-94	EA-9	260.63	N/A	N/A	7.87	252.76	N/A	0.00	N/A
21-Apr-94	EA-9	260.63	N/A	N/A	7.76	252.87	N/A	0.00	N/A
28-Apr-94	EA-9	260.63	N/A	N/A	8.06	252.57	N/A	0.00	N/A
26-May-94	EA-9	260.63	N/A	N/A	8.52	252.11	N/A	0.00	N/A
20-Jul-94	EA-9	260.63	N/A	N/A	7.40	253.23	N/A	0.00	N/A
18-Aug-94	EA-9	260.63	N/A	N/A	7.66	252.97	N/A	0.00	N/A
30-Aug-94	EA-9	260.63	N/A	N/A	7.78	252.85	N/A	0.00	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
22-Sep-94	EA-9	260.63	N/A	N/A	7.74	252.89	N/A	0.00	N/A
25-Oct-94	EA-9	260.63	N/A	N/A	7.41	253.22	N/A	0.00	N/A
11-Jan-94	EA-10	260.01	N/A	N/A	7.33	252.68	N/A	0.00	N/A
19-Jan-94	EA-10	260.01	N/A	N/A	7.21	252.80	N/A	0.00	N/A
07-Mar-94	EA-10	260.01	N/A	N/A	6.56	253.45	N/A	0.00	N/A
29-Mar-94	EA-10	260.01	N/A	N/A	6.61	253.40	N/A	0.00	N/A
14-Apr-94	EA-10	260.01	N/A	N/A	7.25	252.76	N/A	0.00	N/A
21-Apr-94	EA-10	260.01	N/A	N/A	7.11	252.90	N/A	0.00	N/A
28-Apr-94	EA-10	260.01	N/A	N/A	7.46	252.55	N/A	0.00	N/A
26-May-94	EA-10	260.01	N/A	N/A	7.80	252.21	N/A	0.00	N/A
20-Jul-94	EA-10	260.01	N/A	N/A	6.66	253.35	N/A	0.00	N/A
18-Aug-94	EA-10	260.01	N/A	N/A	6.84	253.17	N/A	0.00	N/A
30-Aug-94	EA-10	260.01	N/A	N/A	6.98	253.03	N/A	0.00	N/A
22-Sep-94	EA-10	260.01	N/A	N/A	6.97	253.04	N/A	0.00	N/A
25-Oct-94	EA-10	260.01	N/A	N/A	6.65	253.36	N/A	0.00	N/A
18-Aug-94	EA-11	259.74	N/A	N/A	6.24	253.50	N/A	0.00	N/A
30-Aug-94	EA-11	259.74	N/A	N/A	6.36	253.38	N/A	0.00	N/A
22-Sep-94	EA-11	259.74	N/A	N/A	6.34	253.40	N/A	0.00	N/A
25-Oct-94	EA-11	259.74	N/A	N/A	6.00	253.74	N/A	0.00	N/A
18-Aug-94	EA-12	259.48	N/A	N/A	5.83	253.65	N/A	0.00	N/A
30-Aug-94	EA-12	259.48	N/A	N/A	5.97	253.51	N/A	0.00	N/A
22-Sep-94	EA-12	259.48	N/A	N/A	5.94	253.54	N/A	0.00	N/A
25-Oct-94	EA-12	259.48	N/A	N/A	5.58	253.90	N/A	0.00	N/A
18-Aug-94	EA-13	259.40	N/A	N/A	4.76	254.64	N/A	0.00	N/A
30-Aug-94	EA-13	259.40	N/A	N/A	4.94	254.46	N/A	0.00	N/A
22-Sep-94	EA-13	259.40	N/A	N/A	4.88	254.52	N/A	0.00	N/A
25-Oct-94	EA-13	259.40	N/A	N/A	4.46	254.94	N/A	0.00	N/A
18-Aug-94	EA-14	259.68	N/A	N/A	5.35	254.33	N/A	0.00	N/A
30-Aug-94	EA-14	259.68	N/A	N/A	5.68	254.00	N/A	0.00	N/A
22-Sep-94	EA-14	259.68	N/A	N/A	5.61	254.07	N/A	0.00	N/A
25-Oct-94	EA-14	259.68	N/A	N/A	5.19	254.49	N/A	0.00	N/A
18-Aug-94	EA-15	260.12	N/A	N/A	5.29	254.83	N/A	0.00	N/A
30-Aug-94	EA-15	260.12	N/A	N/A	5.48	254.64	N/A	0.00	N/A
22-Sep-94	EA-15	260.12	N/A	N/A	5.34	254.78	N/A	0.00	N/A
25-Oct-94	EA-15	260.12	N/A	N/A	5.05	255.07	N/A	0.00	N/A
18-Aug-94	EA-16	259.25	N/A	N/A	6.21	253.04	N/A	0.00	N/A
30-Aug-94	EA-16	259.25	N/A	N/A	6.35	252.90	N/A	0.00	N/A
22-Sep-94	EA-16	259.25	N/A	N/A	6.31	252.94	N/A	0.00	N/A
25-Oct-94	EA-16	259.25	N/A	N/A	5.98	253.27	N/A	0.00	N/A
15-Aug-94	EA-17	259.10	N/A	N/A	6.20	252.90	N/A	0.00	N/A
18-Aug-94	EA-17	259.10	N/A	N/A	6.15	252.95	N/A	0.00	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
30-Aug-94	EA-17	259.10	N/A	N/A	6.18	252.92	N/A	0.00	N/A
22-Sep-94	EA-17	259.10	N/A	N/A	6.55	252.55	N/A	0.00	N/A
25-Oct-94	EA-17	259.10	N/A	N/A	5.74	253.36	N/A	0.00	N/A
15-Aug-94	EA-18	259.42	N/A	N/A	4.74	254.68	N/A	0.00	N/A
18-Aug-94	EA-18	259.42	N/A	N/A	4.92	254.50	N/A	0.00	N/A
30-Aug-94	EA-18	259.42	N/A	N/A	5.05	254.37	N/A	0.00	N/A
22-Sep-94	EA-18	259.42	N/A	N/A	5.03	254.39	N/A	0.00	N/A
25-Oct-94	EA-18	259.42	N/A	N/A	5.03	254.39	N/A	0.00	N/A
15-Aug-94	EA-19	259.47	N/A	N/A	2.90	256.57	N/A	0.00	N/A
18-Aug-94	EA-19	259.47	N/A	N/A	2.95	256.52	N/A	0.00	N/A
30-Aug-94	EA-19	259.47	N/A	N/A	2.99	256.48	N/A	0.00	N/A
22-Sep-94	EA-19	259.47	N/A	N/A	3.42	256.05	N/A	0.00	N/A
25-Oct-94	EA-19	259.47	N/A	N/A	2.78	256.69	N/A	0.00	N/A
15-Aug-94	EA-20	259.50	N/A	N/A	6.62	252.88	N/A	0.00	N/A
18-Aug-94	EA-20	259.50	N/A	N/A	6.68	252.82	N/A	0.00	N/A
30-Aug-94	EA-20	259.50	N/A	N/A	6.33	253.17	N/A	0.00	N/A
22-Sep-94	EA-20	259.50	N/A	N/A	6.83	252.67	N/A	0.00	N/A
25-Oct-94	EA-20	259.50	N/A	N/A	6.65	252.85	N/A	0.00	N/A
18-Aug-94	EA-21	259.52	N/A	N/A	5.08	254.44	N/A	0.00	N/A
30-Aug-94	EA-21	259.52	N/A	N/A	5.42	254.10	N/A	0.00	N/A
22-Sep-94	EA-21	259.52	N/A	N/A	5.39	254.13	N/A	0.00	N/A
25-Oct-94	EA-21	NOT GAUGED - WELL BURIED							
18-Aug-94	EA-22	260.25	N/A	N/A	6.94	253.31	N/A	0.00	N/A
30-Aug-94	EA-22	260.25	N/A	N/A	7.04	253.21	N/A	0.00	N/A
22-Sep-94	EA-22	260.25	N/A	N/A	7.13	253.12	N/A	0.00	N/A
25-Oct-94	EA-22	260.25	N/A	N/A	6.67	253.58	N/A	0.00	N/A
15-Aug-94	EA-23	259.78	N/A	N/A	7.30	252.48	N/A	0.00	N/A
18-Aug-94	EA-23	259.78	N/A	N/A	7.17	252.61	N/A	0.00	N/A
30-Aug-94	EA-23	259.78	N/A	N/A	7.20	252.58	N/A	0.00	N/A
22-Sep-94	EA-23	259.78	N/A	N/A	7.25	252.53	N/A	0.00	N/A
25-Oct-94	EA-23	259.78	N/A	N/A	6.89	252.89	N/A	0.00	N/A

SITE 70 VENT WELL GAUGING:

01-Nov-93	VW-1	N/A	7.96	N/A	7.99	N/A	N/A	0.03	0.01
02-Nov-93	VW-1	N/A	7.94	N/A	7.96	N/A	N/A	0.02	0.01
05-Nov-93	VW-1	N/A	N/A	N/A	7.78	N/A	N/A	0.00	N/A
10-Nov-93	VW-1	N/A	N/A	N/A	7.69	N/A	N/A	0.00	N/A
17-Nov-93	VW-1	N/A	N/A	N/A	7.79	N/A	N/A	0.00	N/A
07-Jan-94	VW-1	N/A	N/A	N/A	7.29	N/A	N/A	0.00	N/A
07-Mar-94	VW-1	N/A	N/A	N/A	6.47	N/A	N/A	0.00	N/A
29-Mar-94	VW-1	N/A	N/A	N/A	6.56	N/A	N/A	0.00	N/A
14-Apr-94	VW-1	N/A	N/A	N/A	7.16	N/A	N/A	0.00	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
28-Apr-94	VW-1	N/A	N/A	N/A	7.33	N/A	N/A	0.00	N/A
26-May-94	VW-1	N/A	N/A	N/A	7.79	N/A	N/A	0.00	N/A
26-Jul-94	VW-1	N/A	SHEEN	N/A	6.73	N/A	N/A	SHEEN	N/A
25-Oct-94	VW-1	N/A	N/A	N/A	6.66	N/A	N/A	0.00	N/A
01-Nov-93	VW-2	N/A	7.98	N/A	7.99	N/A	N/A	0.01	0.00
02-Nov-93	VW-2	N/A	SHEEN	N/A	7.97	N/A	N/A	SHEEN	N/A
05-Nov-93	VW-2	N/A	N/A	N/A	7.70	N/A	N/A	0.00	N/A
10-Nov-93	VW-2	N/A	N/A	N/A	7.72	N/A	N/A	0.00	N/A
17-Nov-93	VW-2	N/A	N/A	N/A	7.79	N/A	N/A	0.00	N/A
07-Jan-94	VW-2	N/A	N/A	N/A	7.33	N/A	N/A	0.00	N/A
07-Mar-94	VW-2	N/A	N/A	N/A	6.48	N/A	N/A	0.00	N/A
08-Mar-94	VW-2	N/A	N/A	N/A	6.47	N/A	N/A	0.00	N/A
29-Mar-94	VW-2	N/A	N/A	N/A	6.52	N/A	N/A	0.00	N/A
14-Apr-94	VW-2	N/A	N/A	N/A	7.17	N/A	N/A	0.00	N/A
28-Apr-94	VW-2	N/A	N/A	N/A	7.35	N/A	N/A	0.00	N/A
26-May-94	VW-2	N/A	N/A	N/A	7.81	N/A	N/A	0.00	N/A
26-Jul-94	VW-2	N/A	N/A	N/A	6.65	N/A	N/A	0.00	N/A
25-Oct-94	VW-2	N/A	N/A	N/A	6.65	N/A	N/A	0.00	N/A
01-Nov-93	VW-3	260.08	7.96	252.12	8.21	251.87	252.07	0.25	0.12
02-Nov-93	VW-3	260.08	7.98	252.10	8.01	252.07	252.09	0.03	0.02
05-Nov-93	VW-3	260.08	7.80	252.28	7.82	252.26	252.28	0.02	0.02
10-Nov-93	VW-3	260.08	N/A	N/A	7.73	252.35	N/A	0.00	N/A
17-Nov-93	VW-3	260.08	N/A	N/A	7.81	252.27	N/A	0.00	N/A
07-Jan-94	VW-3	260.08	N/A	N/A	7.36	252.72	N/A	0.00	N/A
07-Mar-94	VW-3	260.08	N/A	N/A	6.51	253.57	N/A	0.00	N/A
29-Mar-94	VW-3	260.08	N/A	N/A	6.60	253.48	N/A	0.00	N/A
14-Apr-94	VW-3	260.08	N/A	N/A	7.19	252.89	N/A	0.00	N/A
28-Apr-94	VW-3	260.08	N/A	N/A	7.38	252.70	N/A	0.00	N/A
26-May-94	VW-3	260.08	N/A	N/A	7.83	252.25	N/A	0.00	N/A
26-Jul-94	VW-3	260.08	N/A	N/A	6.65	253.43	N/A	0.00	N/A
25-Oct-94	VW-3	260.08	6.65	253.43	6.78	253.30	253.41	0.13	0.00
01-Nov-93	VW-4	N/A	N/A	N/A	8.09	N/A	N/A	0.00	N/A
02-Nov-93	VW-4	N/A	N/A	N/A	8.14	N/A	N/A	0.00	N/A
05-Nov-93	VW-4	N/A	N/A	N/A	7.52	N/A	N/A	0.00	N/A
10-Nov-93	VW-4	N/A	N/A	N/A	7.99	N/A	N/A	0.00	N/A
17-Nov-93	VW-4	N/A	N/A	N/A	8.12	N/A	N/A	0.00	N/A
07-Jan-94	VW-4	N/A	N/A	N/A	7.67	N/A	N/A	0.00	N/A
07-Mar-94	VW-4	N/A	N/A	N/A	6.75	N/A	N/A	0.00	N/A
18-Mar-94	VW-4	N/A	N/A	N/A	7.12	N/A	N/A	0.00	N/A
29-Mar-94	VW-4	N/A	N/A	N/A	6.69	N/A	N/A	0.00	N/A
14-Apr-94	VW-4	N/A	N/A	N/A	7.48	N/A	N/A	0.00	N/A
28-Apr-94	VW-4	N/A	N/A	N/A	7.68	N/A	N/A	0.00	N/A
26-May-94	VW-4	N/A	N/A	N/A	8.15	N/A	N/A	0.00	N/A
26-Jul-94	VW-4	N/A	N/A	N/A	6.94	N/A	N/A	0.00	N/A
25-Oct-94	VW-4	N/A	N/A	N/A	6.91	N/A	N/A	0.00	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
01-Nov-93	VW-5	N/A	N/A	N/A	8.00	N/A	N/A	0.00	N/A
02-Nov-93	VW-5	N/A	N/A	N/A	8.00	N/A	N/A	0.00	N/A
05-Nov-93	VW-5	N/A	N/A	N/A	7.22	N/A	N/A	0.00	N/A
10-Nov-93	VW-5	N/A	N/A	N/A	7.77	N/A	N/A	0.00	N/A
17-Nov-93	VW-5	N/A	N/A	N/A	7.85	N/A	N/A	0.00	N/A
07-Jan-94	VW-5	N/A	N/A	N/A	7.38	N/A	N/A	0.00	N/A
07-Mar-94	VW-5	N/A	6.52	N/A	6.55	N/A	N/A	0.03	-
08-Mar-94	VW-5			NOT GAUGED: MANUAL PRODUCT RECOVERY =					0.02
18-Mar-94	VW-5	N/A	N/A	N/A	6.89	N/A	N/A	0.00	N/A
29-Mar-94	VW-5	N/A	6.30	N/A	6.31	N/A	N/A	0.01	-
07-Apr-94	VW-5	N/A	N/A	N/A	7.12	N/A	N/A	0.00	N/A
14-Apr-94	VW-5	N/A	N/A	N/A	7.31	N/A	N/A	0.00	N/A
28-Apr-94	VW-5	N/A	SHEEN	N/A	7.43	N/A	N/A	SHEEN	N/A
04-May-94	VW-5	N/A	N/A	N/A	7.22	N/A	N/A	0.00	N/A
26-May-94	VW-5	N/A	SHEEN	N/A	7.92	N/A	N/A	SHEEN	N/A
26-Jul-94	VW-5	N/A	6.79	N/A	6.84	N/A	N/A	0.05	0.02
25-Oct-94	VW-5	N/A	6.71	N/A	6.77	N/A	N/A	0.06	0.00
01-Nov-93	VW-6	N/A	7.87	N/A	7.94	N/A	N/A	0.07	0.02
02-Nov-93	VW-6	N/A	7.89	N/A	7.90	N/A	N/A	0.01	-
05-Nov-93	VW-6	N/A	6.92	N/A	6.93	N/A	N/A	0.01	0.01
10-Nov-93	VW-6	N/A	7.66	N/A	7.67	N/A	N/A	0.01	0.02
17-Nov-93	VW-6	N/A	N/A	N/A	7.75	N/A	N/A	0.00	N/A
07-Jan-94	VW-6	N/A	N/A	N/A	7.28	N/A	N/A	0.00	N/A
07-Mar-94	VW-6	N/A	6.41	N/A	6.43	N/A	N/A	0.02	-
08-Mar-94	VW-6			NOT GAUGED: MANUAL PRODUCT RECOVERY =					0.005
18-Mar-94	VW-6	N/A	N/A	N/A	6.80	N/A	N/A	0.00	N/A
29-Mar-94	VW-6	N/A	6.22	N/A	6.35	N/A	N/A	0.13	0.3
07-Apr-94	*VW-6	N/A	N/A	N/A	7.07	N/A	N/A	0.00	N/A
14-Apr-94	*VW-6	N/A	N/A	N/A	7.19	N/A	N/A	0.00	0.01
21-Apr-94	VW-6	N/A	N/A	N/A	7.09	N/A	N/A	0.00	N/A
28-Apr-94	VW-6	N/A	N/A	N/A	7.33	N/A	N/A	0.00	N/A
04-May-94	VW-6	N/A	N/A	N/A	7.16	N/A	N/A	0.00	N/A
26-May-94	VW-6	N/A	N/A	N/A	7.82	N/A	N/A	0.00	N/A
26-Jul-94	VW-6	N/A	6.66	N/A	6.67	N/A	N/A	0.01	0.01
25-Oct-94	VW-6	N/A	6.63	N/A	6.64	N/A	N/A	0.01	0.00
01-Nov-93	VW-7	260.34	8.00	252.34	8.34	252.00	252.28	0.34	0.20
02-Nov-93	VW-7	260.34	8.00	252.34	8.34	252.00	252.28	0.34	0.15
05-Nov-93	VW-7	260.34	7.53	252.81	7.87	252.47	252.75	0.34	0.18
10-Nov-93	VW-7	260.34	7.78	252.56	8.11	252.23	252.50	0.33	0.20
17-Nov-93	*VW-7	260.34	8.05	252.29	8.23	252.11	252.26	0.18	0.02
07-Jan-94	*VW-7	260.34	7.39	252.95	7.66	252.68	252.90	0.27	0.15
21-Jan-94	*VW-7	260.34	7.35	252.99	7.57	252.77	252.95	0.22	1.1
07-Mar-94	*VW-7	260.34	6.56	253.78	6.73	253.61	253.75	0.17	0.2
08-Mar-94	VW-7			NOT GAUGED: MANUAL PRODUCT RECOVERY =					0.2
18-Mar-94	*VW-7	260.34	6.88	253.46	7.00	253.34	253.44	0.12	0.2
29-Mar-94	*VW-7	260.34	6.55	253.79	6.73	253.61	253.76	0.18	0.7
07-Apr-94	*VW-7	260.34	7.14	253.20	7.29	253.05	253.17	0.15	0.5

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
14-Apr-94	VW-7	260.34	7.28	253.06	7.51	252.83	253.02	0.23	0.1
21-Apr-94	*VW-7	260.34	7.21	253.13	7.35	252.99	253.10	0.14	0.05
28-Apr-94	*VW-7	260.34	7.55	252.79	7.65	252.69	252.77	0.10	0.1
04-May-94	*VW-7	260.34	7.50	252.84	7.58	252.76	252.82	0.08	0.1
10-May-94	*VW-7	260.34	7.71	252.63	7.81	252.53	252.61	0.10	0.1
26-May-94	*VW-7	260.34	8.08	252.26	8.17	252.17	252.24	0.09	0.05
03-Jun-94	VW-7	260.34	8.25	252.09	8.33	252.01	252.07	0.08	0.1
08-Jun-94	VW-7	260.34	8.01	252.33	8.35	251.99	252.27	0.34	0.25
17-Jun-94	VW-7	260.34	SHEEN	N/A	7.56	252.78	N/A	SHEEN	N/A
20-Jun-94	VW-7	260.34	7.88	252.46	8.21	252.13	252.40	0.33	0.30
18-Jul-94	VW-7	260.34	6.81	253.53	6.83	253.51	253.53	0.02	0.01
26-Jul-94	VW-7	260.34	N/A	N/A	6.84	253.50	N/A	0.00	N/A
02-Aug-94	VW-7	260.34	N/A	N/A	6.86	253.48	N/A	0.00	N/A
09-Aug-94	VW-7	260.34	SHEEN	N/A	7.05	253.29	N/A	SHEEN	N/A
18-Aug-94	VW-7	260.34	7.02	253.32	7.04	253.30	253.32	0.02	0.00
08-Sep-94	VW-7	260.34	7.32	253.02	7.39	252.95	253.01	0.07	0.05
22-Sep-94	VW-7	260.34	N/A	N/A	7.20	253.14	N/A	0.00	N/A
30-Sep-94	VW-7	260.34	7.44	252.90	7.45	252.89	252.90	0.01	0.00
14-Oct-94	VW-7	260.34	N/A	N/A	6.86	253.48	N/A	0.00	N/A
25-Oct-94	VW-7	260.34	SHEEN	N/A	6.83	253.51	N/A	SHEEN	0.00
01-Nov-93	VW-8	N/A	7.97	N/A	8.45	N/A	N/A	0.48	0.25
02-Nov-93	VW-8	N/A	8.04	N/A	8.15	N/A	N/A	0.11	0.08
05-Nov-93	VW-8	N/A	7.91	N/A	7.96	N/A	N/A	0.05	0.02
10-Nov-93	VW-8	N/A	7.84	N/A	7.88	N/A	N/A	0.04	0.03
17-Nov-93	*VW-8	N/A	N/A	N/A	7.95	N/A	N/A	0.00	N/A
07-Jan-94	*VW-8	N/A	7.37	N/A	7.69	N/A	N/A	0.32	0.2
21-Jan-94	*VW-8	N/A	7.29	N/A	7.60	N/A	N/A	0.31	1.0
07-Mar-94	VW-8	N/A	6.51	N/A	6.85	N/A	N/A	0.34	0.8
08-Mar-94	*VW-8	N/A	6.64	N/A	6.91	N/A	N/A	0.27	0.55
09-Mar-94	*VW-8	N/A	6.64	N/A	6.92	N/A	N/A	0.28	1.25
18-Mar-94	*VW-8	N/A	6.90	N/A	7.11	N/A	N/A	0.21	1.0
29-Mar-94	*VW-8	N/A	6.61	N/A	6.91	N/A	N/A	0.30	1.2
31-Mar-94	*VW-8	N/A	6.51	N/A	6.78	N/A	N/A	0.27	0.4
07-Apr-94	*VW-8	N/A	7.18	N/A	7.51	N/A	N/A	0.33	0.8
14-Apr-94	*VW-8	N/A	7.33	N/A	7.60	N/A	N/A	0.27	0.05
14-21 Apr 94	^VW-8						SKIMMER BELT RECOVERY =		1.0
21-Apr-94	VW-8	N/A	7.23	N/A	7.60	N/A	N/A	0.37	0.10
28-Apr-94	*VW-8	N/A	N/A	N/A	7.55	N/A	N/A	0.00	0.05
04-May-94	VW-8	N/A	7.57	N/A	7.60	N/A	N/A	0.03	0.05
10-May-94	*VW-8	N/A	N/A	N/A	7.70	N/A	N/A	0.00	N/A
26-May-94	*VW-8	N/A	SHEEN	N/A	7.97	N/A	N/A	SHEEN	0.001
03-Jun-94	VW-8	N/A	N/A	N/A	8.14	N/A	N/A	0.00	N/A
08-Jun-94	VW-8	N/A	N/A	N/A	8.12	N/A	N/A	0.00	N/A
17-Jun-94	VW-8	N/A	N/A	N/A	8.05	N/A	N/A	0.00	N/A
20-Jun-94	VW-8	N/A	7.99	N/A	8.00	N/A	N/A	0.01	0.00
18-Jul-94	VW-8	N/A	N/A	N/A	6.81	N/A	N/A	0.00	N/A
26-Jul-94	VW-8	N/A	N/A	N/A	6.93	N/A	N/A	0.00	N/A
02-Aug-94	VW-8	N/A	N/A	N/A	6.98	N/A	N/A	0.00	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
09-Aug-94	VW-8	N/A	SHEEN	N/A	7.14	N/A	N/A	SHEEN	N/A
18-Aug-94	VW-8	N/A	SHEEN	N/A	7.11	N/A	N/A	SHEEN	N/A
08-Sep-94	VW-8	N/A	7.43	N/A	7.45	N/A	N/A	0.02	0.01
22-Sep-94	VW-8	N/A	N/A	N/A	7.26	N/A	N/A	0.00	N/A
30-Sep-94	VW-8	N/A	7.49	N/A	7.55	N/A	N/A	0.06	0.05
14-Oct-94	VW-8	N/A	N/A	N/A	6.98	N/A	N/A	0.00	N/A
25-Oct-94	VW-8	N/A	6.92	N/A	6.98	N/A	N/A	0.06	0.00
01-Nov-93	VW-9	N/A	8.21	N/A	8.34	N/A	N/A	0.13	0.1
02-Nov-93	VW-9	N/A	8.25	N/A	8.28	N/A	N/A	0.03	0.05
05-Nov-93	VW-9	N/A	7.70	N/A	7.81	N/A	N/A	0.11	0.07
10-Nov-93	VW-9	N/A	8.04	N/A	8.15	N/A	N/A	0.11	0.05
17-Nov-93	*VW-9	N/A	8.14	N/A	8.19	N/A	N/A	0.05	0.01
07-Jan-94	*VW-9	N/A	7.65	N/A	7.79	N/A	N/A	0.14	0.05
21-Jan-94	*VW-9	N/A	7.54	N/A	7.58	N/A	N/A	0.04	0.05
07-Mar-94	*VW-9	N/A	6.81	N/A	6.84	N/A	N/A	0.03	0.1
09-Mar-94	*VW-9	N/A	N/A	N/A	6.89	N/A	N/A	0.00	0.01
18-Mar-94	*VW-9	N/A	7.01	N/A	7.03	N/A	N/A	0.02	-
29-Mar-94	*VW-9	N/A	6.63	N/A	6.69	N/A	N/A	0.06	0.1
07-Apr-94	*VW-9	N/A	7.45	N/A	7.49	N/A	N/A	0.04	0.1
14-Apr-94	*VW-9	N/A	N/A	N/A	7.65	N/A	N/A	0.00	0.01
21-Apr-94	VW-9	N/A	N/A	N/A	7.56	N/A	N/A	0.00	N/A
28-Apr-94	VW-9	N/A	N/A	N/A	7.81	N/A	N/A	0.00	N/A
04-May-94	VW-9	N/A	7.66	N/A	7.68	N/A	N/A	0.02	0.03
10-May-94	VW-9	N/A	N/A	N/A	7.93	N/A	N/A	0.00	N/A
26-May-94	VW-9	N/A	8.23	N/A	8.28	N/A	N/A	0.05	0.01
18-Jul-94	VW-9	N/A	7.13	N/A	7.17	N/A	N/A	0.04	0.02
26-Jul-94	VW-9	N/A	N/A	N/A	7.16	N/A	N/A	0.00	N/A
08-Sep-94	VW-9	N/A	7.68	N/A	7.71	N/A	N/A	0.03	0.02
22-Sep-94	VW-9	N/A	7.56	N/A	7.57	N/A	N/A	0.01	0.00
30-Sep-94	VW-9	N/A	N/A	N/A	7.45	N/A	N/A	0.00	N/A
25-Oct-94	VW-9	N/A	7.12	N/A	7.14	N/A	N/A	0.02	0.00
01-Nov-93	VW-10	N/A	8.16	N/A	8.39	N/A	8.20	0.23	0.15
02-Nov-93	VW-10	N/A	8.22	N/A	8.27	N/A	8.23	0.05	0.05
05-Nov-93	VW-10	N/A	7.74	N/A	7.78	N/A	7.75	0.04	0.04
10-Nov-93	VW-10	N/A	8.03	N/A	8.04	N/A	8.03	0.01	0.01
17-Nov-93	VW-10	N/A	N/A	N/A	8.12	N/A	N/A	0.00	N/A
07-Jan-94	VW-10	N/A	N/A	N/A	7.67	N/A	N/A	0.00	N/A
07-Mar-94	VW-10	N/A	6.74	N/A	6.94	N/A	6.78	0.20	0.40
09-Mar-94	*VW-10	N/A	N/A	N/A	6.93	N/A	N/A	0.00	0.005
29-Mar-94	*VW-10	N/A	N/A	N/A	6.88	N/A	N/A	0.00	0.005
14-Apr-94	VW-10	N/A	N/A	N/A	7.59	N/A	N/A	0.00	N/A
21-Apr-94	VW-10	N/A	N/A	N/A	7.49	N/A	N/A	0.00	N/A
28-Apr-94	VW-10	N/A	N/A	N/A	7.74	N/A	N/A	0.00	N/A
04-May-94	VW-10	N/A	N/A	N/A	7.71	N/A	N/A	0.00	N/A
26-May-94	VW-10	N/A	N/A	N/A	8.17	N/A	N/A	0.00	N/A
26-Jul-94	VW-10	N/A	N/A	N/A	7.09	N/A	N/A	0.00	N/A
25-Oct-94	VW-10	N/A	SHEEN	N/A	7.09	N/A	N/A	SHEEN	N/A

TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA.

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
01-Nov-93	VW-11	N/A	N/A	N/A	8.20	N/A	N/A	0.00	N/A
02-Nov-93	VW-11	N/A	N/A	N/A	8.19	N/A	N/A	0.00	N/A
05-Nov-93	VW-11	N/A	N/A	N/A	8.02	N/A	N/A	0.00	N/A
10-Nov-93	VW-11	N/A	N/A	N/A	7.89	N/A	N/A	0.00	N/A
17-Nov-93	VW-11	N/A	N/A	N/A	8.12	N/A	N/A	0.00	N/A
07-Jan-94	VW-11	N/A	N/A	N/A	7.64	N/A	N/A	0.00	N/A
07-Mar-94	VW-11	N/A	N/A	N/A	6.64	N/A	N/A	0.00	N/A
29-Mar-94	VW-11	N/A	N/A	N/A	6.87	N/A	N/A	0.00	N/A
14-Apr-94	VW-11	N/A	N/A	N/A	7.51	N/A	N/A	0.00	N/A
28-Apr-94	VW-11	N/A	N/A	N/A	7.73	N/A	N/A	0.00	N/A
26-May-94	VW-11	N/A	N/A	N/A	8.19	N/A	N/A	0.00	N/A
26-Jul-94	VW-11	N/A	N/A	N/A	6.85	N/A	N/A	0.00	N/A
25-Oct-94	VW-11	N/A	N/A	N/A	6.85	N/A	N/A	0.00	N/A
01-Nov-93	VW-12	N/A	N/A	N/A	7.58	N/A	N/A	0.00	N/A
02-Nov-93	VW-12	N/A	N/A	N/A	7.67	N/A	N/A	0.00	N/A
05-Nov-93	VW-12	N/A	N/A	N/A	7.37	N/A	N/A	0.00	N/A
10-Nov-93	VW-12	N/A	N/A	N/A	7.49	N/A	N/A	0.00	N/A
17-Nov-93	VW-12	N/A	N/A	N/A	7.65	N/A	N/A	0.00	N/A
07-Jan-94	VW-12	N/A	N/A	N/A	7.16	N/A	N/A	0.00	N/A
07-Mar-94	VW-12	N/A	N/A	N/A	6.29	N/A	N/A	0.00	N/A
29-Mar-94	VW-12	N/A	N/A	N/A	6.21	N/A	N/A	0.00	N/A
14-Apr-94	VW-12	N/A	N/A	N/A	7.09	N/A	N/A	0.00	N/A
28-Apr-94	VW-12	N/A	N/A	N/A	7.27	N/A	N/A	0.00	N/A
26-May-94	VW-12	N/A	N/A	N/A	7.69	N/A	N/A	0.00	N/A
26-Jul-94	VW-12	N/A	N/A	N/A	6.59	N/A	N/A	0.00	N/A
25-Oct-94	VW-12	N/A	N/A	N/A	6.54	N/A	N/A	0.00	N/A
01-Nov-93	VW-13	N/A	N/A	N/A	7.47	N/A	N/A	0.00	N/A
02-Nov-93	VW-13	N/A	N/A	N/A	7.45	N/A	N/A	0.00	N/A
05-Nov-93	VW-13	N/A	N/A	N/A	7.65	N/A	N/A	0.00	N/A
10-Nov-93	VW-13	N/A	N/A	N/A	7.49	N/A	N/A	0.00	N/A
17-Nov-93	VW-13	N/A	N/A	N/A	7.70	N/A	N/A	0.00	N/A
07-Jan-94	VW-13	N/A	N/A	N/A	7.26	N/A	N/A	0.00	N/A
07-Mar-94	VW-13	N/A	N/A	N/A	6.38	N/A	N/A	0.00	N/A
29-Mar-94	VW-13	N/A	N/A	N/A	6.02	N/A	N/A	0.00	N/A
14-Apr-94	VW-13	N/A	N/A	N/A	7.18	N/A	N/A	0.00	N/A
28-Apr-94	VW-13	N/A	N/A	N/A	7.37	N/A	N/A	0.00	N/A
26-May-94	VW-13	N/A	N/A	N/A	7.79	N/A	N/A	0.00	N/A
26-Jul-94	VW-13	N/A	N/A	N/A	6.64	N/A	N/A	0.00	N/A
25-Oct-94	VW-13	N/A	N/A	N/A	6.54	N/A	N/A	0.00	N/A
01-Nov-93	VW-14	260.26	8.15	252.11	8.20	252.06	252.10	0.05	0.02
02-Nov-93	VW-14	260.26	N/A	N/A	7.96	252.30	N/A	0.00	N/A
05-Nov-93	VW-14	260.26	N/A	N/A	7.65	252.61	N/A	0.00	N/A
10-Nov-93	VW-14	260.26	N/A	N/A	7.70	252.56	N/A	0.00	N/A
17-Nov-93	VW-14	260.26	N/A	N/A	7.93	252.33	N/A	0.00	N/A
07-Jan-94	VW-14	260.26	N/A	N/A	7.35	252.91	N/A	0.00	N/A



TABLE 6 (CONT) SUMMARY OF GAUGING DATA FOR UNDERGROUND STORAGE TANK  
SITES #70 AND #72, ROBINS AIR FORCE BASE, GEORGIA

11206.69

Date	Well #	Casing Elev. (feet)	LPH Level (feet)	LPH Elev. (feet)	Water Level (feet)	Water Elev. (feet)	Corrected Water Elev. (feet)	LPH Thickness (feet)	LPH Recovered (gallons)
07-Mar-94	VW-14	260.26	N/A	N/A	6.51	253.75	N/A	0.00	N/A
29-Mar-94	VW-14	260.26	N/A	N/A	6.52	253.74	N/A	0.00	N/A
14-Apr-94	VW-14	260.26	N/A	N/A	7.33	252.93	N/A	0.00	N/A
28-Apr-94	VW-14	260.26	N/A	N/A	7.49	252.77	N/A	0.00	N/A
26-May-94	VW-14	260.26	N/A	N/A	7.90	252.36	N/A	0.00	N/A
26-Jul-94	VW-14	260.26	N/A	N/A	6.83	253.43	N/A	0.00	N/A
25-Oct-94	VW-14	260.26	N/A	N/A	6.85	253.41	N/A	0.00	N/A
08-Mar-94	VW-15	N/A	N/A	N/A	6.09	N/A	N/A	0.00	N/A
28-Apr-94	VW-15	N/A	N/A	N/A	6.39	N/A	N/A	0.00	N/A
26-May-94	VW-15	N/A	N/A	N/A	6.38	N/A	N/A	0.00	N/A
25-Oct-94	VW-15	N/A	N/A	N/A	6.36	N/A	N/A	0.00	N/A
08-Mar-94	VW-16	N/A	N/A	N/A	5.98	N/A	N/A	0.00	N/A
14-Apr-94	VW-16	N/A	N/A	N/A	6.78	N/A	N/A	0.00	N/A
28-Apr-94	VW-16	N/A	N/A	N/A	6.80	N/A	N/A	0.00	N/A
26-May-94	VW-16	N/A	N/A	N/A	6.80	N/A	N/A	0.00	N/A
25-Oct-94	VW-16	N/A	N/A	N/A	6.50	N/A	N/A	0.00	N/A

\* = WELL WAS GAUGED FOLLOWING REMOVAL OF PASSIVE RECOVERY WICK

^ = LIQUID PHASE HYDROCARBON RECOVERY BY SKIMMER BELT ON THESE DATES

WELL #:	GALLONS RECOVERED:
EA-2	1097.30
VW-8	8.89
VW-7	5.01
EA-1	3.02
VW-9	0.78
VW-10	0.66
VW-6	0.38
VW-3	0.16
VW-5	0.04
VW-1	0.02
VW-14	0.02

TOTAL LPH RECOVERED TO DATE = 1116.3

**APPENDIX D**

**LETTER DETAILING WATER DISCHARGE FLOWRATE AND CONCENTRATIONS**

June 2, 1995

Tom Kirby  
CEOIW  
Building 141, IWTP  
Robins AFB, GA 31098

Attn: Mr. Tom Kirby, Water Facility PoC

Dear Mr. Kirby:

The purpose of this letter is to outline the expected water discharge flowrate and contaminant levels of Total Petroleum Hydrocarbons (TPH) and benzene in the discharge water from the short-term bioslurper pilot tests at Warner Robins AFB. There will be two sites at Warner Robins AFB where the bioslurper pilot tests will be performed. They are the SS010 site and the #70 and #72 underground storage tank (UST) area. These two sites are contaminated with JP-4 jet fuel.

A site assessment was performed at the #70 and #72 UST site in August of 1994. The analytical results obtained from the groundwater samples collected gave ranges of TPH from <0.5 to 600.0 mg/L. The results for benzene in the groundwater ranged from <0.001 to 4.2 mg/L. And the results for all BTEX compounds in the site groundwater ranged from <0.001 to 13.85 mg/L.

A separate site assessment was performed at the SS010 site in August of 1989. The analytical results obtained from the groundwater samples collected at this site gave benzene in a concentration of 9.7 mg/L, and total BTEX (benzene, toluene, ethylbenzene, and total xylenes) compounds in a concentration of 29.9 mg/L. There was no analysis for TPH performed during this site assessment.

The amount of contaminant levels for TPH and benzene found in the groundwater sampling during these site assessments is approximate to the levels of contamination in the groundwater experienced at two other bioslurper short-term test sites; Travis AFB, California and Andrews AFB, Maryland. The short-term bioslurper pilot test has already been performed at these two sites. The following table documents the water discharge flowrates and the concentrations of TPH, benzene, and total BTEX compounds found in the bioslurper system discharge samples from the two pilot test sites.

Table 1. Bioslurper System Discharge Data at Travis AFB, California and Andrews AFB, Maryland

Base	Water Discharge Rate (gal/min)	TPH Concentration (mg/L)	Benzene Concentration (mg/L)	BTEX Concentration (mg/L)
Andrews AFB	1.26	72	0.074	0.715
		49	0.042	0.743
Travis AFB	1.33	16.8	1.03	7.83

During the short-term test performed at Travis AFB the system discharge water was sent directly to a full-sized Baker tank. The water discharge samples were taken from the outlet of the bioslurper oil/water separator. Figure 1 shows a schematic of the bioslurper system. The oil/water separator is designed to allow the product, JP-4 jet fuel at Robins AFB, and the groundwater being extracted from the monitoring well to separate into two distinct phases. Since the concentration levels at Travis AFB were low, no additional unit operations were used to further separate the oil and water extracted from the monitoring well during the short-term test. However, at Andrews AFB the concentration levels of TPH (analyzed as diesel fuel) were high, and the wastewater was surface discharged. Also, due to the extreme vacuum exerted by the bioslurper pump, an emulsion of site soils and fuel formed in the oil/water separator. The oil/water unit was, therefore, unable to completely separate the oil and water phases. And the resultant water discharge stream (cloudy-white in appearance) had a TPH concentration of 400 mg/L. Due to the occurrence of the emulsion and the high TPH concentration in the discharge stream, an additional settling tank was used to allow the water discharge stream to "clean itself" before being discharged to the surface. Analysis of the water discharge from the settling tank showed that the TPH concentration was reduced to less than 100 mg/L and the benzene concentration in the stream was also reduced to less than 0.1 mg/L.




Figure 1. Bioslurper Process Flow Diagram

It is believed that at both Robins AFB test sites the concentrations of TPH and benzene in the water discharge stream will not exceed 100 mg TPH/L, and 1.0 mg benzene/L. We are therefore requesting to discharge the bioslurper system wastewater directly to the base sanitary sewer. We will monitor the concentration of TPH and benzene in the waste stream throughout the bioslurper short-term testing. An additional oil/water separator will be on-site to further separate the extracted fuel and water phases. And if additional operations (i.e. a settling tank) are needed to reduce contaminant levels in the discharge stream they will be employed.

The bioslurper short-term tests at Robins AFB are tentatively scheduled to begin July 10, 1995. We expect the field activities to be completed in approximately 4 weeks.

We believe that the wastewater from the bioslurper system will not exceed the 100 mg/L TPH level experienced at the aforementioned bioslurper pilot test sites, and that we should expect a water discharge rate of approximately 1.25 gpm. If you have any questions, comments, or require additional information, please call me at (614) 424-6122, or my colleague, Eric Drescher, at (614) 424-3088.

Sincerely,

Jeffrey A. Kittel  
Program Manager  
Environmental Restoration Department

JAK

Attachments

cc: Mike Stevens  
WR-ALC EMR  
216 Ocmulgee Court  
Warner Robins AFB, GA 31098-1646

Mr. Patrick Haas  
Headquarters, AFCEE  
8001 Arnold Drive (Bldg. 642)  
Brooks AFB, TX 78235-5357

Mr. Mark Rounsavill, HSC/PKVBC  
Department of the Air Force  
Air Force Material Command  
PSC/PK, 3005 9th Street  
Brooks AFB, TX 78235-5353

Mr. Leon Sultan  
DCMAO Dayton  
Gentile Station  
1001 Hamilton Street  
Dayton, OH 45444-5300

Ms. Petra Rosales  
Contract Administrator  
Contract Management Branch HSC/PKVA  
8005 pth Street (Bldg. 627)  
Brooks AFB, TX 78235-5353

**APPENDIX B**  
**LABORATORY ANALYTICAL REPORTS**

# @ AIR TOXICS LTD.

AN ENVIRONMENTAL ANALYTICAL LABORATORY

## WORK ORDER #: 9508100

### Work Order Summary

CLIENT: Mr. Eric Dreschler  
Battelle Memorial Institute  
505 King Avenue  
Columbus, OH 43201

BILL TO: Same


PHONE: 614-424-3753  
FAX: 614-424-3667  
DATE RECEIVED: 8/15/95  
DATE COMPLETED: 8/23/95

INVOICE # 7781  
P.O. #  
PROJECT # G462201-30B1501 Bioslurper  
AMOUNT\$: \$568.51

<u>FRACTION #</u>	<u>NAME</u>	<u>TEST</u>	<u>RECEIPT</u> <u>VAC./PRES.</u>	<u>PRICE</u>
01A	R1-STACK-1 (9536)	TO-3	0.5 "Hg	\$120.00
02A	R1-STACK-2 (94906)	TO-3	2.0 "Hg	\$120.00
03A	R2-STACK-1 (9486)	TO-3	1.5 "Hg	\$120.00
04A	R2-STACK-2 (9473)	TO-3	3.0 "Hg	\$120.00
05A	Lab Blank	TO-3	NA	NC

Misc. Charges	1 Liter Summa Canister Preparation (4) @ \$10.00 each.	\$40.00
	Shipping (7/17/95)	\$48.51

CERTIFIED BY

  
Laboratory Director

DATE:

8/23/95

180 BLUE RAVINE ROAD, SUITE B FOLSOM, CA 95630  
(916) 985-1000 • (800) 985-5955 • FAX (916) 985-1020

# AIR TOXICS LTD.

SAMPLE NAME: R1-STACK-1 (9536)

ID#: 9508100-01A

## EPA METHOD TO-3

(Aromatic Volatile Organics in Air)

### GC/PID

File Name: 6081808 Date of Collection: 8/5/95  
Dil. Factor: 17000 Date of Analysis: 8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	17	55	370	1200
Toluene	17	65	140	540
Ethyl Benzene	17	75	20	88
Total Xylenes	17	75	65	290

## TOTAL PETROLEUM HYDROCARBONS

### GC/FID

(Quantitated as Jet Fuel)

File Name: 6081808 Date of Collection: 8/5/95  
Dil. Factor: 17000 Date of Analysis: 8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH* (C5+ Hydrocarbons)	170	1100	27000	180000
C2 - C4** Hydrocarbons	170	310	8300	15000

\*TPH referenced to Jet Fuel (MW=156)

\*\*C2 - C4 Hydrocarbons referenced to Propane (MW=44)

Container Type: 1 Liter Summa Canister



# AIR TOXICS LTD.

SAMPLE NAME: R1-STACK-2 (94906)

ID#: 9508100-02A

## EPA METHOD TO-3

(Aromatic Volatile Organics in Air)

### GC/PID

File Name:	6081814	Date of Collection:	8/6/95
Dil. Factor:	22000	Date of Analysis:	8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	22	71	660	2100
Toluene	22	84	260	1000
Ethyl Benzene	22	97	43	190
Total Xylenes	22	97	130	570

## TOTAL PETROLEUM HYDROCARBONS

### GC/FID

(Quantitated as Jet Fuel)

File Name:	6081814	Date of Collection:	8/6/95
Dil. Factor:	22000	Date of Analysis:	8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH* (C5+ Hydrocarbons)	220	1400	47000	300000
C2 - C4** Hydrocarbons	220	400	11000	20000

\*TPH referenced to Jet Fuel (MW=156)

\*\*C2 - C4 Hydrocarbons referenced to Propane (MW=44)

Container Type: 1 Liter Summa Canister

# AIR TOXICS LTD.

SAMPLE NAME: R2-STACK-1 (9486)

ID#: 9508100-03A

## EPA METHOD TO-3

(Aromatic Volatile Organics in Air)

### GC/PID

File Name:	6081813	Date of Collection: 8/10/95		
Dil. Factor:	11000	Date of Analysis: 8/18/95		
Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	11	36	830	2700
Toluene	11	42	890	3400
Ethyl Benzene	11	49	200	880
Total Xylenes	11	49	750	3300

## TOTAL PETROLEUM HYDROCARBONS

### GC/FID

(Quantitated as Jet Fuel)

File Name:	6081813	Date of Collection:	8/10/95	
Dil. Factor:	11000	Date of Analysis:	8/18/95	
	Det. Limit	Det. Limit	Amount	Amount
Compound	(ppmv)	(uG/L)	(ppmv)	(uG/L)
TPH* (C5+ Hydrocarbons)	110	710	60000	390000
C2 - C4** Hydrocarbons	110	200	2800	5100

\*TPH referenced to Jet Fuel (MW=156)

\*\*C2 - C4 Hydrocarbons referenced to Propane (MW=44)

Container Type: 1 Liter Summa Canister

# AIR TOXICS LTD.

SAMPLE NAME: R2-STACK-2 (9473)

ID#: 9508100-04A

## EPA METHOD TO-3

(Aromatic Volatile Organics in Air)

### GC/PID

File Name:	6081816	Date of Collection:	8/11/95
Dil. Factor:	220	Date of Analysis:	8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.22	0.71	13	42
Toluene	0.22	0.84	21	80
Ethyl Benzene	0.22	0.97	6.7	30
Total Xylenes	0.22	0.97	29	130

## TOTAL PETROLEUM HYDROCARBONS

### GC/FID

(Quantitated as Jet Fuel)

File Name:	6081816	Date of Collection:	8/11/95
Dil. Factor:	220	Date of Analysis:	8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH* (C5+ Hydrocarbons)	2.2	14	680	4400
C2 - C4** Hydrocarbons	2.2	4.0	69	130

\*TPH referenced to Jet Fuel (MW=156)

\*\*C2 - C4 Hydrocarbons referenced to Propane (MW=44)

Container Type: 1 Liter Summa Canister

# AIR TOXICS LTD.

SAMPLE NAME: Lab Blank

ID#: 9508100-05A

## EPA METHOD TO-3

(Aromatic Volatile Organics in Air)

### GC/PID

File Name:	6081807	Date of Collection:	NA
Dil. Factor:	1.0	Date of Analysis:	8/18/95

Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
Benzene	0.001	0.003	Not Detected	Not Detected
Toluene	0.001	0.004	Not Detected	Not Detected
Ethyl Benzene	0.001	0.004	Not Detected	Not Detected
Total Xylenes	0.001	0.004	Not Detected	Not Detected

## TOTAL PETROLEUM HYDROCARBONS

### GC/FID

(Quantitated as Jet Fuel)

File Name:	6081807	Date of Collection:	NA
Dil. Factor:	1.0	Date of Analysis:	8/18/95


Compound	Det. Limit (ppmv)	Det. Limit (uG/L)	Amount (ppmv)	Amount (uG/L)
TPH* (C5+ Hydrocarbons)	0.010	0.065	Not Detected	Not Detected
C2 - C4** Hydrocarbons	0.010	0.018	Not Detected	Not Detected

\*TPH referenced to Jet Fuel (MW=156)

\*\*C2 - C4 Hydrocarbons referenced to Propane (MW=44)

Container Type: NA





LUBRICATION ANALYSTS, INC.  
P.O. BOX 3427  
1604 WEST OAKRIDGE DRIVE  
ALBANY, GA 31706  
(912) 435-6826

### ANALYTICAL REPORT

**DATE:** AUGUST 4, 1995

**TO:** MR. ERIC DRESCHER  
BATTELLE MEMORIAL INSTITUTE  
505 KING AVENUE  
COLUMBUS, OHIO 43201-2693

**SUBJECT:** (05) WATER SAMPLES SUBMITTED FOR TPH (PURGABLE JET FUEL) ANALYSIS

**ORIGIN:** ROBINS AFB - BIOSLURPER  
SAMPLE DATE: 08/03/95  
RECEIVED IN LAB: 08/03/95

**METHODS:** 5030/8015 (GAS CHROMATOGRAPH - FLAME IONIZATION)

**DETECTION LIMITS:** 0.5 PPM

### RESULTS:

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>TPH JET FUEL (PPM)</u>
8073	R1 - H2O - 1	22.2 OWS
8074	R1 - H2O - 2	29.4 1500 gal tank
8075	R1 - H2O - 2(DUPLICATE)	31.4
8076	R1 - H2O - 3	19.9 After Clay #2
8077	R1 - H2O - 4	ND After Carbon #2


COMMENTS: ND = NONE DETECTED

RESPECTFULLY SUBMITTED,

*Brad Williams*  
BRAD WILLIAMS, LAB DIRECTOR  
BW/lk

REVIEWED BY,

*CB*



LUBRICATION ANALYSTS, INC.  
P.O. BOX 3427  
1604 WEST OAKRIDGE DRIVE  
ALBANY, GA 31706  
(912) 435-6826

**ANALYTICAL REPORT**

**DATE:** AUGUST 4, 1995

**TO:** MR. ERIC DRESCHER  
BATTELLE MEMORIAL INSTITUTE  
505 KING AVENUE  
COLUMBUS, OHIO 43201-2693

**SUBJECT:** (05) WATER SAMPLES SUBMITTED FOR BTEX ANALYSIS

**ORIGIN:** ROBINS AFB - BIOSLURPER  
SAMPLE DATE: 08/03/95  
RECEIVED IN LAB: 08/03/95

**METHODS:** 602 (GAS CHROMATOGRAPH - PHOTOIONIZATION)

**DETECTION LIMITS:** 0.5 ppb on all constituents (INSTRUMENT DETECTION) SPIKE RECOVERY 99.2%  
**RESULTS:**

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>B-T-E-X</u>	<u>(ppb)</u>
8073	R1 - H20 - 1	BENZENE	131.9
		TOLUENE	91.9
		ETHYLBENZENE	91.9
		XYLENES	739.2
8074	R1 - H20 - 2	BENZENE	302.9
		TOLUENE	331.6
		ETHYLBENZENE	126.1
		XYLENES	734.3
8075	R1 - H20 - 2 DUPLICATE	BENZENE	268.6
		TOLUENE	309.3
		ETHYLBENZENE	122.8
		XYLENES	884.9
8076	R1 - H20 - 3	BENZENE	222.4
		TOLUENE	184.6
		ETHYLBENZENE	42.9
		XYLENES	274.8

BTEX ANALYSES  
BATTELE MEMORIAL INSTITUTE  
PAGE 2

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>B-T-E-X</u>	<u>(ppb)</u>
8077	R1 - H20 - 4	BENZENE	ND
		TOLUENE	ND
		ETHYLBENZENE	ND
		XYLENES	ND

COMMENTS: ND = NONE DETECTED

RESPECTFULLY SUBMITTED,


*Brad Williams*

BRAD WILLIAMS, LAB DIRECTOR  
BW/lk

REVIEWED BY,

*Bw*





LUBRICATION ANALYSTS, INC.  
P.O. BOX 3427  
1604 WEST OAKRIDGE DRIVE  
ALBANY, GA 31706  
(912) 435-6826

### ANALYTICAL REPORT

DATE: AUGUST 16, 1995

TO: MR. ERIC DRESCHER  
BATTELLE MEMORIAL INSTITUTE  
505 KING AVENUE  
COLUMBUS, OHIO 43201-2693

SUBJECT: (06) WATER SAMPLES SUBMITTED FOR TPH (PURGABLE JET FUEL) ANALYSIS

ORIGIN: ROBINS AFB - BIOSLURPER  
SAMPLE DATE: 08/11/95  
RECEIVED IN LAB: 08/15/95

METHODS: 5030/8015 (GAS CHROMATOGRAPH - FLAME IONIZATION)

DETECTION  
LIMITS: 0.5 PPM

#### RESULTS:

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>TPH JET FUEL (PPM)</u>
8227	R2 - H20 - 1	45.9 OWS
8228	R2 - H20 - 2	36.0 1500 gal tank
8229	R2 - H20 - 2(DUPLICATE)	90.2
8230	R2 - H20 - 3	21.6 After Clay #2
8031	R2 - H20 - 4	ND After Carbon #2
8032	R2-H20-4(DUPLICATE)	ND

COMMENTS: ND = NONE DETECTED


RESPECTFULLY SUBMITTED,

*Brad Williams*

BRAD WILLIAMS, LAB DIRECTOR  
BW/cb

REVIEWED BY,

*CS*



LUBRICATION ANALYSTS, INC.  
P.O. BOX 3427  
1604 WEST OAKRIDGE DRIVE  
ALBANY, GA 31706  
(912) 435-6826

**ANALYTICAL REPORT**

**DATE:** AUGUST 16, 1995

**TO:** MR. ERIC DRESCHER  
BATTELLE MEMORIAL INSTITUTE  
505 KING AVENUE  
COLUMBUS, OHIO 43201-2693

**SUBJECT:** (06) WATER SAMPLES SUBMITTED FOR BTEX ANALYSIS

**ORIGIN:** ROBINS AFB - BIOSLURPER  
SAMPLE DATE: 08/11/95  
RECEIVED IN LAB: 08/15/95

**METHODS:** 602 (GAS CHROMATOGRAPH - PHOTOIONIZATION)

**DETECTION LIMITS:** 0.5 ppb on all constituents (INSTRUMENT DETECTION) SPIKE RECOVERY 99.2%  
**RESULTS:**

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>B-T-E-X</u>	<u>(ppb)</u>
8227	R2 - H20 - 1	BENZENE	185.8
		TOLUENE	51.6
		ETHYLBENZENE	391.9
		XYLENES	580.4
8228	R2 - H20 - 2	BENZENE	99.1
		TOLUENE	47.3
		ETHYLBENZENE	ND
		XYLENES	144.9
8229	R2 - H20 - 2(DUPLICATE) DUPLICATE	BENZENE	107.5
		TOLUENE	58.2
		ETHYLBENZENE	ND
		XYLENES	205.8
8230	R2 - H20 - 3	BENZENE	361.0
		TOLUENE	304.8
		ETHYLBENZENE	91.8
		XYLENES	568.7

BTX ANALYSES  
BATTELE MEMORIAL INSTITUTE  
PAGE 2

<u>LAB #</u>	<u>SAMPLE I.D.</u>	<u>B-T-E-X</u>	<u>(ppb)</u>
8231	R2 - H20 - 4	BENZENE TOLUENE ETHYLBENZENE XYLENES	ND ND ND ND
8232	R2 - H20 - 4(DUPLICATE)	BENZENE TOLUENE ETHYLBENZENE XYLENES	ND ND ND ND

RESPECTFULLY SUBMITTED,

*Brad Williams*  
BRAD WILLIAMS, LAB DIRECTOR  
BW/cb

REVIEWED BY,

CB



## Columbus Laboratories

## CHAIN OF CUSTODY RECORD

Form No. Revis. 2

[illegible]




**Battelle**

Columbus Laboratories

CHAIN OF CUSTODY RECORD

Form No. ROBINS-02

Project Title		SAMPLE TYPE (✓)		Container No.	Number of Containers	Remarks
Proj. No.						
G41-2201-30B1521		BIOSURFER - ROBINS AFB				
SAMPLERS: (Signature) <u>Eric Drescher</u>						
DATE	TIME	SAMPLE I.D.	TPH (Ingrable)	BTEX		
8/11/95	-	R2-H2O-1	X	X	8227	OWS
8/11/95	-	R2-H2O-2	X	X	8228	1500
8/11/95	-	R2-H2O-2 DUPLICATE	X	X	8229	1500
8/11/95	-	R2-H2O-3	X	X	8230	CARB #2
8/11/95	-	R2-H2O-4	X	X	8231	CARB #2
8/12/95	-	R2-H2O-4 DUPLICATE	X	X	8232	CARB #2
8/12/95	-	<del>R2-H2O-4</del>				
xx PLEASE ANALYZE SAMPLES FOR 24-Hr Turnaround FAX RESULTS TO ERIC DRESCHER (EMR)						
912-926-9642						
Relinquished by: (Signature) <u>Eric Drescher</u>		Date/Time	Received by: (Signature)	Relinquished by: (Signature)		Received by: (Signature)
8/14/95		3:00	<u>John ex.</u>			
Relinquished by: (Signature)		Date/Time	Received by: (Signature)	Relinquished by: (Signature)		Received by: (Signature)
8/15/95		7:30	<u>Malcolm Piegler</u>			
Relinquished by: (Signature)		Date/Time	Received for Laboratory by: (Signature)	Date/Time		Remarks
8/15/95						



# Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21  
Sparks, Nevada 89431  
(702) 355-1044  
FAX: 702-355-0406  
1-800-283-1183

Boise, Idaho  
(208) 336-4145

Las Vegas, Nevada  
(702) 386-6747

## ANALYTICAL REPORT

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#: Bio Slurper Robins AFB  
Phone: (614) 424-3088  
Attn: Eric Drescher

Sampled: 07/22-23/95 Received: 07/25/95 Analyzed: 07/31/95  
Matrix: [ X ] Soil [ ] Water [ ] Waste

Analysis Requested: TPH - Total Petroleum Hydrocarbons-Purgeable  
Quantitated As Gasoline  
BTXE - Benzene, Toluene, Xylenes, Ethylbenzene

Methodology: TPH - Modified 8015/DHS LUFT Manual/BLS-191  
BTXE - Method 624/8240

### Results:

Client ID/ Lab ID	Parameter	Concentration	Detection Limit
R1-MPA-7.0'- 7.5' /BMI072595-01	TPH (Purgeable)	31,000	1,000 mg/Kg
	Benzene	13,000	2,000 ug/Kg
	Toluene	19,000	2,000 ug/Kg
	Total Xylenes	190,000	2,000 ug/Kg
	Ethylbenzene	31,000	2,000 ug/Kg
R1-MPA-7.5'- 8.0' /BMI072595-02	TPH (Purgeable)	19,000	1,000 mg/Kg
	Benzene	14,000	2,000 ug/Kg
	Toluene	15,000	2,000 ug/Kg
	Total Xylenes	140,000	2,000 ug/Kg
	Ethylbenzene	24,000	2,000 ug/Kg
R2-MPA-6.0'- 6.5' /BMI072595-03	TPH (Purgeable)	430	100 mg/Kg
	Benzene	ND	200 ug/Kg
	Toluene	1,300	200 ug/Kg
	Total Xylenes	8,200	200 ug/Kg
	Ethylbenzene	1,300	200 ug/Kg
R2-MPA-6.5'- 7.0' /BMI072595-04	TPH (Purgeable)	410	100 mg/Kg
	Benzene	ND	200 ug/Kg
	Toluene	1,500	200 ug/Kg
	Total Xylenes	8,900	200 ug/Kg
	Ethylbenzene	1,400	200 ug/Kg

ND - Not Detected

Approved by:

*Roger L. Scholl*  
Roger L. Scholl, Ph.D.  
Laboratory Director

Date:

*8/3/95*

**Laboratory  
Analysis Report**



**Sierra  
Environmental  
Monitoring, Inc.**

**ALPHA ANALYTICAL  
255 GLENDALE AVENUE, SUITE 21  
SPARKS NV 89431**

**Date : 8/15/95  
Client : ALP-855  
Taken by: CLIENT  
Report : 13836  
PO# :**

Page: 1

Sample	Collected		MOISTURE CONTENT %	PARTICLE SIZE CLASSIF. HYDROMETER	DENSITY G/CM3	POROSITY %		
	Date	Time						
BMI072595-01 - R1-MPA-7.0-7.5'	7/22/95	:	9.6%	YES	1.21	45.7%		
BMI072595-03 - R2-MPA-6.0-6.5'	7/23/95	:	17.2%	YES	1.83	69.1%		

Approved By: 

This report is applicable only to the sample received by the laboratory. The liability of the laboratory is limited to the amount paid for this report. This report is for the exclusive use of the client to whom it is addressed and upon the condition that the client assumes all liability for the further distribution of the report or its contents.

1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404

William F. Pillsbury  
President

John C. Seher  
Manager



Sierra  
Environmental  
Monitoring, Inc.

November 27, 1995

TO: Alpha Analytical  
FROM: Sierra Environmental Monitoring, Inc.  
RE: Particle Size Distribution Analysis for Samples:  
SEM 9507-0719 AAI BMI072595-01  
SEM 9507-0720 AAI BMI072595-03

As per your request, we have performed particle size analysis on the samples submitted to our laboratory. Test results are as follows:

	BMI072595-01	BMI072595-03
% Sand	91.0	86.0
% Silt	4.0	4.0
% Clay	5.0	10.0

The sample was passed through a #10 sieve prior to analysis as per procedure. All results are based on oven dry sample weights.

We appreciate this opportunity to provide our laboratory testing services. If you have any questions or require further testing, please feel free to contact us at your convenience.

Sincerely,  
SIERRA ENVIRONMENTAL MONITORING, INC.

John Seher  
Laboratory Manager

William F. Pillsbury  
President

1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404

John C. Seher  
Manager



**Laboratory  
Analysis Report**



**Sierra  
Environmental  
Monitoring, Inc.**

**ALPHA ANALYTICAL  
255 GLENDALE AVENUE, SUITE 21  
SPARKS NV 89431**

**Date :  
Client : ALP-855  
Taken by: CLIENT  
Report : 13836  
PO# :**

**Page: 2**

---

**Ammended Report: Previous report contained an error in calculation of the  
soil porosity.**

**This report is applicable only to the sample received by the laboratory. The liability of the laboratory is limited to the amount paid for this report. This report is for the exclusive use of the client to whom it is addressed and upon the condition that the client assumes all liability for the further distribution of the report or its contents.**

---

**William F. Pillsbury  
President**

**1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404**

**John C. Seher  
Manager**

**Laboratory  
Analysis Report**



**Sierra  
Environmental  
Monitoring, Inc.**

**ALPHA ANALYTICAL  
255 GLENDALE AVENUE, SUITE 21  
SPARKS NV 89431**

**Date : 9/20/95  
Client : ALP-855  
Taken by: CLIENT  
Report : 13836  
PO# :**

Page: 1

Sample	Collected		MOISTURE CONTENT %	PARTICLE SIZE CLASSIF. HYDROMETER	DENSITY G/CM3	POROSITY %		
	Date	Time						
BMI072595-01 - R1-MPA-7.0-7.5'	7/22/95	:	9.6%	YES	1.21	54.3%		
BMI072595-03 - R2-MPA-6.0-6.5'	7/23/95	:	17.2%	YES	1.83	30.9%		

Approved By: 

This report is applicable only to the sample received by the laboratory. The liability of the laboratory is limited to the amount paid for this report. This report is for the exclusive use of the client to whom it is addressed and upon the condition that the client assumes all liability for the further distribution of the report or its contents.

William F. Pillsbury  
President

1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404

John C. Seher  
Manager

**Laboratory  
Analysis Report**



**Sierra  
Environmental  
Monitoring, Inc.**

**ALPHA ANALYTICAL  
255 GLENDALE AVENUE, SUITE 21  
SPARKS NV 89431**

**Date : 8/17/95  
Client : ALP-855  
Taken by: CLIENT  
Report : 13965  
PO# :**

Page: 1

Sample	Collected		FLASHPOINT					
	Date	Time	DEG C					
BMI080895-01 - R1-FUEL-1	8/04/95	:	49 F					

Approved By: 

This report is applicable only to the sample received by the laboratory. The liability of the laboratory is limited to the amount paid for this report. This report is for the exclusive use of the client to whom it is addressed and upon the condition that the client assumes all liability for the further distribution of the report or its contents.

William F. Pillsbury  
President

1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404

John C. Seher  
Manager

**Laboratory  
Analysis Report**



**Sierra  
Environmental  
Monitoring, Inc.**

**ALPHA ANALYTICAL  
255 GLENDALE AVENUE, SUITE 21  
SPARKS NV 89431**

**Date :  
Client : ALP-855  
Taken by: CLIENT  
Report : 13965  
PO# :**

**Page: 2**

---

**ANALYSIS PERFORMED BY UNITED TESTING GROUP**


---

This report is applicable only to the sample received by the laboratory. The liability of the laboratory is limited to the amount paid for this report. This report is for the exclusive use of the client to whom it is addressed and upon the condition that the client assumes all liability for the further distribution of the report or its contents.

**William F. Pillsbury  
President**

**1135 Financial Blvd.  
Reno, NV 89502  
Phone (702) 857-2400  
FAX (702) 857-2404**

**John C. Seher  
Manager**



## Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21

Sparks, Nevada 89431

(702) 355-1044

FAX: 702-355-0406

1-800-283-1183

Boise, Idaho  
(208) 336-4145

Las Vegas, Nevada  
(702) 386-6747

### Purgeable TPH Matrix Spike/Matrix Spike Duplicate Recovery EPA Method 5030/8015

Lab Name: Alpha Analytical, Inc.

Client ID: 18-MW-09

Date Analyzed: 08/16/95

AAI Lab ID: BM1081295-02

Compound	Spike Added (mg/L)	Sample Conc. (mg/L)	MS Conc. (mg/L)	MS % Recovery	Advisory Limits % Recovery
Gasoline	10	0	7.8	78	50-150


Compound	Spike Added (mg/L)	MSD Conc. (mg/L)	MSD % Recovery	% RPD	Advisory Limits % RPD	% Recovery
Gasoline	10	7.5	75	4	50	50-150



100-51407-23375013

[illegible]



**Alpha Analytical, Inc.**

255 Glendale Avenue, Suite 21

Sparks, Nevada 89431

(702) 355-1044

FAX: 702-355-0406

1-800-283-1183

Boise, Idaho

(208) 336-4145

Las Vegas, Nevada

(702) 386-6747

**ANALYTICAL REPORT**

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#:  
Phone: (614) 424-6199  
Attn: Al Pollock

Sampled: 08/05-06/95    Received: 08/08/95    Analyzed: 08/11/95

Matrix: [   ] Soil    [ X ] Water    [   ] Waste

Analysis Requested: TPH - Total Petroleum Hydrocarbons-Purgeable  
Quantitated As Gasoline

BTXE - Benzene, Toluene, Xylenes, Ethylbenzene

Methodology:            TPH - Modified 8015/DHS LUFT Manual/BLS-191  
BTXE - Method 624/8240

**Results:**

Client ID/ Lab ID	Parameter	Concentration	Detection Limit
R1-OutH20-1 /BMI080895-02	TPH (Gasoline)	ND	0.50 mg/L
	Benzene	ND	1.0 ug/L
	Toluene	ND	1.0 ug/L
	Total Xylenes	ND	1.0 ug/L
	Ethylbenzene	ND	1.0 ug/L
R1-OutH20-2 /BMI080895-03	TPH (Gasoline)	ND	0.50 mg/L
	Benzene	ND	1.0 ug/L
	Toluene	ND	1.0 ug/L
	Total Xylenes	ND	1.0 ug/L
	Ethylbenzene	ND	1.0 ug/L

ND - Not Detected

Approved by:


*Roger E. Scholl*

Roger E. Scholl, Ph.D.  
Laboratory Director

Date:

*8/18/95*



**Alpha Analytical, Inc.**

255 Glendale Avenue, Suite 21  
Sparks, Nevada 89431  
(702) 355-1044  
FAX: 702-355-0406  
1-800-283-1183

Boise, Idaho  
(208) 336-4145

Las Vegas, Nevada  
(702) 386-6747

**ANALYTICAL REPORT**

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#:  
Phone: (614) 424-6199  
Attn: Al Pollock

Sampled: 08/04/95      Received: 08/08/95      Analyzed: 08/16/95

Matrix: [    ] Soil      [    ] Water      [ X ] Other

Analysis Requested: BTXE - Benzene, Toluene, Xylenes, Ethylbenzene

Methodology:      BTXE - Method 624/8240

**Results:**

Client ID/ Lab ID	Parameter	Concentration	Detection Limit
R1-Fuel-1 /BMI080895-01	Benzene	460	350 mg/Kg
	Toluene	1,600	350 mg/Kg
	Total Xylenes	7,200	350 mg/Kg
	Ethylbenzene	1,100	350 mg/Kg

Approved by:

*Roger L. Scholl*  
Roger L. Scholl, Ph.D.  
Laboratory Director

Date:

*8/18/95*

**Alpha Analytical, Inc.**

255 Glendale Avenue, Suite 21  
Sparks, Nevada 89431  
(702) 355-1044  
FAX: 702-355-0406  
1-800-283-1183

Boise, Idaho  
(208) 336-4145

Las Vegas, Nevada  
(702) 386-6747

**ANALYTICAL REPORT**

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#:  
Phone: (614) 424-6199  
Attn: Al Pollock

Alpha Analytical Number: BMI080895-01

Client I.D. Number: R1-Fuel-1

Compound	Method	Concentration mg/Kg	Detection Limit mg/Kg	Date Analyzed
Benzene	8240	460	350	08/16/95
Toluene	8240	1,600	350	08/16/95
Total Xylenes	8240	7,200	350	08/16/95
Ethylbenene	8240	1,100	350	08/16/95
C-range Compounds	Method	Percentage of Total (%)	Detection Limit (Not	Date Analyzed
C9<	GC/FID	17.33	NA	08/22/95
C10	GC/FID	28.09	NA	08/22/95
C11	GC/FID	19.14	NA	08/22/95
C12	GC/FID	12.48	NA	08/22/95
C13	GC/FID	10.31	NA	08/22/95
C14	GC/FID	6.60	NA	08/22/95
C15	GC/FID	3.53	NA	08/22/95
C16	GC/FID	1.59	NA	08/22/95
C17>	GC/FID	0.93	NA	08/22/95

Approved by:

*Roger L. Scholl*  
Roger L. Scholl, Ph.D.  
Laboratory Director

Date:

*8/22/95*



**Battelle**

Columbus Laboratories

CHAIN OF CUSTODY RECORD




Form No. AD-1015-3

Project Title		SAMPLE TYPE (✓)		Container No.	Number of Containers	Remarks
DATE	TIME	SAMPLE I.D.				
9/14/95		1.1 - FUEL - 1			1	
9/15/95		1.1 - COAL - 1			1	
9/16/95		1.1 - OIL - 2			1	
PLEASE SEND RESULTS TO A. PULLACK						
PATTICE						
655 KIDDO AVE						
COLUMBUS OH 43201						
Relinquished by: (Signature)	Date/Time	Received by: (Signature)	Relinquished by: (Signature)	Date/Time	Received by: (Signature)	
<i>[Signature]</i>	9/17/95 7:00AM					
Relinquished by: (Signature)	Date/Time	Received by: (Signature)	Relinquished by: (Signature)	Date/Time	Received by: (Signature)	
Relinquished by: (Signature)	Date/Time	Received for Laboratory by: (Signature)	Date/Time	Remarks		
		<i>[Signature]</i>	9/18/95 1000			


**Alpha Analytical, Inc.**

255 Glendale Avenue, Suite 21  
Sparks, Nevada 89431  
Phone (702) 355-1044  
Fax (702) 355-0406

[illegible]

Relinquished by	Signature	Print Name	Company	Date	Time
Received by		Linda Lerner	AAZ	8/8/95	1000
Relinquished by		Linda Lerner	AAZ	8/9/95	1555
Received by		Jim Olferton	SEM	8/9/95	3:55
Relinquished by					
Received by					

**NOTE:** Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.



# Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21

Sparks, Nevada 89431

(702) 355-1044

FAX: 702-355-0406

1-800-283-1183

Boise, Idaho

(208) 336-4145

Las Vegas, Nevada

(702) 386-6747

## ANALYTICAL REPORT

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#: Robins AFB Bio Slurper  
Phone: (614) 424-6199  
Attn: Eric Drescher

Sampled: 08/07-10/95    Received: 08/25/95    Analyzed: 08/28/95

Matrix: [   ] Soil    [ X ] Water    [   ] Waste

Analysis Requested: TPH - Total Petroleum Hydrocarbons-Purgeable  
Quantitated As Gasoline

BTXE - Benzene, Toluene, Xylenes, Ethylbenzene

Methodology:            TPH - Modified 8015/DHS LUFT Manual/BLS-191  
BTXE - Method 624/8240

### Results:

Client ID/ Lab ID	Parameter	Concentration	Detection Limit
R2-OUT H2O-1 /BMI082595-02	TPH (Purgeable)	ND	0.50 mg/L
	Benzene	ND	1.0 ug/L
	Toluene	ND	1.0 ug/L
	Total Xylenes	ND	1.0 ug/L
	Ethylbenzene	ND	1.0 ug/L
R2-OUT H2O-2 /BMI082595-03	TPH (Purgeable)	ND	0.50 mg/L
	Benzene	ND	1.0 ug/L
	Toluene	ND	1.0 ug/L
	Total Xylenes	ND	1.0 ug/L
	Ethylbenzene	ND	1.0 ug/L
R1-OUT H2O-3 /BMI082595-04	TPH (Purgeable)	ND	0.50 mg/L
	Benzene	ND	1.0 ug/L
	Toluene	ND	1.0 ug/L
	Total Xylenes	ND	1.0 ug/L
	Ethylbenzene	ND	1.0 ug/L


ND - Not Detected

Approved by:

*Roger L. Scholl*  
Roger L. Scholl, Ph.D.  
Laboratory Director

Date:

*9/13/95*



## Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21  
Sparks, Nevada 89431  
(702) 355-1044  
FAX: 702-355-0406  
1-800-283-1183

Boise, Idaho  
(208) 336-4145

Las Vegas, Nevada  
(702) 386-6747

### ANALYTICAL REPORT

Battelle  
505 King Ave  
Columbus Ohio 43201

Job#: Robins AFB-Bioslurper  
Phone: (614) 424-6122  
Attn: Eric Drescher

Alpha Analytical Number: BMI082595-05

Client I.D. R2-Fuel-1

Compound	Method	Concentration ug/Kg	Detection Limit ug/Kg	Date Analyzed
Benzene	8240	ND	720,000	08/28/95
Toluene	8240	1,400,000	720,000	08/28/95
Total Xylenes	8240	18,000,000	720,000	08/28/95
Ethylbenene	8240	2,200,000	720,000	08/28/95
C-range Compounds	Method	Percentage of Total	Detection Limit (Not Applicable)	Date Analyzed
C9<	GC/FID	38.7	NA	09/12/95
C10	GC/FID	19.3	NA	09/12/95
C11	GC/FID	15.6	NA	09/12/95
C12	GC/FID	11.1	NA	09/12/95
C13	GC/FID	8.3	NA	09/12/95
C14	GC/FID	3.9	NA	09/12/95
C15	GC/FID	1.9	NA	09/12/95
C16	GC/FID	0.63	NA	09/12/95
C17>	GC/FID	0.45	NA	09/12/95


Approved by:

*Roger L. Scholl*

Roger L. Scholl, Ph.D.  
Laboratory Director

Date:

*9/13/95*



# Alpha Analytical, Inc.

255 Glendale Avenue, Suite 21

Sparks, Nevada 89431

(702) 355-1044

FAX: 702-355-0406

1-800-283-1183

Boise, Idaho

(208) 336-4145

Las Vegas, Nevada

(702) 386-6747

## WATER VOLATILE MATRIX SPIKE/MATRIX SPIKE DUPLICATE RECOVERY

EPA Method 624/8240

Lab Name: Alpha Analytical, Inc.

AAI Lab ID: BM1081295-02

Date Analyzed: 08/16/95

Compound	Spike Added (ug/L)	Sample Concentration (ug/L)	MS Concentration (ug/L)	MS Percent Recovery #	QC Limits Recovery
Benzene	50	0	39	78	76-127
Toluene	50	0	45	90	76-125

Compound	Spike Added (ug/L)	MSD Concentration (ug/L)	MSD Percent Recovery #	Percent RPD #	QC Limits RPD Recovery	
Benzene	50	47	94	19*	11	76-127
Toluene	50	57	114	24*	13	76-125

# - Column to be used to flag recovery and RPD values with an asterisk

\* - Values outside of QC limits

RPD: 2 out of 2 outside of limits

Spike Recovery: 0 out of 4 outside of limits



**Battelle**

Columbus Laboratories

Proj. No.  
C462201-

30B1501

Project Title

ROBINS AFB- BIOSURPER

SAMPLERS: (Signature)

*Tim Dresher*

CHAIN OF CUSTODY RECORD

Form No.

ROBINS - 4

Project Title		SAMPLE TYPE (✓)				Number of Containers	Remarks
DATE	TIME	SAMPLE I.D.	BTEX	Boiling Pt Range	TPH (as jet fuel)		
8/10/95	-	R2 - OUTH <sub>2</sub> O - 1	X		X	1	
	-	R2 - OUTH <sub>2</sub> O - 1 DUP	X		X	1	
8/11/95	-	R2 - OUTH <sub>2</sub> O - 2	X		X	1	
	-	R2 - OUTH <sub>2</sub> O - 2 DUP	X		X	1	
		<del>R2 - OUTH<sub>2</sub>O</del>					
8/7/95	-	R1 - OUTH <sub>2</sub> O - 3	X		X	1	
	-	R1 - OUTH <sub>2</sub> O - 3 DUP	X		X	1	
8/10/95	-	R2 - FUEL - 1	X	X	X	1	
DO NOT ANALYZE THE DUPLICATE SAMPLES UNLESS THE ORIGINALS CONTAIN BTEX AND/OR TPH. THANKS.							
Relinquished by: (Signature)		Date/Time	Received by: (Signature)		Date/Time	Received by: (Signature)	
<i>Tim Dresher</i>		8/21/95					
Relinquished by: (Signature)		Date/Time	Received by: (Signature)		Date/Time	Received by: (Signature)	
Relinquished by: (Signature)		Date/Time	Received for Laboratory by: (Signature)		Date/Time	Remarks	
			<i>Tim Dresher</i>		8/23/95 1130		



**Billing Information:**

Name \_\_\_\_\_  
 Address \_\_\_\_\_  
 City, State, Zip \_\_\_\_\_  
 Phone Number \_\_\_\_\_

**Alpha Analytical, Inc.**  
 255 Glendale Avenue, Suite 21  
 Sparks, Nevada 89431  
 Phone (702) 355-1044  
 Fax (702) 355-0406



Client Name		Address		City, State, Zip		Report Attention		P.O. #		Phone #		Analyses Required		Remarks	
Time	Date	Sampled	Lab ID Number	Sampled by	Sample Description	Number of Containers									
5/10	5/10	✓	03	03	R2 - OUTH2O - 1 + Dupl A 2	2									
5/11	5/11	✓	04	04	R2 - OUTH2O - 2 + Dupl A 2	2									
5/12	5/12	✓	05	05	R1 - OUTH2O - 3 + Dupl C 2	2									
5/13	5/13	✓	06	06	R2 - Fuel - 1	1									
5/14	5/14	✓	07	07											
5/15	5/15	✓													
5/16	5/16	✓													
5/17	5/17	✓													
5/18	5/18	✓													
5/19	5/19	✓													
5/20	5/20	✓													
5/21	5/21	✓													
5/22	5/22	✓													
5/23	5/23	✓													
5/24	5/24	✓													
5/25	5/25	✓													
5/26	5/26	✓													
5/27	5/27	✓													
5/28	5/28	✓													
5/29	5/29	✓													
5/30	5/30	✓													
5/31	5/31	✓													

Signature	Print Name	Company	Date	Time
<i>[Signature]</i>	Linda CERNER	AAZ	8/25/85	1030
Relinquished by				
Received by				
Relinquished by				
Received by				
Relinquished by				
Received by				

NOTE: Samples are discarded 60 days after results are reported unless other arrangements are made. Hazardous samples will be returned to client or disposed of at client expense.

\*Key: AQ - Aqueous      SO - Soil      WA - Waste      OT - Other

**APPENDIX C**  
**SYSTEM CHECKLISTS**

**SITE UST 70/72**

# Checklist for System Shakedown

Site: UST 70/72

Date: 7/24/95

Operator's Initials: ED/MW

Equipment	Check if Okay	Comments
Liquid Ring Pump	X	5.0-hp liquid ring pump has failed, have sent for a new liquid ring pump
Aqueous Effluent Transfer Pump	✓	
Oil/Water Separator	✓	
Vapor Flowmeter	✓	
Fuel Flowmeter	✓	
Water Flowmeter	✓	
Emergency Shut off Float Switch Effluent Transfer Tank	✓	
Analytical Field Instrumentation GasTector™ O <sub>2</sub> /CO <sub>2</sub> Analyzer TraceTector™ Hydrocarbon Analyzer Oil/Water Interface Probe Magnehelic Boards Thermocouple Thermometer	✓ ✓ ✓ ✓ ✓	Calibrated GasTector Analyzer w/ 10% O <sub>2</sub> /CO <sub>2</sub> Calibration Gases

**SITE SS010**

# Checklist for System Shakedown

Site: 55010

Date: 8/9/95

Operator's Initials: ED/KF

Equipment	Check if Okay	Comments
Liquid Ring Pump	✓	
Aqueous Effluent Transfer Pump	✓	
Oil/Water Separator	✓	
Vapor Flowmeter	✓	
Fuel Flowmeter	✓	
Water Flowmeter	✓	
Emergency Shut off Float Switch Effluent Transfer Tank	✓	
Analytical Field Instrumentation GasTector™ O <sub>2</sub> /CO <sub>2</sub> Analyzer TraceTector™ Hydrocarbon Analyzer Oil/Water Interface Probe Magnetic Helic Boards Thermocouple Thermometer	✓ ✓ ✓ ✓ ✓	Calibrated all Tectors w/ Calibration gas

**APPENDIX D**

**DATA SHEETS FROM THE SHORT-TERM PILOT TEST**

**SITE UST 70/72**



## LIQUID DISCHARGE LOG

DESCRIPTION OF CONTAMINANTS: NONE TPH 0 ppm (ND)  
BTEX 0 ppm (ND)

DRUM NUMBER	SOURCE	VOLUME OF LIQUIDS (gallons)
BY SEWER LINE	UST SITE 70/72	Skimmer = 1420 gal
	WELL EA-2	Bioslurper = 5425 gal
		Drawdown = 1910 gal
		Total = 8755 gal

# Baildown Test Record Sheet

Site: ROBINS AFB - SITE UST 70/72

Well Identification: EA-2

Well Diameter (OD/ID): 4"

Date at Start of Test: 7/20/95

Sampler's Initials: ED/MW

Time at Start of Test: 8:30

## Initial Readings

Depth to Groundwater (ft)	Depth to LNAPL (ft)	LNAPL Thickness (ft)	Total Volume Bailed (L)
8.50	6.67	1.83	5.8 L.

## Test Data

Sample Collection Time	Depth to Groundwater (ft)	Depth to LNAPL (ft)	LNAPL Thickness (ft)
0:00	8.09	6.78	1.31
0:10	8.35	6.67	1.68
0:20	8.38	6.67	1.71
0:30	8.40	6.67	1.73
3:04	8.45	6.67	1.78
7:26	8.47	6.67	1.80
22:06	8.50	6.67	1.83

TIME  
8:50  
7/20/95

11:54

16:16

7/21/95 6:56 am

UST 70/72 Site - Robins AFB																
Test : Skimmer Pump Test #1																
Time (min)	Time (hr)	LNAPL Recovery Col. (gal)	LNAPL Recovery Total (gal)	LNAPL Flowrate (gpm)	Total LNAPL Flowrate (gpm)	Groundwater Col. (gal)	Groundwater Removal Rate Total (gal)	Total GW Flowrate (gpm)	Total GW Flowrate (gph)	Time Period GW Flowrate (gpm)	Diff. Stack Pressure (in H <sub>2</sub> O)	Stack Temperature (deg C)	Pump Head Vacuum (in Hg)	Ambient Temperature (deg C)	Relative Humidity (%)	Barometric Pressure (in Hg)
0	0	0	0	0.00	0.00	0	0.0	0.00	0.00	0.00	0.03	37.4	26	34.2	55	29.4
60	1	1.2	1.2	0.02	1.20	35	35.0	0.58	35.00	0.58						
150	2.5	1.2	2.4	0.02	0.96	33	68.0	0.45	27.20	0.37						
225	3.75	1.2	3.6	0.02	0.96	37	105.0	0.47	28.00	0.49	0.015	41.2	25.5			
330	5.5	1.3	4.9	0.01	0.89	70	175.0	0.53	31.82	0.67						
540	9	2.6	7.5	0.01	0.83	100	275.0	0.51	30.56	0.48						
960	16	4.5	12	0.01	0.75	215	490.0	0.51	30.63	0.51	0.045	40.5	26			
1110	18.5	0.5	12.5	0.01	0.68	90	580.0	0.52	31.35	0.60						
1800	30	4.3	16.8	0.01	0.56	380	960.0	0.53	32.00	0.55	0.03	38.6	24.5	35.5	30	29.2
1950	32.5	0.7	17.5	0.01	0.54	110	1070.0	0.55	32.92	0.73						
2160	36	0.4	17.9	0.01	0.50	170	1240.0	0.57	34.44	0.81	0.02	41.2	25			
2325	38.75	0.1	18	0.01	0.46	120	1360.0	0.58	35.10	0.73						
2415	40.25	0.2	18.2	0.01	0.45	60	1420.0	0.59	35.28	0.67	0.035	41.6	25			
Test : Skimmer Pump Test #2																
Time (min)	Time (hr)	LNAPL Recovery Col. (gal)	LNAPL Recovery Total (gal)	LNAPL Flowrate (gpm)	Total LNAPL Flowrate (gpm)	Groundwater Col. (gal)	Groundwater Removal Rate Total (gal)	Total GW Flowrate (gpm)	Total GW Flowrate (gph)	Time Period GW Flowrate (gpm)	Diff. Stack Pressure (in H <sub>2</sub> O)	Stack Temperature (deg C)	Pump Head Vacuum (in Hg)	Ambient Temperature (deg C)	Relative Humidity (%)	Barometric Pressure (in Hg)
0	0	0	0.00	0.00	0.00	0.0	0.0	0.00	0.00	0.00	0.05	39.5	26	36.3	25	29
90	1.5	0.9	0.90	0.01	0.60	51.0	51.0	0.57	34.00	0.57						
270	4.5	1.4	2.30	0.01	0.51	94.0	145.0	0.54	32.22	0.52	0.04	40.1	25.5			
480	8	1.4	3.70	0.01	0.46	114.0	259.0	0.54	32.38	0.54						
1290	21.5	0.7	4.40	0.00	0.20	418.0	677.0	0.52	31.49	0.52						
1335	22.25	0.2	4.60	0.00	0.21	20.0	697.0	0.52	31.33	0.44	0.015	41.2	22.5			



**SITE SS010**

## LIQUID DISCHARGE LOG

DESCRIPTION OF CONTAMINANTS: NONE TPH 0 ppm (ND)  
BTEX 0 ppm (ND)

DRUM NUMBER	SOURCE	VOLUME OF LIQUIDS (gallons)
Bf TANK (200 gal)	JP-4 SPILL SITE	1850 8/10
"	"	1400 8/11
"	"	1400 8/12
"	"	1400 8/13
"	"	1400 8/14
"	"	800 8/15
		Total = 8250gal

# Baildown Test Record Sheet

Site: ROBINS AFB - SITE 55010

Well Identification: LIF-3

Well Diameter (OD/ID): 2"

Date at Start of Test: 7/22/95

Sampler's Initials: ED/MW

Time at Start of Test: 2:00 pm

## Initial Readings

Depth to Groundwater (ft)	Depth to LNAPL (ft)	LNAPL Thickness (ft)	Total Volume Bailed (L)
7.30	6.78	0.52	1.6

## Test Data

Sample Collection Time	Depth to <del>Groundwater</del> LNAPL (ft)	<sup>H<sub>2</sub>O</sup> Depth to <del>LNAPL</del> (ft)	LNAPL Thickness (ft)
01:00	6.89	6.91	0.02
01:10	6.87	6.92	0.05
01:20	6.85	6.93	0.08
01:30	6.84	6.93	0.09
1:30	6.83	6.95	0.12
13:45	6.82	6.97	0.15
20:20	6.82	6.97	0.15
23:40	6.81	6.97	0.16
47:15	6.79	7.07	0.28
66:30	6.77	7.22	0.45

### Baildown Test Record Sheet

Site: ROBINS AFB - SITE SS010

Well Identification: PZ-1

Well Diameter (OD/ID): 1"

Date at Start of Test: 7/22/95

Sampler's Initials: ED/mw

Time at Start of Test: 9:00

#### Initial Readings

Depth to Groundwater (ft)	Depth to LNAPL (ft)	LNAPL Thickness (ft)	Total Volume Bailed (L)
4.60	3.90	0.70	0.9

#### Test Data

Sample Collection Time	Depth to Groundwater (ft)	Depth to LNAPL (ft)	LNAPL Thickness (ft)
0:00	4.06	4.05	0.01
0:10	4.09	4.05	0.05
0:20	4.11	4.04	0.07
0:30	4.11	4.03	0.08
1:30	4.20	4.03	0.17
15:00	4.22	4.02	0.20
20:40	4.24	4.02	0.22
24:05	4.27	4.00	0.27
47:20	4.39	3.95	0.44
66:40	4.50	3.95	0.55

Figure 7. Typical Baildown Test Record Sheet



SS010 Site - Robins AFB													
Test : Skimmer Pump Test													
Time (min)	Time (hr)	LNAPL Recovery Col. (gal)	LNAPL Recovery Total (gal)	Total LNAPL Flowrate (gpm)	Total LNAPL Flowrate (gph)	Groundwater Removal Rate Col. (gal)	Groundwater Removal Rate Total (gal)	Total GW Flowrate (gpm)	Total GW Flowrate (gph)	Time Period GW Flowrate (gpm)	Time Period GW Flowrate (gph)	Diff. Stack Pressure (in H <sub>2</sub> O)	Stack Temperature (deg C)
0	0	0	0	0.00	0.00	0	0.0	0.00	0.00	0.00	0.00	0.045	39.5
60	1	0	0	0.00	0.00	28	28.0	0.47	28.00	0.47	28.00	0.47	39.5
105	1.75	0.8	0.8	0.01	0.46	28	28.0	0.53	32.00	0.56	32.00	0.56	39.5
300	5	0.4	1.2	0.00	0.24	110	186.0	0.55	33.20	0.56	33.20	0.56	39.5
960	16	0.5	1.7	0.00	0.11	399	565.0	0.59	35.31	0.60	35.31	0.60	39.5
1740	29	0.2	1.9	0.00	0.07	485	1050.0	0.60	36.21	0.62	36.21	0.62	39.5
2040	34	2.3	2.3	0.00	0.07	1245.0	1245.0	0.61	36.62	0.65	36.62	0.65	39.5
2340	39	0.2	2.5	0.00	0.06	180	1425.0	0.61	36.54	0.60	36.54	0.60	39.5
2550	42.5	0	2.5	0.00	0.06	125	1550.0	0.61	36.47	0.60	36.47	0.60	39.5
SS010 Site - Robins AFB													
Test : Vacuum Enhancement Pump Test													
Time (min)	Time (hr)	LNAPL Recovery Col. (gal)	LNAPL Recovery Total (gal)	Total LNAPL Flowrate (gpm)	Total LNAPL Flowrate (gph)	Groundwater Removal Rate Col. (gal)	Groundwater Removal Rate Total (gal)	Total GW Flowrate (gpm)	Total GW Flowrate (gph)	Time Period GW Flowrate (gpm)	Time Period GW Flowrate (gph)	Diff. Stack Pressure (in H <sub>2</sub> O)	Stack Temperature (deg C)
0	0	0	0	0.00	0.00	0	0.0	0.00	0.00	0.00	0.00	0.03	39.5
30	0.5	0	0	0.00	0.00	35.0	35.0	1.17	70.00	1.17	70.00	1.17	39.5
90	1.5	1.1	1.1	0.01	0.73	70.0	105.0	1.17	70.00	1.17	70.00	1.17	39.5
390	6.5	1.2	2.30	0.01	0.35	321.0	426.0	1.09	65.54	1.07	65.54	1.07	39.5
860	11	0	2.30	0.00	0.21	249.0	675.0	1.02	61.36	0.92	61.36	0.92	39.5
1620	27	3.3	5.60	0.00	0.21	1019.0	1894.0	1.05	62.74	1.06	62.74	1.06	39.5
1920	32	1.2	6.80	0.00	0.21	316.0	2010.0	1.05	62.81	1.05	62.81	1.05	39.5
3240	54	1.4	8.20	0.00	0.15	1375.0	3385.0	1.04	62.89	1.04	62.89	1.04	39.5
3360	56	1.9	10.10	0.00	0.18	65.0	3450.0	1.03	61.61	0.54	61.61	0.54	39.5
4170	69.5	0.4	10.50	0.00	0.15	865.0	4315.0	1.03	62.09	1.07	62.09	1.07	39.5
4350	72.5	0.4	10.90	0.00	0.15	144.0	4459.0	1.03	61.50	0.80	61.50	0.80	39.5
4820	77	0.2	11.10	0.00	0.14	231.0	4690.0	1.02	60.91	0.86	60.91	0.86	39.5
5145	85.75	0.4	11.50	0.00	0.13	530.0	5220.0	1.01	60.87	1.01	60.87	1.01	39.5
SS010 Site - Robins AFB													
Test : Drawdown Pump Test													
Time (min)	Time (hr)	LNAPL Recovery Col. (gal)	LNAPL Recovery Total (gal)	Total LNAPL Flowrate (gpm)	Total LNAPL Flowrate (gph)	Groundwater Removal Rate Col. (gal)	Groundwater Removal Rate Total (gal)	Total GW Flowrate (gpm)	Total GW Flowrate (gph)	Time Period GW Flowrate (gpm)	Time Period GW Flowrate (gph)	Diff. Stack Pressure (in H <sub>2</sub> O)	Stack Temperature (deg C)
0	0	0	0	0.00	0.00	0	0.0	0.00	0.00	0.00	0.00	0.05	39.8
120	2	0	0	0.00	0.00	185.0	185.0	1.54	92.50	1.54	92.50	1.54	39.8
360	6	0.25	0.25	0.00	0.04	333.0	518.0	1.44	86.33	1.39	86.33	1.39	39.8
510	8.5	0	0.25	0.00	0.03	174.0	692.0	1.36	81.41	1.18	81.41	1.18	39.8
1320	22	0	0.25	0.00	0.01	952.0	1844.0	1.25	74.73	1.18	74.73	1.18	39.8
1560	26	0.25	0.50	0.00	0.02	321.0	1965.0	1.26	75.58	1.34	75.58	1.34	39.8
1980	33	0	0.50	0.00	0.02	515.0	2480.0	1.25	75.15	1.23	75.15	1.23	39.8

**APPENDIX E**  
**SOIL GAS PERMEABILITY TEST RESULTS**

**SITE UST 70/72**

Site: UST 70/72

Blower Type: 7.5HP Liquid Ring Pump

Time (min.)	Monitoring Point A 8 ft. from vent well		
	Green: 3'	Blue: 5'	Red: 7'
0	0.000	0.000	0.000
5	0.010	1.000	1.700
10	0.020	1.500	1.900
35	0.030	1.500	2.100
50	0.030	1.750	2.000
75	0.030	1.750	2.050
140	0.250	1.750	1.950
1510	0.040	2.000	2.100
1685	0.350	1.950	2.100

Time (min.)	Monitoring Point B 37 ft. from vent well		
	Green: 3'	Blue: 5'	Red: 7'
0	0.000	0.000	0.000
5	0.010	0.050	0.250
10	0.050	0.150	0.500
35	0.070	0.270	0.500
50	0.070	0.250	0.500
75	0.070	0.300	0.520
140	0.070	0.230	0.500
1510	0.070	0.320	0.630
1685	0.070	0.250	0.520

Time (min.)	Monitoring Point C 81 ft. from vent well		
	Green: 3'	Blue: 5'	Red: 7'
0	0.000	0.000	0.000
5	0.000	0.000	0.000
10	0.000	0.000	0.000
35	0.000	0.000	0.010
50	0.000	0.000	0.000
75	0.000	0.000	0.000
140	0.000	0.000	0.000
1510	0.000	0.000	0.000
1685	0.000	0.000	0.000

**SITE SS010**

Site: SS-010 JP-4 Spill Site

Blower Type: 7.5HP Liquid Ring Pump

Time (min.)	Monitoring Point A 12 ft. from vent well		
	Green: 2'	Blue: 4'	Red: 6'
0	0.000	0.000	0.000
1	0.010	0.090	0.100
5	0.090	0.180	0.250
15	0.200	0.500	0.600
30	0.220	0.550	0.600
60	0.250	0.800	1.200
150	0.250	0.850	1.200
860	0.250	0.900	1.200
1535	0.230	0.900	1.250
2820	0.250	0.900	1.250

Time (min.)	Monitoring Point B 25 ft. from vent well		
	Green: 2'	Blue: 4'	Red: 6'
0	0.000	0.000	0.000
1	0.200	0.120	0.150
5	0.160	0.500	0.500
15	0.170	0.550	0.550
30	0.160	0.500	0.500
60	0.170	0.750	0.950
150	0.170	0.800	1.000
860	0.170	0.800	1.000
1535	0.160	0.750	1.000
2820	0.170	0.750	1.050

Time (min.)	Monitoring Point C 38 ft. from vent well		
	Green: 2'	Blue: 4'	Red: 6'
0	0.000	0.000	0.000
1	0.070	0.100	0.100
5	0.130	0.150	0.450
15	0.130	0.170	0.480
30	0.150	0.170	0.550
60	0.160	0.170	0.650
150	0.160	0.170	0.650
860	0.160	0.170	0.650
1535	0.140	0.170	0.650
2820	0.140	0.170	0.650

**APPENDIX F**  
**IN SITU RESPIRATION TEST RESULTS**

**SITE UST 70/72**



# In Situ Respiration Test


Site Name: UST 70/72 - Robins A

Date: 8/16/95

Depth of M.P. (ft): 7'

Monitoring Point: R1-MPA-7

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/11/95 9:30	0.0	20.90	0.50	1.90
8/11/95 9:40	0.2	20.90	0.50	1.90
8/11/95 9:50	0.3	20.70	0.50	1.70
8/11/95 10:00	0.5	20.70	0.50	1.70
8/11/95 10:30	1.0	20.50	0.50	1.80
8/11/95 12:30	3.0	20.50	0.50	1.80
8/11/95 23:40	14.2	17.90	0.90	1.80
8/12/95 10:00	24.5	16.20	1.90	1.40
8/13/95 13:20	51.8	12.50	6.80	1.10
8/14/95 11:30	74.0	7.10	13.00	1.10



Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.1785	0.1545
Intercept	20.8151	-0.0581
Determination Coef.	0.9927	0.9353
No. of Data Points.	10	10

## O<sub>2</sub> Utilization Rate

K <sub>0</sub>	0.003 %/min
	0.178 %/hr
	4.283 %/day

# In Situ Respiration Test


Date: 8/16/95

Site Name: UST 70/72 - Robins A

Monitoring Point: R1-MPB-7

Depth of M.P. (ft): 7'

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/11/95 9:30	0.0	20.90	0.30	1.80
8/11/95 9:40	0.2	20.50	0.50	1.80
8/11/95 9:50	0.3	20.50	0.50	1.80
8/11/95 10:00	0.5	20.00	0.60	1.70
8/11/95 10:30	1.0	19.80	0.70	1.80
8/11/95 12:30	3.0	19.70	0.70	1.80
8/11/95 23:40	14.2	18.20	0.80	1.70
8/12/95 10:00	24.5	17.00	1.10	1.50
8/13/95 13:20	51.8	11.00	7.50	1.20
8/14/95 11:30	74.0	5.00	12.70	1.10



## O<sub>2</sub> Utilization Rate

Ko	0.003 %/min
	0.199 %/hr
	4.767 %/day

Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.1986	0.1540
Intercept	20.6270	-0.0706
Determination Coef.	0.9842	0.9229
No. of Data Points.	10	10

# In Situ Respiration Test


Date: 8/16/95

Site Name: UST 70/72 - Robins A

Monitoring Point: R1-MPC-7

Depth of M.P. (ft): 7'

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/11/95 9:30	0.0	20.90	0.30	1.80
8/11/95 9:40	0.2	20.90	0.40	1.80
8/11/95 9:50	0.3	20.90	0.40	1.80
8/11/95 10:00	0.5	20.90	0.50	1.80
8/11/95 10:30	1.0	20.70	0.50	1.80
8/11/95 12:30	3.0	20.50	0.50	1.80
8/11/95 23:40	14.2	20.50	0.50	1.80
8/12/95 10:00	24.5	18.20	0.80	1.80
8/13/95 13:20	51.8	17.20	1.00	1.40
8/14/95 11:30	74.0	11.80	7.30	1.10



Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.1080	0.0679
Intercept	21.0801	0.0688
Determination Coef.	0.9246	0.6789
No. of Data Points.	10	10

## O<sub>2</sub> Utilization Rate

Ko	0.002 %/min
	0.108 %/hr
	2.591 %/day

**SITE SS010**

# In Situ Respiration Test


Site Name: SS010 - Robins AFB

Date: 9/1/95

Depth of M.P. (ft): 4'

Monitoring Point: R2-MPA-4

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/17/95 16:30	0.0	20.90	0.50	1.80
8/17/95 16:50	0.3	20.90	0.50	1.80
8/17/95 17:10	0.7	20.50	0.70	1.70
8/17/95 17:30	1.0	19.80	0.90	1.70
8/17/95 19:30	3.0	18.80	1.10	1.70
8/18/95 6:40	14.2	15.00	7.50	1.50
8/18/95 16:30	24.0	11.80	9.60	1.30
8/18/95 21:00	28.5	8.70	10.10	1.30
8/19/95 1:10	32.7	6.80	11.10	1.20
8/19/95 12:45	44.3	5.90	14.30	1.00
8/20/95 13:15	68.8	5.80	16.20	0.80



Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.2646	0.2582
Intercept	19.3091	1.4885
Determination Coef.	0.8578	0.9222
No. of Data Points.	11	11

## O<sub>2</sub> Utilization Rate

K <sub>0</sub>	0.004 %/min
	0.265 %/hr
	6.350 %/day

# In Situ Respiration Test

Date: 9/1/95

Site Name: SS010 - Robins AFB


Monitoring Point: R2-MPB-4

Depth of M.P. (ft): 4'

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/17/95 16:30	0.0	20.90	0.50	1.80
8/17/95 16:50	0.3	20.70	0.50	1.60
8/17/95 17:10	0.7	20.00	0.80	1.60
8/17/95 17:30	1.0	19.50	0.90	1.60
8/17/95 19:30	3.0	18.60	0.90	1.50
8/18/95 6:40	14.2	17.40	1.60	1.50
8/18/95 16:30	24.0	12.10	5.10	1.40
8/18/95 21:00	28.5	10.50	6.80	1.40
8/19/95 1:10	32.7	9.80	8.70	1.20
8/19/95 12:45	44.3	9.50	9.40	1.10
8/20/95 13:15	68.8	9.20	9.90	0.90

## O<sub>2</sub> Utilization Rate

K<sub>0</sub> 0.003 %/min  
0.201 %/hr  
4.834 %/day



Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.2014	0.1647
Intercept	19.2701	0.8461
Determination Coef.	0.8208	0.8865
No. of Data Points.	11	11

# In Situ Respiration Test


Site Name: SS010 - Robins AFB

Depth of M.P. (ft): 4'

Date: 9/1/95

Monitoring Point: R2-MPC-4

Date/Time (mm/dd/yr hr:min)	Time (hr)	Oxygen (%)	Carbon Dioxide (%)	Helium (%)
8/17/95 16:30	0.0	20.90	0.50	1.90
8/17/95 16:50	0.3	20.70	0.50	1.80
8/17/95 17:10	0.7	20.70	0.50	1.80
8/17/95 17:30	1.0	20.40	0.50	1.50
8/17/95 19:30	3.0	20.20	0.90	1.50
8/18/95 6:40	14.2	14.10	6.20	1.40
8/18/95 16:30	24.0	9.10	7.60	1.30
8/18/95 21:00	28.5	7.00	8.50	1.10
8/19/95 1:10	32.7	6.40	8.70	1.10
8/19/95 12:45	44.3	6.20	9.50	0.80
8/20/95 13:15	68.8	6.00	10.20	0.70



Regression Lines	O <sub>2</sub>	CO <sub>2</sub>
Slope	-0.2733	0.1706
Intercept	19.1899	1.5012
Determination Coef.	0.8002	0.8224
No. of Data Points.	11	11

## O<sub>2</sub> Utilization Rate

K <sub>0</sub>	0.005 %/min
	0.273 %/hr
	6.558 %/day